The Park Ogbourne St George TPO

(T1) Horse Chestnut (see photographs)

Prescription – To reduce the crown surface area by 20/25% or to a suitable growth point clear of any decay. Approximate reduction 6-8m

(T2) Horse Chestnut

Prescription – To reduce the crown surface area as above to continue the line/height of the reduction through in order to deflect any strong prevailing winds.

(T3) Horse Chestnut

Prescription – To monolith the tree down to approximately 8m or suitable growth point free of decay. This tree has significant decay in several areas of the bole and has recently failed and lost one large limb (see photographs)

(T4) Horse Chestnut

Prescription – To significantly reduce the weight of the limbs on the field side of the tree by carrying out an overall crown reduction along the same line as T1 and T2 (see photograph) 20/25% overall reduction 6-8m.

(T5) Ash – ADB

Prescription – To carry out a crown reduction down to a suitable monolith point just above a large cavity which is a potential nesting/habitat site.

(T6) Horse Chestnut

Prescription – To re-pollard the tree back to, or just below, the previous pollard points as the majority of the weight from the crown is now within striking distance of the road below.

The road is well used by both vehicles and pedestrians, the prescription also applies to (T7) which is adjacent.

(T7) Horse chestnut

Prescription – Please see above.

(T8) Horse Chestnut

Prescription – To remove one heavy limb which is likely to fail and damage the younger understory planting.

The limb will be reduced back to balance the bole to the height of the already damaged limb at the fork.

Note: All proposed tree works are to reduce the risk of failure/causing injuries to staff/members of the public and damage to property and vehicles and not cosmetic reasons.