N

0m 10m 20m 30m 40m

Scale 1:500

New perimeter fence to connect into existing

3m high with razor wire topping perimeter fence with gravel margin at base

Area to be graded to suitable falls and re-seeded to grass

Gravel margin to perimeter of vehicle store.

Open sided covered vehicle store. Cladding, gutters and RWP's to be Olive Green

Existing hardstanding to be retained as far as possible. New kerbs to perimeter

336 Panel PV Array to southern facing roof

Electrical distribution cabinet

New perimeter fence to connect into existing

Ingleton Wood LLP shall have no liability to the Employer arising out of any unauthorized modification or amendment to, or any transmission, copy or use of the material, or any proprietary work contained therein, by the Employer, Other Project Team Member, or any other third party.

All dimensions are to be checked and verified on-site by the Main Contractor prior to commencement; any discrepancies are to be reported to the Contract Administrator.

This drawing is to be read in conjunction with all other relevant drawings and specifications

Do Not Scale

© Ingleton Wood LLP

Rev	Description	Date	Chk	Apr
P01	PLANNING ISSUE	14/08/23	HW	BB

Project No: 4000027 | Scale @ A3: 1:500 | Drawn By: DJ

Security Classification: OFFICIAL

Project: NEW BUILT MT STORAGE FACILITY IMBER LINES

Client: VIVO DEFENCE SERVICES

Title: PROPOSED SITE PLAN

Drawing Number: 4000027 - IWD - Z0 - 00 - DR - A - 2002

Status: S2 | Purpose of Issue: Information | Revision: P01

Ingleton Wood

Property and Construction Consultants

Issuing office: Nottingham
T: 0115 8654072
www.ingletonwood.co.uk

Vision, form and function