Scottish & Southern Electricity Networks

CONHOLT LANE

SSEN to lay 300 XLPE in open trench.
Lay & blind.
-
Customer to excavate and reinstate trench.

SSEN to HV straight joint onto the existing underground HV cable. Diversion to avoid new extension.
-
Customer to excavate joint hole required 2 x 1.

HV cable highlighted green is to be made redundant.

SSEN: TO INSTALL THIRD WIRE HV TO UPRATE TO THREE PHASE.

SSEN: TO CHANGE POLE TO A H STOUT TERMINAL POLE AND ERECT A 200kVA 3 PHASE PMT.
-
SSEN: TO ERECT 2 x STAY WIRES.

SUBJECT TO WAYLEAVES & LEGALS.
THIRD PARTY LAND.

We reserve the right to amend the charges at any time after the date of this offer as a result of variations to material or labour costs which will impact upon the costs incurred by us in providing the connection. This offer is made on the basis of a desktop study of the site, subsequent site investigations may require design changes which result in additional charges.

Middle Conholt

Middle Conholt Farm

Tank

Track

Job Ref: FAE428
Design Review & Verification Completed

Scottish & Southern Electricity Networks

Name:	Martyn Moore-Cresswell	**Drawing No:**	1
Date:	09/08/2023	**Version**	2

Address: MIDDLE CONHOLT, CONHOLT LANE, CONHOLT, WILTSHIRE, SP11 9HD

Quotation subject to wayleaves and third party consents as well as post acceptance site survey

---------- :-	HV	HV Cable
---------- :-	LV	Mains Cable
---------- :-	LV	Service Cable
========== :-	150	sqmm Black Poly Duct

Customer to carry out all onsite excavation / reinstatement and traffic management

SSEPD to carry out all off site excavation / reinstatement and traffic management

WARNING

There may have been subsequent alterations to the surface levels. Trial holes must be taken to determine positions and depths of cables. HS (G) 47 Booklet from the Health and Safety Executive - Avoiding Danger from Buried Cables - should be consulted before commencing excavation work. WHEN WORKING IN THE VICINITY OF OVERHEAD LINES THE HEALTH AND SAFETY GUIDANCE NOTE GS6 SHOULD BE CONSULTED (AVAILABLE FROM THE HSE WEBSITE)

Map Centre: 432724, 155276		Grid Ref: SU32725527
Scale: 1:1250	Page Size: A3	Plot Date: 09/06/2023
Designer Name: Moore-Cresswell, Martyn		Job Number: FAE428/1

UNCONTROLLED COPY
Subject to revision
Master held by SSEN Asset Data Team - Asset.Data@sse.com

If you are unsure & need to seek advice before commencing excavations please contact;

General Enquiries	0800 048 3516

NORMAL DEPTH TO THE TOP OF THE CABLE WHEN LAID

	Services	LV	HV	EHV
FOOTPATH/UNMADE	0.45m	0.45m	0.6m	0.8m
ROAD CROSSING	0.6m	0.6m	0.75m	0.9m
AGRICULTURAL	1m	1m	1m	1.1m

Legend