Proposed Works and Materials:

Walls: All existing render to replaced with lime render

Pitched Roof:

- Roof to be repaired like for like
- Roofing membrane to be replaced and re-tiled
- Lead flashing on all chimneys to be replaced
- Flashing on existing dormer to be repaired
- Existing valley lining to be replaced with fibreglass lining

Flat roof: Existing flat roof to be repaired with Marine ply base + fibreglass roofing membrane



Proposed North Elevation
Scale 1:50



Proposed South Elevation
Scale 1:50



Arkiplan
74 Cardiff Road, CF15 7QE • Enquiries@ArkiPlan.co.uk

Site	Lindens, 74 High Street, Heytsbury, Warminster BA12 OED	Date	28.09.2023
		Sheet	23-0901 D11 REV 2
		Job	Internal Alterations
		Scale	As Shown@A1
Title Number	WT254853	Title	As Shown