[redacted]

Gordon Greenwood

11 Canadian Avenue• Salisbury, Wilts SP2 7JL

[redacted]

Mr. J Richardson
Wiltshire Council
Planning Department

03-10-2023

PL/2023/07198

Good Morning Joe
Just to confirm a few aspects and materials relating to the above application.
As you are aware the Original Builder made such a poor job, that the Building Inspector condemned the whole build, this including the roof whole structure.
This left Miss Western with no choice but to reassess the whole project, and this involved the new design.

As the whole roof is being replaced, Karren asked if it were possible to have Natural Slate instead of the concrete tiles at present.
So: -

Materials for the project will be,

1. Dormer walls will be insulated studwork with ply sheathing, there will be wood-grain" composite" cladding.
2. Roof will have natural slate, with roof Insulated.
3. Flat roof to Dormer will be Insulated single ply membrane.
4. Pvcu Facia Boards and Gutters
5. White Pvcu windows and doors.

Gordon

[redacted]