INNER LINING SKIN INSULATED 140MM TIMBER STUD WALL.
REFLECTIVE BREATHER THEN 9MM OSB3 , THEN 140x38MM TREATED TIMBER CARCASSING
FILLED WITH 140MM WOOD FIBBE INSULATION. 25MM SERVICE VOID THEN 52.5MM THERMAL LAMINATE BOARD.

INTERNAL100MM TIMBER STUD PARTIONS, MINERAL WOOL ACOUSTIC INSULATION.

13063 mm
2875 mm
6540 mm
2875 mm
3901 mm
1600 mm
750 mm

4813 mm
1000 mm
3165 mm
2388 mm

1200 mm
3000 mm
2965 mm

BEDROOM 1
LIVING / KITCHEN AREA
BEDROOM 2
POCKET DOOR
POCKET DOOR
POCKET DOOR
DOORS FIXED SHUT AS EXTERNAL CLADDING INSULATED LINING BEHIND

TO EXISTING CHAMBER

900 mm
1400 mm
1790 mm
1800 mm
5902 mm
1180 mm
2080 mm
1180 mm
1025 mm

EXISTING DOORS FITTED WITH DOUBLE GLAZED PAINTED TIMBER UNITS
EXISTING WINDOWS REPLACED WITH DOUBLE GLAZED PAINTED TIMBER UNITS

PROPOSED GF PLAN

0 1 5
METRES 1:50 @ A1

EXISTING ENTRANCE RENEWED WITH STONE EDGINGS AND COBBLE PAVERS TO EXISTING GAS POSITION
WALL HEIGHT APPROX 300MM ABOVE GROUND LEVEL
APPROX 6000 MM

N

B4040 LUCKINGTON - SHERSTON ROAD

HEAT PUMP POSITION

PROPOSED SITE PLAN

0 1 10
METRES 1:200 @ A1

architecture

ANDREW JARVIS :: ANGEL FARM, LUCKINGTON ROAD, SHERSTON, WILTSHIRE, SN16 0QA :: MAY 9, 2023