Caveat:

PLEASE NOTE
- Excavation, reinstatement and traffic management are an estimate only and maybe subject to change during the detailed design stage post acceptance.
- Any additional costs will be passed onto the client.
-- Quotation is based on existing 95ABC spans being 4 wire. If 95ABC needs replacing from 3 wire to 4 wire a requote will be required.

SSEN to re-configure 5 spans of 4 wire 95ABC from single phase to three phase.

SSEN to install uprate existing single phase 50kVA PMT to 100kVA three phase PMT on a new tall H stout intermediate pole.
-
HV shutdown and cards required.

SSEN to uprate 2 spans of 50ABC to 95ABC 4 wire.

SSEN to install new LV intermediate pole due to the distance and weight of new 95ABC.
-
SSEN to replace existing LV poles to sustain new 95ABC spans.

We reserve the right to amend the charges at any time after the date of this offer as a result of variations to material or labour costs which will impact upon the costs incurred by us in providing the connection. This offer is made on the basis of a desktop study of the site, subsequent site investigations may require design changes which result in additional charges.

WARNING

There may have been subsequent alterations to the surface levels. Trial holes must be taken to determine positions and depths of cables. HS (G) 47 Booklet from the Health and Safety Executive - Avoiding Danger from Buried Cables - should be consulted before commencing excavation work. WHEN WORKING IN THE VICINITY OF OVERHEAD LINES THE HEALTH AND SAFETY GUIDANCE NOTE GS6 SHOULD BE CONSULTED (AVAILABLE FROM THE HSE WEBSITE)

Map Centre: 409599, 189646		Grid Ref: SU09598964
Scale: 1:1000	Page Size: A3	Plot Date: 14/09/2023
Designer Name: Moore-Cresswell, Martyn (Distribution)		Job Number: FAA857/3

UNCONTROLLED COPY
Subject to revision
Master held by SSEN Asset Data Team - Asset.Data@sse.com

If you are unsure & need to seek advice before commencing excavations please contact;

General Enquiries	0800 048 3516

NORMAL DEPTH TO THE TOP OF THE CABLE WHEN LAID

	Services	LV	HV	EHV
FOOTPATH/UNMADE	0.45m	0.45m	0.6m	0.8m
ROAD CROSSING	0.6m	0.6m	0.75m	0.9m
AGRICULTURAL	1m	1m	1m	1.1m

Legend