KEY

External wall finish
(A1) Vertical sweet chestnut boarding to match ancillary building. Timber lengths vary. 10mm gaps should be maintained between all vertical timber elements
Refer to drawing 252_GA_142

(B) External windows and doors
(B1) Double glazed Polyester Powder Coated (PPC) aluminium casement windows with PPC aluminium cills and trickle vents
(B2) Hit and miss cladding across openings within timber fence to match existing ancillary building
(B3) External door D01 Double glazed Polyester Powder Coated (PPC) aluminium casement door with side light
(B4) Velux standard roof light, frame & surround colour: black to match roof

(C) Services and utilities
(C1) Mechanical extract vent to AWC
(C2) Incoming services at high level from existing ancillary building (power, data, recycled and potable water, waste and foul drainage) to be integrated within timber fence

(D) Fences
(D1) sweet chestnut boarding to match ancillary building. Timber lengths vary. 10mm gaps should be maintained between all vertical timber elements
Refer to drawing 252_GA_142
(D2) Fence posts, as required

(E) Timber decking
(E1) Timber decking to raise level of ground to adjacent pavement to provide level access

(F) Access
(F1) Pedestrian access to temporary space through temporary courtyard
(F2) Pedestrian access for staff to existing ancillary building

(G) Landscaping
(G1) All weather safe play surface to be level with surrounding finishes: 300mm of top soil to be excavated and reinstated on removal of temporary facilities
(G2) Perimeter bench to support fences (D) please refer to drawing 252_AD_801_Proposed Courtyard Fence and Bench Sections

(H) Way finding
(H1) Vertical sign for temporary education space fixed to timber cladding

Tarmac road surface
Paved surface
Ancillary Building
Section B-B
102.75
(D1)
(F1)
(F2)
(B3)
(G2)
Entrance lobby
6 sqm
Bag storage cage 900 x 600 x 1320
Bag storage cage 900 x 600 x 1320
Bag storage cage 900 x 600 x 1320
ramp up
Storage
Proposed Temporary Education Space
105 sqm
(E1)
(G1)
Proposed Temporary External Courtyard
Inspection Chamber
Storage
6 sqm
Section A-A
AWC
3.3 sqm
AWC
3.3 sqm
(B1)
(C2)
Section A-A
252_AD_801
(D1)
(G2)
Section B-B
252_AD_801
Grounds Store
(B1) (B1) (B1) (B1) (B1)
12000
(F2)
102.75
102.25
102.50
102.25
102.0
101.75
101.75
101.50

AOC
AOC Architecture Ltd
38-50 Pritchards Road London E2 9AP
t. +44 20 7739 9950 f. +44 870 458 1877
studio@theAOC.co.uk www.theaoc.co.uk

0 1 2 3 4 5m

DO NOT SCALE FROM THIS DRAWING.
ALL DIMENSIONS IN MILLIMETRES & TO BE CHECKED ON SITE.
COPYRIGHT RESERVED.

World Heritage boundary

Rev.	Status	Date	Drawn	Checked
L	Record	17.04.23	BM	GS
K	PLANNING	24.02.21	BM	GS
J	Information	10.02.21	BM	GS
I	Information	05.02.21	BM	GS
H	Information	29.01.21	BM	GS
G	Information	19.01.21	BM	GS
F	Information	15.01.21	BM	GS
E	Information	21.12.20	BM	GS
D	PLANNING	02.12.20	BM	GS
C	Information	27.11.20	BM	GS
B	Information	25.11.20	BM	GS
A	Information	11.11.20	BM	GS

Project
252
Temporary Facilities
Stonehenge Visitor Centre

Stonehenge, Salisbury, SP4 7DE

Dwg title
PROPOSED
Ground Floor Plan

Dwg no. 252_GA_120
Rev. L
Scale 1:100 @ A3