FINISHES SCHEDULE
27 Home Ground, Royal Wootton Bassett, Swindon SN4 8NB

FASCIAS & VERGES

Verges and fascias to be stripped back, cleaned, ready for new clip-on pvc-u verge and fascia panels from Direct Plastics Ltd – existing colour mahogany/rosewood



DORMER CLADDING

Cladding to dormer units to be from the Neo Timber Deluxe range – To match fascias and verges as closely as possible



GUTTERS & DOWNPIPES

Gutters and downpipes to be replaced with new black deep flow gutters and 70mm dia. downpipes to client's specification.- black



STAIN FINISH TO EXISTING TIMBER CANOPIES

Canopy frameworks, fascias and all exposed timbers – existing colour mahogany



