GENERAL NOTES:
This drawing is to be read in conjunction with all other relevant disciplines drawings, schedules, specifications and supporting information. The contractor is to verify all dimensions and conditions on site. This drawing should not be scaled. Only figured dimensions are to be followed. Any discrepancies are to be reported to New Enclosure and resolution sought prior to proceeding. This drawing is subject to copyright www.newenclosure.com



N

SCALE BAR
5m 25m

PLANT SCHEDULE

Single species native hedge

	Qty	Dsty	Specification
Fagus sylvatica	387	#	C 3L or BR; 60-90cm
Taxus baccata		3/m	C 5L+ or RB; 90-120cm

Low lavender 'hedge'

Lavendula angustifolia	168	4/m^2	C 3L; 20-30cm

Native hedgerow

Acer campestre (20%)	65	*	BR; 40-60cm
Corylus avellana (20%)	65	*	BR; 40-60cm
Crateagus monogyna (40%)	130	*	BR; 40-60cm
Prunus spinosa (20%)	65	*	BR; 40-60cm

Trees

Acer campestre	4	-	BR, C, or RB; 10-12cm girth; 3.0-3.5m
Corylus avellana 'Purpurea'	3	-	BR, C, or RB; 10-12cm girth; 3.0-3.5m
Fagus sylvatica 'Purpurea'	1	-	RB; 12-14cm girth; 3.5-4.0m
Quercus robur	1		RB; 12-14cm girth; 3.5-4.0m

Shrubs

Cornus Sanguinea 'Midwinter Fire'	10	1m^2	C 3-5L; 40-60cm
Viburnum davidii	66	3/m	C 3L; 20-40cm

Seeding

Marginal wildflower	180m^2	4g/m^2	Emorsgate EM8 Wetland Mix

Hazel scrub

Corylus avellana +	300	0.5/m^2	BR; 90-120cm

Single species native hedge (beech) to be planted at ~4 plants per linear metre except hedge D (see 394_PN_02) which is to be planted in double staggered rows 600mm apart at 500mm centres.

* Native hedgerow planting to be in double staggered rows 600mm apart at 500mm centres; plant in random groups of 5-12 whips of the same species. All whips to be protected with biodegradable spiral wound shrub guards, or 150mm diameter shrub guards. Plants to be supported by a cane/stake driven ~300mm into the base of the pit.

+ Hazel scrub: All whips to be protected with biodegradable spiral wound shrub guards, or 150mm diameter shrub guards. Plants to be supported by a cane/stake driven ~300mm into the base of the pit.

Default Specification for Protective Barrier



Specification for Above Ground Stabilised Protective Barrier



TREE PROTECTION

A suitably qualified arboriculturalist will be appointed to ensure the safeguarding of trees. To include the liaison with Council tree officer and others on the design and construction team throughout the course of implementation. A watching brief during erection of tree protection measures will be required.

See details to the right for further information on tree protection fencing.

NEW ENCLOSURE
LANDSCAPE CONSULTANTS

specialists in the creation of spaces for **people + nature**

T 07868603026 E richard@newenclosure.com W newenclosure.com
A Old Fire Station, Salt Lane, Salisbury, SP1 1DU

EXISTING TREES
INCLUDES WOODED AREA TO THE NORTH OF SITE FOR CONTEXT; DASHED RED LINE DENOTES TREE PROTECTION

EXISTING HEDGEROW

PROPOSED TREE
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

PROPOSED NATIVE HEDGEROW
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

PROPOSED NATIVE WHIP PLANTING
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

PROPOSED NATIVE HEDGE
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

PROPOSED PLANTING
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

PROPOSED AMENITY GRASS
TURFED OR SEEDED; RETAIN EXISTING WHERE ABLE

PROPOSED MEADOW
YELLOW HATCH DENOTES CONTINUED MANAGEMENT OF EXISTING CHALK GRASSLAND/MEADOW; PURPLE HATCH DENOTES MARGINAL WILDFLOWER.
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

PROPOSED HAZEL AND GRASSLAND SCRUB AREAS
WHITE CROSS (HIGH DENSITY DOTS) HATCH DENOTES AREA TO BE MANAGED AS HAZEL SCRUB; WHITE GRASS (LOWER DENSITY DOTS) HATCH DENOTES AREA TO MANAGED FOR ESTABLISHMENT OF GRASSLAND SCRUB.
SEE PLANTING PLANS, AND PLANT SCHEDULE AND SPECIFICATION FOR DETAIL

EXISTING / PROPOSED GRAVEL
E.G. LOCALLY SOURCED MEDIUM SIZE FRACTION ANGULAR LIMESTONE GRAVEL WITHIN GROUND STABILISATION SYSTEM AS REQUIRED. 'MAKING GOOD' OF EXISTING GROUND E.G. FOR ACCESS TRACK WITH SAME OR SIMILAR MATERIAL I.E. HARDCORE IS ACCEPTABLE

PROPOSED HARDSTANDING
E.G. LOCALLY SOURCED SELF-BINDING LIMESTONE GRAVEL/HARDCORE

PROPOSED PAVING
TO MATCH STONE USED FOR BUILDING. E.G. WARM-BUFF LIMESTONE. SMALL FORMAT FLAGS AND/OR SETTS FOR THRESHOLDS; LARGE FORMAT PAVING FOR PATIO AREAS

PROPOSED BOUNDARIES / ENCLOSURE
BLUE LINE DENOTES PRIVACY SCREENS: TIMBER TO MATCH HOLIDAY LET CLADDING; 1.8m HIGH, WITH GRADUAL STEP DOWN TO 1.2m HIGH MOVING AWAY FROM THE BUILDINGS.
BLUE BOXED LINES DENOTES STONE WALL: TO MATCH BUILDING STONE WALL, 1.8m HIGH
FIELD GATES TO BE 5 BAR AGRICULTURAL TIMBER GATE; GATES TO PROPOSED DWELLING TO BE E.G. 'WINDSOR-STYLE' DOUBLE LEAF TIMBER GATE

PROPOSED EXTERNAL LIGHTING
E.G. COLLINGWOOD IROKO 95 LUMEN TIMBER DOWN LIGHT LIGHTING BOLLARD; 1m HIGH X 95mm^2

REV	DESC	DATE	BY	CHK
E	Bin store information added	2023-11-08	RC	RC
-	First Issue	2023-09-08	RC	RC

PROJECT
Hill View Farm

CLIENT
Trudy Exell

DRAWING TITLE
Landscape Plan

DRAWING NO.	REV	STATUS	SCALE
394_PN_01	E	PLANNING	1:250 AO