LEGEND - KERB TYPES

HB2	HALF BATTERED KERB (TYPE HB2: 125mm UPSTAND)
TE	TIMBER EDGING KERB (TYPE TE: 125mm UPSTAND / LAID FLUSH)
BNF	BULLNOSED KERB (TYPE BN: LAID FLUSH)
BN 6mm	BULLNOSED KERB (TYPE BN: 6mm UPSTAND)
BN 25mm	BULLNOSED KERB (TYPE BN: 25mm UPSTAND)
CS2	CHANNEL SQUARE KERB (TYPE CS2: LAID FLUSH)
EF	FLAT TOP EDGING KERB (TYPE EF: LAID FLUSH)
TK	TRANSITION KERB (TYPE TL/TR: UPSTAND KERB TO DROPPED KERB)
DK	DROPPER KERB (TYPE DL/DR: UPSTAND KERB TO DROPPED KERB)

POROUS ASPHALT:

TYPE A1: ASPHALT PAVING CONSTRUCTION -
- PEDESTRIAN LOADING ONLY

TYPE A1 (P): POROUS ASPHALT PAVING CONSTRUCTION -
- PEDESTRIAN LOADING ONLY
- INFILTRATION INTO GROUND

TYPE A1 (P2): POROUS ASPHALT PAVING CONSTRUCTION -
- PEDESTRIAN LOADING ONLY
- TANKED

TYPE A1 (P3): POROUS ASPHALT PAVING CONSTRUCTION -
- PEDESTRIAN LOADING ONLY
- DEPTH OF SUB BASE TO MATCH ADJACENT CAR PARK

TYPE A3 (P): POROUS ASPHALT PAVING CONSTRUCTION -
- CARS, LIGHT VEHICLES AND OCCASIONAL HGV'S

TYPE A3 (P2): POROUS ASPHALT PAVING CONSTRUCTION -
- CARS, LIGHT VEHICLES AND OCCASIONAL HGV'S

TYPE CWA3- TPZ(P): CELLWEB ON PROPOSED SURFACE -
- TREE PROTECTION ZONE
- CARS, LIGHT VEHICLES AND OCCASIONAL HGV'S

TYPE C1: CONCRETE SLAB FOR BIN STORE / ASHP

G: GRAVEL

REFER TO DRAWING 18665-HYD-00-ZZ-DR-C-7300 FOR DETAILS

LEGEND - LEVELS AND GRADIENTS

+ 00.000	PROPOSED SPOT LEVEL
+ (00.00)	EXISTING SPOT LEVEL
1:100	PROPOSED GRADIENT
(1:100)	EXISTING GRADIENT

1:200 @ A1
1:400 @ A3
0 2 4 6 8 10 12 m



KEY PLAN

NOTES

1. All dimensions are to be checked on site before the commencement of works. Any discrepancies are to be reported to the Architect & Engineer for verification. Figured dimensions only are to be taken from this drawing.
2. The DWG file is issued for the purposes of coordination only and do not represent formal drawing issue and are not to be reprinted in any form. Formal issue of drawings is via DWF, Adobe PDF files and/or hard copies and their associated information issue sheets.
3. Note that all care has been taken with the export of DWG files and their content, but we recommend that you make due dimensional checks before using any DWG file information. Any errors found are to be reported to Hydrock immediately.
4. All levels are shown in metres above Ordnance Datum (m AOD).
5. In the event of any contradiction between this drawing and the specification, then the contractor shall seek clarification from the engineer before proceeding.
6. Refer to landscape architects drawings for extent of external surfaces and kerbing.
7. The landscape architect / architect is responsible for providing setting out of the proposed site layout.
8. The works on site affect statutory undertakers apparatus, where the contractor is required to verify the location and depth of all such apparatus prior to commencement of work and to take any precautions necessary when working in the vicinity of apparatus.

NOTE A
Proposed spot levels have been determined from tie in levels provided by Brunel Surveys 19911-200-01 dated Oct 2018. The contractor is responsible for the coordination of the off-site tie in levels and to advise Hydrock of any variations/discrepancies

NOTE B
Prior to commencement of remediation/overlay works the contractor is to undertake a full service/utilities scan to establish details of existing utilities in the vicinity of the works. The contractor is responsible for the co-ordination/alterations of such utilities with the proposed works.

REV	DRAWN BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE
C13	SCALE BAR ADDED. B.MURPHY	07/12/23	J.MAGEE	07/12/23	J.MAGEE	07/12/23
C12	UPDATED TO ADDRESS SURFACING/ KERB COMMENTS B.MURPHY	28/11/23	B.MURPHY	28/11/23	J.MAGEE	28/11/23
C11	TIMBER EDGING REVISED TO CONCRETE AS PER BEARD MARK UP. PLAY AREA / PV AREA EXTENT UPDATED. SENSORY GARDEN SURFACING ADDED. ACCESS TIE IN LEVELS PROVIDED. C.HOPKINSON	22/11/23	B.MURPHY	22/11/23	J.MAGEE	22/11/23
C10	UPDATED TO ADDRESS CONTRACTOR / ARCHITECT COMMENTS. ISSUED FOR CONSTRUCTION. B.MURPHY	15/09/23	J.MAGEE	15/09/23	J.MAGEE	15/09/23
C09	REVISED TO SUIT DESIGN SCOPE CHANGES. B.MURPHY	07/09/23	J.MAGEE	07/09/23	J.MAGEE	07/09/23
C08	MINOR UPDATE TO EXISTING LEVELS IN FRONT OF HOUSE. COURTYARD CONCRETE ADDED. O.LAINCHBURY	16/05/23	B.MURPHY	16/05/23	J.MAGEE	16/05/23
C07	UPDATED SITE PLAN AND ADDED CONCRETE SLAB TO AIR SOURCE HEAT PUMP O.LAINCHBURY	17/03/23	B.MURPHY	17/03/23	J.MAGEE	17/03/23
C06	FOOTPATH KERB UPDATED. CARPARK CUT BACK TO PARKING BAYS, LEVELS ADJUSTED TO SUIT. O.LAINCHBURY	23/01/23	B.MURPHY	23/01/23	J.MAGEE	23/01/23
C05	AS BUILT LEVELS OF CAR PARK INTRODUCED, SURROUNDING LEVELS ADJUSTED TO ACCOUNT. O.LAINCHBURY	28/11/22	B.MURPHY	28/11/22	J.MAGEE	28/11/22
C04	PROW SPECIFIED AS A1. ACCESS ROAD LEVELS ADJUSTED TO ENSURE 125MM UPSTAND. NORTHERN KERB HB2/TE - TBC BY BEARD, DEPENDANT ON TPZ. O.LAINCHBURY	21/10/22	B.MURPHY	21/10/22	J.MAGEE	21/10/22

Hydrock
Merchants' House North
Wapping Road
Bristol
BS1 4RW
t: +44 (0)117 945 9225
e: bristolcentral@hydrock.com

CLIENT
WILTSHIRE COUNCIL

PROJECT
MELKSHAM HOUSE

TITLE
EXTERNAL WORKS

HYDROCK PROJECT NO.	SCALE @ A1
C-18665-C	1:200

STATUS DESCRIPTION	STATUS
SUITABLE FOR CONSTRUCTION	A5

DRAWING NO. (PROJECT-CODE-ORGINATOR-ZONE-LEVEL-TYPE-ROLE-NUMBER)	REVISION
18665-HYD-00-ZZ-DR-C-7200	C13