I have reviewed the information submitted under Condition 16 on behalf of the council's drainage team.

Although we now agree that the discharge rates are in accordance with the Council's betterment policy (as shown in the table below), we cannot currently discharge the condition as the MADD Factor within calculations has been set to 20m3/ha; our informative on Condition 16 stated that this should be set to 0m3/ha so as to prevent any overestimation of attenuation volume.
We therefore request that calculations are re-run with the correct MADD factor, and results provided back to us, before we can discharge the condition.

	GREENFIELD RATE WITH 20% BETTERMENT	DISCHARGE NETWORK 1	DISCHARGE NETWORK 2	TOTAL PROPOSED DISCHARGE
1 Year	**8.72**	6	1.6	**7.6**
30 Year	**23.28**	6	1.6	**7.6**
100 Year	**32.8**	6	1.9	**7.9**

Kind Regards

Ben Wilding *MEng (Hons) CEng MICE*
Principal Civil Engineer