T2 - Flowering Cherry Crown lift over road to provide 5.0m ground level clearance.

T4 - Ash Remove Sycamore at base of trunk.

T6 - Turkey Oak Climbing inspection with report of topping area. Oak will have a 2m crown reduction as well as survey recommendations

T7 - Flowering Cherry Crown lift over road to provide 5.0m ground level clearance. Prune clear of street lamp.

T8 - Ash Remove major deadwood if considered necessary otherwise leave for habitat.

T9 - Common Ash, Yew, Elder, Holly Sever Ivy

T11 - Rowan Formative prune to improve form and shape of tree and provide separation from building. Lift over driveway to provide 3.0m ground clearance.

T24 - Beech Manage new growth at topped point within 2 years.

T25 - Purple Beech Crown lift to provide 5.0m ground level clearance over road.

T26 - Ash Crown lift to provide 5.0m ground level clearance over road.

T27 - Sycamore Crown lift to provide 5.0m ground level clearance over road.

GRP1 - Portuguese Laurel x 16 Trim lower growth over road to provide 5.0m ground level clearance.

GRP1a - Cherry, Laurel, Yew Trim and crown lift over road to provide 5.0m ground level clearance as required.