

KEY DIAGRAM WITH FIELD NUMBERS.

N

Existing paved surface under bridge

A4 Bridge

Maximum slope gradient of 1:4

Rowden Mile 3m wide cycle route, finished with buff coloured macadam surfacing with Heras fencing 2m beyond

Bramble and other scrub to be cleared

Existing Public Right of Way CHIP 1

Gateway sculpture

Approximate area of regrading to achieve maximum 1:21 cycle path gradient

FIELD 2

Field maintained as existing

Maximum slope gradient of 1:4

FOR CONTINUATION PLEASE SEE 416.00404.00048.29.017

Existing Public Right of Way upgraded to a 2m cyclepath linking Chippenham to Lackham College

Bramble and other scrub to be cleared

Pond/drainage ditch

2m wide footway / cycleway with Temporary Herras fencing 2m beyond

Bramble and other scrub to be cleared

FIELD 4

Field maintained as existing

FOR CONTINUATION PLEASE SEE 416.00404.00048.29.021

0 5 10 15 20m 30 40 50
Metres 1:500

LEGEND

- SITE BOUNDARY
- RIVERSIDE PARK BOUNDARY
- EXISTING PUBLIC RIGHT OF WAY
- EXISTING TRACK
- PROPOSED FOOT/CYCLE WAY (NOTE 3)
- PROPOSED ROWDEN MILE (NOTE 3)
- PROPOSED INFORMAL GRASS PATH
- EXISTING WOODLAND / HEDGES / TREE GROUPS
- PROPOSED WOODLAND
- EXISTING TREE AND HEDGE TO BE RETAINED AND ROOT PROTECTION AREA (IN RED)
- PROPOSED TREE
- PROPOSED HEDGE PLANTING
- TEMPORARY LOCATION OF HERRAS FENCING DURING CONSTRUCTION
- VEGETATION TO BE REMOVED
- EXISTING WATER BODY
- EXISTING SCRUB
- PROPOSED NATIVE SCRUB PLANTING
- PROPOSED ORNAMENTAL PLANTING
- PROPOSED AMENITY GRASS
- PROPOSED WILDFLOWER SEEDING
- PROPOSED MEADOW
- PROPOSED WET MEADOW
- PROPOSED MARGINAL / AQUATIC PLANTING
- PROPOSED BULB PLANTING
- PROPOSED BRIDGE
- PROPOSED BICYCLE STAND
- PROPOSED SEAT
- PROPOSED PICNIC BENCH
- PROPOSED DOG WASTE BIN
- PROPOSED HIBERNACULA
- PROPOSED COMPOST HEAPS
- PROPOSED BEETLE WOOD PILES
- PROPOSED INTERPRETATION BOARD
- PROPOSED SCULPTURE LOCATION

Notes:
1. Numbers on trees, hedges and groups are in the arboricultural survey.
Refer to Treeworks Arboriculture Impact Report for tree and hedgerow protective fencing.
2. Landscape subject to future reserved matters applications.
3. Surfaced with buff coloured self binding material in accordance with SUSTRANS guidance and engineers specification for path construction; timber board edging except for Rowden Mile which shall have 50x150mm PCC Kerb edging.

12	CK	CK	23.02.24	SECTION OF ROWDEN MILE SURFACING UPDATED
11	CK	CK	12.10.23	PATH ALIGNMENT UPDATED, AS PER CLIENT COMMENTS
10	CK	CK	09.10.23	PATH ALIGNMENT AND SURFACING UPDATED, AS PER CLIENT COMMENTS
9	LA	JJ	20.11.18	NOTE AMENDED & OS LICENCE UPDATED
8	LA	JJ	12.11.18	HATCH ADDED TO ROWDEN MILE. LEGEND UPDATED
7	LA	CM	02.08.18	RIVERSIDE PARK BOUNDARY ADDED. WERM UTILITIES UPDATED
6	LA	CM	25.06.18	TREES ADDED TO FIELD BOUNDARIES
5	AH	CM	05.04.18	LIFEBUOY REMOVED FROM KEY, GRAPHICS CHANGED FOR REGRADING OF CYCLE PATH
4	LA/RH	CM	09.11.17	FOOTCYCLEWAY ALONG PATTERDOWN RD ADJUSTED BRIDGE NOTES UPDATED. VIS SPLAY AND BOARDWALK ADDED
3	LA/RH	CM	20.10.17	MARK UP COMMENTS
2	LA	CM	21.09.17	TEXT AMENDMENTS
1	LA	CM	11.09.17	CUT LINES ADJUSTED

3RD FLOOR
THE BREW HOUSE
JACOB STREET
BRISTOL, BS2 0EQ

T: 01179 064280
www.slrconsulting.com

ROWDEN PARK, CHIPPENHAM

STRATEGIC HARD AND SOFT LANDSCAPE PROPOSALS FIELDS 2 & 4

416.00404.00048.29.018.12

Scale: 1:500@A1
Date: AUGUST 2017

416.00404.00048.29.017-038.05-13_STRATEGIC HARD SOFT LANDSCAPE PLAN_23-02-2024-RHL.dwg

Contains OS data © Crown copyright [and database rights] 0100031673.

© This drawing and its content are the copyright of SLR Consulting Ltd and may not be reproduced or amended except by prior written permission. SLR Consulting Ltd accepts no liability for any amendments made by other persons.