Please refer to drawings 5416:1000–1003 & 5416:1050–1053 for Parcel B2a/B2b Infrastructure Levels, drainage and longitudinal section information.

PARCEL B2b
INDICATIVE WIP

F10
E=411558.925
N=132254.224
Ht=106.037

Please refer to drawings 5416:76 for Parcel B2 Infiltration Pond 3 levels & details.

Please refer to drawings 5416:1100 for Parcel B2 POS Levels.

LEAP
20m x 20m

Please refer to drawings 5416:1000–1003 & 5416:1050–1053 for Parcel B2a/B2b Infrastructure Levels, drainage and longitudinal section information.

PHB3 ROAD 2
PHB4 ROAD 1
PHB4 ROAD 1A
ACCESS ROAD 1A
ACCESS ROAD 1A

Limit of Phase B4 Works

Drawing Notes:

1. This drawing is based on the latest architectural planning layout supplied by Persimmon Homes, together with all other relevant drawings series connected to this parcel including documents and specifications, including and developer house type information.
2. Any discrepancies should be reported to MJA Consulting.
3. Do not scale from this drawing.
4. All levels relate to Ordnance Datum; all dimensions in metres unless otherwise specified. Site survey grid & co-ordinates to be checked on site prior to commencement of any works.
5. The level & location of all existing services shall be verified and marked on site by the Contractor prior to commencing any construction works.
6. All highway works should be built to an adoptable standard and carried out in accordance with the MCHW Specification for Highway Works and the requirements of the Local Highway Authority.
7. All adoptable foul & surface manholes, pipework and associated structures shall be constructed in accordance with current form of Sewers for Adoption latest 'Design & Construction Guidance (DCG)' and to Wessex Water's Water Authority specification and Addendum.
   All adoptable pipework up to DN225 shall be Extra Strength Vitrified Clay, DN300 or above shall be concrete. All adoptable pipes to be Strength Class 120. If the contractor wishes to use structural wall plastic pipe, then approval must be gained from the Adopting Water Authority.
8. All highway drainage and associated structures to be constructed in accordance with Sewers Adoption guidance and any relevant specification issued by the Local Highway Authority.
9. All surface water sewers which are not to be adopted as public sewers under a Section 104 agreement, shall be constructed using TwinWall pipes up to DN600 unless agreed otherwise by the developer. Pipes >DN600 shall be concrete material.
10. Engineering layouts show below ground drainage only. All soil pipes, stub stacks, WC outlets and rainwater downpipe locations are indicative only. Details should be cross checked against latest development Architect's drawings to ensure compatibility. All stub stacks to be fitted with air admittance valve where branch drain exceeds 12m, except head of run. Lintels or sleeves to be used for passing through foundation brickwork.
11. Rainwater downpipes to be connected directly to drains via removable adaptor to permit access for rodding.
12. All foul & storm water building drainage not offered for adoption shall be constructed using clay, uPVC or structural wall plastic pipework laid in accordance with manufacturer's specification, Building Regulations Part H, BS EN 752 and to NHBC Standards.
13. Building drainage. Foul drainage to be DN100 laid at a minimum gradient of 1 in 40 where serving less than 1 WC, 1 in 80 otherwise or as specified. Minimum gradient for surface water to be 1 in 80 or as specified.
    Minimum depth of cover to unprotected gravity pipework should be:
    - Domestic gardens without vehicle access – 0.6m
    - Domestic driveways and parking courts – 0.9m
    - All access roads and main parking areas – 1.2m
14. Private inspection chambers shall be non-access structural wall plastic. Chamber sizes to accord with manufacturers specifications, Building Regulations Part H, BS EN 752 and to NHBC Standards.
15. Sewers of different diameters to be laid soffit to soffit.
16. All gully connections other than at manholes to be 'Y' junctions
17. All finished floor levels shown are for guidance only and may need to be adjusted on site where required. However, any amendments or deviation are subject to Engineer's approval. Levels shown within rear gardens are indicative only and subject to landscaping proposals.
18. Requirement for raised DPC / Tanking as follows (refer to Persimmon Homes/Charles Church detail drawings numbered SOCO–GD–TF–DPC–01 & S4GD–ACC–02):
    - Standard DPC where ground level is 150mm below FFL
    - Raised DPC where external ground level is between –150 & level with FFL
    - Where ground level is above the FFL then tanking will be required, specified by structural engineer.
19. Position of driveway or parking area gullies and manholes are nominal and should be adjusted to suit, linear drains to be installed where private areas fall towards adjacent to public highway. All covers and gully grates to be suitable for vehicle loading.
20. All drainage chambers to be inspected and runs to be flushed through to remove any building material and debris prior to final tests by Building Inspector.
21. All private garden areas to be prepared in accordance with NHBC regulations 10.2.9 and Landscape Architects requirements. Old foundations, concrete bases and similar obstructions removed from within 450mm of the finished surface. Subsoil decompaction, such as rotavating, to a minimum depth of 300mm and topsoil cultivation to the full depth of compaction.

© This drawing is the copyright of Michael A Jennings Associates Limited and may not be copied, altered or reproduced in any way without their permission.

KEY:

Adoptable Sewers:
- Proposed Foul sewer
- Foul sewer Installed as per 5416 Infrastructure Design
- Foul Backdrop

Private Drainage:
- Storm sewer
- Storm Gully
- Storm Backdrop
- Foul drain

Internal private foul connections shown indicatively. Awaiting working house sub-structures.
- Storm drain
- Rodding eye
- Yard gully
- Aco drain (ACO DRAIN)
- PCC 900x450 Gully

*Aquacell Soakaway (Aquacell)

*All soakaways to extend a min. 300mm into chalk strata.
Where chalk cannot be encountered below 3.0m, contractor to contact engineer for solution.

All private inspection chambers shall be polypropylene non-access chambers in accordance with The Building Regulations, Part H.

Chamber sizes:
Depth to invert <0.6m DN300
Depth to invert >0.6m DN475

Invert levels shown thus: F10.00 S10.00

Refer to note 14 regarding building drainage sizes and gradients

Externals:
- Existing Levels
- Proposed Carriageway Levels
- Proposed External Plot & Parking Levels
- Finished floor levels shown thus: FFL 10.00
- All driveways to be set 10mm lower than finished level abutting garages entrances for water check purposes.
- Fall Arrows
- Proposed Road Contours
- Flush Access
- Stepped Access
- Pedestrian Crossing (PC)
- Dropped Kerb – Pedestrian Access (DK)
- Exposed Brickwork (EXT BWK)
- Tanking (T-T-T-T-T-T-T-)
- Slab on Edge (SOE SOE)

Refer to architects working details

For areas where the external ground levels are above, flush with, or less than 150mm below finished floor levels refer to Persimmon Homes /Charles Church detail drawings numbered SOCO–GD–TF–DPC–01 & S4GD–ACC–02 for DPC details

In accordance with Part–M of the Building Regulations – Every flight of steps with three or more risers (approach to primary access point to have a suitable grippable handrail on one side of the flight (or both sides where the flight is wider than 1000mm). This grippable handrail is 850–1000mm above the pitch line of the flight and extends at least 300mm beyond the top and bottom nosings.

Retaining Walls
- RWALL – To structural engineers details
- CGB – Concrete Gravel Board

Air Source Heat Pump (ASHP)

STREET LIGHTING

On–site parcel lighting indicative. Awaiting external consultants lighting design.


WHITE LINING SCHEDULE

LINE No	REFERENCE No	MARK	GAP	WIDTH	DESCRIPTION
WL1	1003	600	300	200	Give Way Markings
WL2	1009	600	300	100	Edge of carriageway
WL3	1004	4000	2000	100	Lane Markings
WL4	1023	1250x3750			Give Way Triangle Marking
WL5	1062	–	–	–	Hump Marking

PAVING SCHEDULE

No	BRAND OR SIMILAR APPROVED	LENGTH	WIDTH	COLOUR	DESCRIPTION
P1	MARSHALLS	400	400	Buff	Tactile blister paving
P2	MARSHALLS	400	400	Buff	Hazard warning tactile paving – raised ribs.

SHEET KEY



REV. No.	DATE	DESCRIPTION	DRAWN	CHECKED
T3	16.01.24	Plots 910,915–920,921–926,927–932,973–981,1041–1046 & 1065–1073 substructure and foul drainage points updated. Plots 973–981 car parking arrangement revised to suit the HV cable. Street lighting updated to latest Proelectric proposals.	LJW	KTG
T2	28.11.23	Private drainage and plot levels updated following MJA and client value engineering exercise.	LJW	KTG
T1	06.10.23	Tender Issue.	LJW	KTG

Client: PERSIMMON HOMES (North Coast) LTD

Project: Fugglestone Red Phase B3 & B4, Salisbury, Wiltshire

Title: Engineering Layout Sheet 3

MJA CONSULTING
CIVIL & STRUCTURAL ENGINEERS
Ipsum Court, 24 The Quadrant,
Abingdon Science Park, Abingdon
Oxon, OX14 3YS
Tel: 01235 555173
Email: mail@mjaconsulting.co.uk

Scale: 1:250@A0 | Status: TENDER

Drawn:	Project Engineer	MJA Project No:	Date:
AMc	AMc	6741	July '23

Drawing Number: 6741–MJA–SW–XX–DR–C–003 | Rev: T2