FLOOR	ELEVATION	REFERENCE	OPENING TYPE	PROPOSED WINDOW / DOOR TYPE
BASEMENT	WEYMOUTH STREET	WD-B-1	AS EXISTING	REPLACEMENT METAL SASH BEHIND GRILLS
		WD-B-2	AS EXISTING	REPLACEMENT METAL SASH BEHIND GRILLS
		WD-B-3	AS EXISTING	EXISTING BEER DROP DOOR RETAINED
	COURTYARD EAST	WD-B-4	RE-OPEN	NEW TIMBER BOX SASH
GROUND	WEYMOUTH STREET	WD-G-1	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-G-2	AS EXISTING	EXISTING TIMBER DOOR
		WD-G-3	AS EXISTING	NEW TIMBER DOOR AND FANLIGHT
		WD-G-4	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-G-5	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-G-6	AS EXISTING	EXISTING TIMBER DOOR
	COURTYARD EAST	WD-G-7	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-G-8	RE-FORM	NEW TIMBER BOX SASH
		WD-G-9	RE-FORM	NEW TIMBER BOX SASH
		WD-G-10	RE-FORM	NEW TIMBER BOX SASH
		WD-G-11	AS EXISTING	NEW TIMBER DOOR
		WD-G-12 - A	AS EXISTING	NEW TIMBER BOX SASH
	COURTYARD WEST	WD-G-12 - B	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-G-13	AS EXISTING	NEW TIMBER DOOR
		WD-G-14	AS EXISTING	NEW FIXED WINDOW
		WD-G-15	AS EXISTING	NEW FIXED WINDOW
		WD-G-16	REDUCE	NEW DOOR
		WD-G-17	AS EXISTING	NEW GLAZED SCREEN
		WD-G-18	ENLARGE	NEW CASEMENT WINDOW
		WD-G-19	ENLARGE	NEW CASEMENT WINDOW
	REAR SOUTH	WD-G-20	ENLARGE	NEW CASEMENT WINDOW
		WD-G-21	AS EXISTING	NEW TIMBER / GLAZED SCREEN
FIRST	WEYMOUTH STREET	WD-F-1	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-2	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-3	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-4	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-5	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-6	AS EXISTING	EXISTING TIMBER BOX SASH
	COURTYARD EAST	WD-F-7	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-8	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-9	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-10	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-F-11	AS EXISTING	EXISTING TIMBER BOX SASH
	COURTYARD WEST	WD-F-12	RE-OPEN	NEW CASEMENT WINDOW
		WD-F-13	AS EXISTING	EXISTING CASEMENT WINDOW
		WD-F-14	NEW	NEW CASEMENT WINDOW
		WD-F-15	AS EXISTING	NEW CASEMENT WINDOW
	REAR SOUTH	WD-F-16	AS EXISTING	NEW CASEMENT WINDOW
	REAR EAST	WD-F-17	AS EXISTING	NEW CASEMENT WINDOW
	REAR NORTH	WD-F-18	AS EXISTING	NEW CASEMENT WINDOW
SECOND	WEYMOUTH STREET	WD-S-1	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-2	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-3	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-4	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-5	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-6	AS EXISTING	EXISTING TIMBER BOX SASH
	COURTYARD EAST	WD-S-7	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-8	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-9	AS EXISTING	EXISTING TIMBER BOX SASH
		WD-S-10	AS EXISTING	REPLACEMENT TIMBER BOX SASH
		WD-S-11	AS EXISTING	EXISTING FIXED WINDOW
		WD-S-12	AS EXISTING	REPLACEMENT TIMBER BOX SASH
ROOF	COURTYARD EAST	WD-R-1	NEW	CONSERVATION STYLE ROOF WINDOW

Rev	Note		By	Date
Scale:	NTS	**Size:**	@A3	
Date:	24.09.24	**Status:**	PLANNING	
Drawn:	IMA	**Checked:**	-	
Job No:	978	**Dwg/Rev:**	19	
Title:	Proposed Window and External Door Schedule			
Project:	The John Barleycorn 3 Weymouth Street Warminster			
Client:	Robert Selwood Ltd			

DHA ARCHITECTS
33 Powell Street •Birmingham •B1 3DH •
Tel: 0121 200 2638 • Fax: 0121 236 8356•
e-mail: design@dhaa.co.uk•