



- Statutory approvals to be received prior to commencement of works. - Building control submission to be deposited prior to any works. - Check / trace positions of existing services / drainage prior to new works. - Ensure no Easements / rights of way exist on site prior to construction. - Check dimensions on site against site survey prior to any new works. - Report and resolve any discrepancies prior to any new building works. - Relevant Party Wall notices to be served and agreed before new works. - CDM Co-ordinator to be appointed with Health & Safety file in place prior to any new works.			
Revision:	Date:	Description:	By:

Play Area

Sports Court

Recreation Ground

Wall Material Key:

	Natural Stone
	Brickwork - Stock red
	Through colour roughcast render - Colour ivory

To be read in conjunction with house type elevations.
All brickwork below DPC is to be Red brick.

All contrasting brick architectural dressings to be in the same brick.

Client:



Drawn By:



Site Address:
LAND OFF BIDDESTONE LANE
YATTON KEYNELL

Drawing Title:
SITE LAYOUT & WALL MATERIALS

Scale: 1:500	Date drawn: MARCH 2025	Drawn by: BT
-----------------	---------------------------	-----------------

Project Number: 948	Drawing Number: 104	Revision: -
------------------------	------------------------	----------------

Status: **PLANNING**

0 10m 50m

A1