

1
20-01

EAST ELEVATION AS PROPOSED
1:50

01. Existing soil vent pipe removed.

02. Eaves detail changed to accommodate roof insulation as drawing 1254-P40-03 and gutter is replaced in CI to larger section to cope with increased rainfall patterns.

03. Ridge height raised by 140mm on elevation to accommodate insulation as drawing 1254-P40-03.

04. Existing roof lights removed.

05. New lead flashings to brick chimneys.

06. Existing render cornice retained and repaired.

07. Spalling Roman Cement plinth rendered in Roman Stucco to match existing

08. Spalling Roman Cement buttress weatherings and render to be replaced in Roman Stucco render to match existing lined render.

09. Spalled Roman Cement hood moulds and window head render replaced in 'Roman Stucco' render to match existing with new stainless steel armature dowels.

10. 80mm downpipes replaced in new 100mm cast iron to cope with increased rainfall patterns.

11. Roman Cement render figurative carvings conserved in-situ.

12. Spalling Roman Cement merlon and embrasure crenellations to porch replaced in Roman Stucco to match existing.

13. -

14. Existing spalled, hollow and poorly patched Roman Cement render to be replaced with lined Roman Stucco render (subject to full assessment from scaffold). Render to be colour-matched to unify appearance.

15. Porch door and fanlight repaired and redecorated

16. Vegetation cut back to allow for scaffolding and re-rendering.

17. Chimney heads re-flaunched (assume all chimney pointing renewed in lime mortar).

18. Existing clay tile roofing renewed in matching clay tile with new over-rafters, thermal insulation and counter battens, breather membrane and battens.

19. Roof light location moved to align with space and trusses beneath. New conservation roof light flush with tile pitch.

Rev	Date	Purpose of issue	By
A	04/07/2024	Stone hood moulds omitted and render notes amended	HM
B	05/12/2024	Roman Cement notes 8 and 14 clarified	DJ

PLANNING

All drawings are copyright of DHV architects and shall not be reproduced without the consent of the designers.

0 2.5m

Studios 12-13, 9 Bath Buildings, Bristol, BS6 5PT
E info@dhva.co.uk W www.dhva.co.uk T 0117 914 5317

dittrichhudsonvasettiarchitects

Job Title	Leaden Hall Renovations				Drg Title	Leaden Hall Proposed East Elevation	
Client	Salisbury Cathedral						
Scale	1:50@A1	Drawn	DJ	Checked	IH	Job No 1254	Drg No P20-01	Rev B