

www.frystonework.co.uk



39 Caretakers Close

Melksham, Wilts.

SN12 8FR

📞 Yell.com Business Listing. (Fry Stonework) &
Google business listing.



<https://www.frystonework.co.uk>

jeremy@frystonework.co.uk

TO

Claire Vines

45 London Road

Chippenham, Wiltshire.

SN15



ESTIMATE

DATE

TOTAL

EST0391

28/09/2025

GBP

DESCRIPTION	RATE	QTY	AMOUNT
Dear Clare, thank you for choosing Frystonework to quote for your building project @ the above address. I have prepared the quote to cover the work discussed . Brief description of works , 1. Remove shrubs from garden area directly behind stone wall , roots from these are part of the reason the wall is bowing out significantly towards public footpath & in my professional opinion is a definite safety issue for anyone in this vicinity. 2. Remove existing wall & copings & save anything that can be reused 3. Excavate new foundations , soiled section of garden behind retaining wall to allow for 9" flat concrete block wall to be built with drainage weep holes to stop any excess water building up behind new wall. Stainless steel ties placed in wall to tie in the front elevation of stone with lime mortar. 4. Put existing copings on providing there in good order. Quote does not include making good/ rebuilding any of the neighbours wall should deemed unsafe whilst work is carried out on Clare's wall. I'm happy to take on board any requests / info from any parties involved with this building project.		1	

Thank you for choosing Frystonework to quote for your building project. Any questions, please don't hesitate to contact me.

Many thanks
Jeremy Fry.
MD.

£0.00 1 £0.00

TOTAL GBP