

NOTES:

1. THE CONTRACTOR IS TO DETERMINE THE LOCATION AND STATUS OF ANY UTILITY APPARATUS PRIOR TO THE COMMENCEMENT OF ANY WORKS.
2. DRAWING TO BE READ IN CONJUNCTION WITH DRAWINGS:

- D-0151: DRAINAGE CULVERT LONG SECTION.

- D-0155: DRAINAGE CONSTRUCTION DETAILS.
3. CONTRACTOR MUST COMPLY WITH THE NRSWA 1991 FOR TRAFFIC MANAGEMENT AND FOR ANY ROAD WORKS WITHIN THE HIGHWAY. OXFORDSHIRE COUNTY COUNCIL STREETWORKS DEPARTMENT SHOULD BE CONSULTED FOR DETAILS OF RESTRICTED WORKING TIMES/PERIODS, THIS MAY BE IN ADDITION TO ANY RESTRICTIONS STATED IN PLANNING CONDITION.
4. PROPOSED ADOPTABLE HIGHWAY DRAINS ARE ONLY PERMITTED TO HAVE OTHER DRAINS/GULLY CONNECTIONS AND OTHER SERVICES LAID AT AN ANGLE OF BETWEEN 45° AND 90° ACROSS THE LINE WITH A VERTICAL CLEARANCE IN EXCESS OF 300mm.
5. THE CONTRACTOR IS TO DETERMINE THE LOCATION AND STATUS OF ANY UTILITY APPARATUS PRIOR TO THE COMMENCEMENT OF ANY WORKS.
6. CONTRACTOR TO UNDERTAKE A SURVEY OF ALL EXISTING SEWER NETWORKS AND REPORT TO THE ENGINEER. ANY CONNECTED NETWORKS NOT IDENTIFIED MUST BE REPORTED TO THE ENGINEER FOR CONSIDERATION.

7. SURFACE WATER DRAINS GREATER THAN 225mmØ SHALL BE HIGH STRENGTH CONCRETE, ALL OTHER DRAINS SHALL BE VITRIFIED CLAY TO BS EN 295-1 UNLESS OTHERWISE INDICATED.
8. TO BE READ IN CONJUNCTION WITH SPECIFICATION FOR HIGHWAY WORKS (SHW) SERIES 500 DRAINAGE AND SERVICE DUCTS.
9. EXISTING DRAINAGE APPARATUS RETAINED TO BE JETTED, CLEARED OF DEBRIS AND DEFECTS IDENTIFIED AND REPLACED.
10. WHERE IT IS PROPOSED TO MAKE USE OF EXISTING DRAINAGE, THE CONTRACTOR SHALL CONFIRM THE SUITABILITY AND CONDITION OF THE EXISTING DRAIN / CONNECTION TO THE ENGINEER.

KEY

REFER TO DRAWING NUMBER: 38342-HYD-XX-XX-DR-D-0155 FOR STANDARD DETAILS.

- G29

NEW GULLY AND CONNECTION. 450mm x 900mm INTERNAL DIMENSION WITH 150mm DIA CONNECTION. UPVC (HDPE) PIPE CONNECTION. REFER TO DRAWING D-0155 FOR PIPE BEDDING. REFER TO WCC DRAWING GULLY TYPE A DETAILS, REF: WC-SHCD-0500-D001

NEW SURFACE WATER CULVERT CONCRETE PIPE REFER TO DRAWING NUMBER D-0155 FOR PIPE BEDDING DETAILS.

NEW HEADWALL. REFER TO HEADWALL SCHEDULE IN 38342-HYD-XX-XX-DR-D-0155.

NEW PRIMARY CONTOURS (0.100m INTERVALS).

NEW SECONDARY CONTOURS (0.020m INTERVALS).

EXISTING PRIMARY CONTOURS (0.100m INTERVALS).

EXISTING SECONDARY CONTOURS (0.020m INTERVALS).
- 
-