




Main Access ramp requirements for M4 Compliance Classifications			
	M4 Classification		
Ramp Gradient	M4(1)	M4(2)	M4(3)
1:12	≤5m	≤2m	N/A
1:15	≤10m	≤5m	≤5m
1:20	∞	≤10m	≤10m
Stepped Approach	Acceptable (Where step free access unachievable due to site gradient)	N/A	N/A

Table 1: Maximum ramp flight lengths

Health & Safety Note :

Refer to standard detail drawings 100 to 108 for additional health & safety notes

The sub-contractor should be familiar with the contents of the geo-environmental reports and protect against any risks that arise.

The sub-contractor is responsible for obtaining copies of service and drainage record plans and taking all care to ensure that existing services are protected or disconnected

All waste material should be placed in appropriate skips or removed from site to avoid trip hazards

- The following items require method statements:-
- Any excavations including safe access and support
- Working in confined spaces
- Working in or adjacent to the public highway
- Working in or connecting to live sewers
- Working near live or overhead services
- Protection to trees and landscaping
- Handling & erection of all steelwork, precast concrete units & pad stones & any units greater than 20kg in weight.
- Protection from risk of fall into all excavations and from exposed faces (including floor slabs) where changes in level where falls could cause an injury

First Issue

16.01.26 AJH

DATE INITIA



Newland
HOMES

Stones Farm, Cricklade Phase 2

Finished Levels Layout Sheet 1

1:250 @ A1

Scale —

247 - 143 - 1

Drawing No

AJH
Dress

16/01/2026

16/01/2026
First issue

—

Revision