

Then Now When

Conservation + Architecture + Sustainability

Materials Schedule

First Issue : 12th February 2026

Ansty Manor, Ansty, Wiltshire

Written by:

jc

Checked by:

ALS

Planning Information Request

This materials schedule is produced to follow the request contained with the pre-application advice from the LPA. For the ease of making a potential planning amendment application in the future, we would welcome a condition that includes reference to this document within any permission or consent issued.

Materials Schedule

Spine Walls and Coping Stones

Ashar limestone, to match that used within the existing spine wall for the existing garden room. Both the original non-weathered, and weathered states, are shown within the photo below. It is taken from within the link to the existing garden room.



Roof

Copper roof surface and soffit, in section to match those of the existing garden room's roof. The weathered state is shown in the photo below.



Mortar Pointing

Off white lime-based mortar with 3 parts washed sand, 1 part sharp sand and 1 part 2.0 NHL lime



Roof and Link Glazing

Set into a stainless steel channel within the surrounding stone walling



Flashings

Code 4 or 5 lead, set into existing mortar joints (rather than routing out stonework)



Fenestration

Thin framed panels, dark bronze colour to match the fenestration within the existing garden room.

