

LEGEND - KERB TYPES

HB2

HALF BATTERED KERB (TYPE HB2: 125mm UPSTAND)

EK

EDEN KERB (TYPE EK: 125mm UPSTAND)

BN 6mm

BULLNOSED KERB (TYPE BN: 6mm UPSTAND)

IHB

INVERTED KERB (TYPE IHB: LAID FLUSH)

CS2

CHANNEL SQUARE KERB (TYPE CS2: LAID FLUSH)

EF

FLAT TOP EDGING KERB (TYPE EF: LAID FLUSH)

DK

DROPPER KERB (TYPE DLDR: UPSTAND KERB TO DROPPED KERB)

LEGEND - SURFACE TYPES

TARMAC:

TYPE OVA2: ASPHALT OVERLAY ON EXISTING ASPHALT -
• CARS, LIGHT VEHICLES, NO COMMERCIAL VEHICLES

TYPE A1(B): BUFF ASPHALT PAVING CONSTRUCTION -
• PEDESTRIAN LOADING ONLY

TYPE A2: ASPHALT PAVING CONSTRUCTION -
• CARS, LIGHT VEHICLES, NO COMMERCIAL VEHICLES

TYPE A2(B): BUFF ASPHALT PAVING CONSTRUCTION -
• CARS, LIGHT VEHICLES, NO COMMERCIAL VEHICLES

TYPE A3: ASPHALT PAVING CONSTRUCTION -
• CARS, LIGHT VEHICLES & OCCASIONAL HGV'S

TYPE A3(B): BUFF ASPHALT PAVING CONSTRUCTION -
• CARS, LIGHT VEHICLES & OCCASIONAL HGV'S

TYPE P-B1: BLOCK PAVING CONSTRUCTION -
• PEDESTRIAN LOADING ONLY

TYPE P-B2: BLOCK PAVING CONSTRUCTION -
• CARS, LIGHT VEHICLES, NO COMMERCIAL VEHICLES

TYPE P-B2(C): BLOCK PAVING CONSTRUCTION (CELLWEB) -
• CARS, LIGHT VEHICLES, NO COMMERCIAL VEHICLES

TYPE P-B3: BLOCK PAVING CONSTRUCTION -
• CARS, LIGHT VEHICLES & OCCASIONAL HGV'S

TYPE P-F1: FLAG PAVING CONSTRUCTION -
• PEDESTRIAN LOADING ONLY

TYPE RB1: RESIN BOUND RUBBER FOOTWAY CONSTRUCTION -
• PEDESTRIAN LOADING ONLY

TYPE HG(C): HOGGING FOOTWAY CONSTRUCTION (CELLWEB)-
• PEDESTRIAN LOADING ONLY

TYPE HG: HOGGING FOOTWAY CONSTRUCTION -
SEE SHEET 2 FOR CONTINUATION

LEGEND - LEVELS AND GRADIENTS

+ 00.000

PROPOSED SPOT LEVEL

+ (00.00)

EXISTING SPOT LEVEL

1:100

PROPOSED GRADIENT

(1:100)

EXISTING GRADIENT

KEY PLAN

NOTES

1. All dimensions are to be checked on site before the commencement of works. Any discrepancies are to be reported to the Architect & Engineer for verification. Figured dimensions only are to be taken from this drawing.

2. The DWG file is issued for the purposes of coordination only and do not represent formal drawing issue and are not to be reprinted in any form. Formal issue of drawings is via DWF, Adobe PDF files and/or hard copies and their associated information issue sheets.

3. Note that all care has been taken with the export of DWG files and their content, but we recommend that you make due dimensional checks before using any DWG file information. Any errors found are to be reported to Hydrock immediately.

4. All levels are shown in metres above Ordnance Datum (m AOD).

5. In the event of any contradiction between this drawing and the specification, then the contractor shall seek clarification from the engineer before proceeding.

6. Refer to landscape architects drawings for extent of external surfaces and kerbing.

7. The landscape architect / architect is responsible for providing setting out of the proposed site layout.

8. The works on site affect statutory undertakers apparatus, where the contractor is required to verify the location and depth of all such apparatus prior to commencement of work and to take any precautions necessary when working in the vicinity of apparatus.

NOTE A

Proposed spot levels have been determined from tie in levels provided by Mendip Land Surveys in 2017.
The contractor is responsible for the coordination of the off-site tie in levels and to advise Hydrock of any variations/discrepancies

NOTE B

Prior to commencement of remediation/overlay works the contractor is to undertake a full service/utilities scan to establish details of existing utilities in the vicinity of the works. The contractor is responsible for the co-ordination/alterations of such utilities with the proposed works.

NOTE C

Level threshold has been assumed around the building footprint. Architect / Landscape Architect to confirm whether there are any requirements for a 150mm step to be introduced from the door thresholds down to external levels.

C02	UPDATED TO LATEST LAYOUT	D.SPARKS	13/02/26	A.TODD	13/02/26	J.MAGEE	13/02/26
C01	UPDATED TO LATEST LAYOUT	K.ARSLAN	07/03/25	A.TODD	07/03/25	A.TODD	07/03/25
P06	UPDATED TO SUIT CONTRACTOR COMMENTS	K.ARSLAN	07/03/25	A.TODD	07/03/25	A.TODD	07/03/25
P05	CLIENT NAME UPDATED	K.ARSLAN	21/01/25	H.MILLER	21/01/25	J.MAGEE	21/01/25
P04	UPDATED TO CONTRACT	K.ARSLAN	17/01/25	A.TODD	17/01/25		
P03	AA - AUTHORISED FOR RIBA STAGE 4	H.MILLER	15/11/24	A.TODD	15/11/24	A.TODD	15/11/24
P02	SCALE BAR ADDED	H.MILLER	10/09/24	J.MAGEE	10/09/24	J.MAGEE	10/09/24
P01	PRELIMINARY ISSUE	J.NEAL-LONG	28/08/24	H.MILLER	28/08/24	A.TODD	28/08/24
REV	REVISION NOTES/COMMENTS	DRAWN BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE

Hydrock

Merchants' House North
Wapping Road
Bristol
BS1 4RW
t: +44 (0)117 945 9225
e: bristolcentral@hydrock.com

CLIENT

ALLIANCE LEISURE

PROJECT

TROWBRIDGE LEISURE CENTRE

TITLE

EXTERNAL WORKS

HYDROCK PROJECT NO.

C-31436-C

SCALE @ A1

1:250

STATUS DESCRIPTION

CONTRACT

DRAWING NO. (PROJECT CODE-ORIGINATOR-ZONE-LEVEL-TYPE-ROLE-NUMBER)

TLC-HYD-00-ZZ-DR-C-7200

STATUS

A4

REVISION

C02