





Proposed Cluster C, Lodges 813- 809:



Proposed Cluster C, Lodges 808 - 804:



Notes:

All works to be carried out in accordance with the current Building Regulations, British Standards and Codes of Practice and to the satisfaction of the Building Control Body. All dimensions are to be checked on site prior to the commencement of the works. Any discrepancies to be reported prior to the commencement of the relevant works. Please note that paper prints of this drawing may not be an accurate reproduction of the given scale.

Site & Cluster Layouts have been produced using 3rd party topographical information. Drawings are shown indicatively and a representation of the existing site and proposed employers' means. The topographical survey does not identify ALL trees referenced in the Assured Tree Survey and locations are approximate. JDA accept no responsibility for its accuracy or omission.

Drawings to be read in conjunction with Core Scope of Works & Typical Patio Layout Drawings.

Each Cluster Layout should be assessed by contractor ahead of commencement of works. Contractor to assess each lodge site scenario to determine if retaining walls, guarding & privacy screens are necessary. All proposed cluster details to show indicatively for pricing purposes. Contractor to confirm on site with client, engineer and arboricultural assessor locations or patios, retaining walls, guarding and privacy screens.

Measurements: Stone pick & make good all levels, Rule topsoil & Seed. Refer to Core Scope of Works.

Refer to the core scope of works for works regarding new and existing block paving entrance paths. Entrance paths not shown on cluster plans but contractor to ensure all new cycle racks have block paving ground them.

Key Site:

- Proposed Patio**
Existing patios are extended using Marshall's Roadbed Paving Flamed paving slabs. Bedded on a 75mm thick semi-dry 1:3 cement and mortar bed and 150mm granular sub-base and laid in a random pattern complete with curved/edge. All edge of patio to have concrete haunching. Any change in level shall be accommodated by re-grading the adjacent ground levels in preference to retaining structures. Re-grading to be at a maximum gradient of 1:3. Re-grading must not raise levels higher than existing ground levels at base of trees. Allow for removal of existing grass growing and include for re-grading the whole patio using a Stone Grey professional paving compound. Joints to be even thick. Include for a 150mm wide pea gravel margin for any new patio / lodge junctions. Pea gravel to a minimum depth of 150mm with geotextile membrane.
- Proposed Block Paving**
Lodge paths shall be jet washed using a rotary pressure washer head. Paths around the entrances are to be extended to fill open areas and encompass additional cycle stands where required. Refer to layout plans for system. Additional paving to be Precast concrete paving 200 x 100 x 50 buff (Longleaf & Woburn Natural (Sherwood & Evesdon) Brindle (Whitfield). Bedded on a 30mm sand/cement bed with 150mm compacted granular sub base. All in accordance with CP standard detail CP21. Include for top soil re-grading of the ground parallel to the edge of all paths to remove any trip hazards where the ground has sunk. Lodge paths to be re-sanded following cleaning. Brush kiln dried sand into all joints. Contractor to check and re-bed any loose joints.
- Proposed Bike Racks**
The number of bike racks brackets should match the lodge accommodation. Contractor shall remove the existing bike racks and retain the gals. Brackets for reuse. The contractor shall survey the lodge and determine/allow for additional brackets where necessary to achieve the number of racks required. Bike racks are shown indicatively on the Cluster plans, which may be subject to on site review. New bike rack shall be provided in accordance with CP standard detail CP21.
- Proposed Barbecue**
Existing brick BBQ structures and base to be removed. New 50mm concrete base required for new BBQ positions. New barbecue built in accordance with standard detail. Supply and install new stainless steel grates and side tables as necessary to fit flush with brickwork. Make allowance to fit new stone benchtop. Refer to Project Autumn standard detail (30)018 102.
- Proposed Outdoor Furniture**
Outdoor Furniture to be supplied by CP. Unpack, installed dispose packaging to all client supplied products.
- Retaining Wall**
Proposed retaining walls to rear of lodges required due to patio extensions being located in close proximity to existing bunds.
- Drainage**
Additional Aco drains to be installed and connected to existing sewage and drainage system.
- Bike Rack**
- Retaining Wall**
- Steps**
- Tactile Paving**
- Aco Drains**



T01	20.02.2024	TENDER ISSUE	AC	MR
Rev	Date	Description	Drawn	Checked

Jackson Design Associates
Lutterworth House, Lutterworth, Leicestershire, LE15 1JY
Telephone: (01423) 843322
Facsimile: (01423) 863555
www.jacksondesign.co.uk

ARCHITECTURE • DESIGN • MANAGEMENT

Project:	Project Autumn Phase 8
Drawing Title:	Proposed Cluster Plan, Phase C Lodges 804 - 813
Project Address:	Longleat Forest, Warminster BA12 7PU
Client:	Center Parcs Ltd.
Drawn:	AC
Checked:	MR
Scale:	1:100 @ A0
Date:	February 2024
Drawing No:	2479-LF-P8-(C)002
Revision:	T01
Issue:	TENEDER ISSUE