

Jubb Consulting Engineers Limited		Page 1
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FEH Rainfall Model	
Return Period (years)	100
FEH Rainfall Version	1999
Site Location	GB 386850 145550 ST 86850 45550
C (1km)	-0.027
D1 (1km)	0.363
D2 (1km)	0.417
D3 (1km)	0.273
E (1km)	0.289
F (1km)	2.484
Maximum Rainfall (mm/hr)	50
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.750
PIMP (%)	100
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.200
Maximum Backdrop Height (m)	1.500
Min Design Depth for Optimisation (m)	1.200
Min Vel for Auto Design only (m/s)	1.00
Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.341	4-8	1.261	8-12	0.072

Total Area Contributing (ha) = 1.673

Total Pipe Volume (m³) = 94.140

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	1.000	0.020	50.0	0.010	4.00	0.0	0.600	o	100	Pipe/Conduit	
1.001	14.185	1.045	13.6	0.010	0.00	0.0	0.600	o	100	Pipe/Conduit	
1.002	17.662	0.220	80.3	0.038	0.00	0.0	0.600	o	225	Pipe/Conduit	
2.000	1.000	0.020	50.0	0.010	4.00	0.0	0.600	o	100	Pipe/Conduit	
2.001	6.793	1.255	5.4	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	4.02	138.270	0.010	0.0	0.0	0.0	1.09	8.6	1.4
1.001	50.00	4.13	138.250	0.020	0.0	0.0	0.0	2.11	16.6	2.7
1.002	50.00	4.33	137.080	0.058	0.0	0.0	0.0	1.46	58.1	7.9
2.000	50.00	4.02	138.260	0.010	0.0	0.0	0.0	1.09	8.6	1.4
2.001	50.00	4.05	138.240	0.010	0.0	0.0	0.0	3.35	26.3	1.4

Jubb Consulting Engineers Limited		Page 3
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
8.000	1.000	0.020	50.0	0.013	4.00	0.0	0.600	o	100	Pipe/Conduit	
8.001	5.359	0.445	12.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
6.004	14.513	0.610	23.8	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
9.000	1.000	0.020	50.0	0.013	4.00	0.0	0.600	o	100	Pipe/Conduit	
9.001	6.287	0.530	11.9	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
6.005	16.038	0.450	35.6	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
10.000	1.775	0.040	44.4	0.013	4.00	0.0	0.600	o	100	Pipe/Conduit	
10.001	5.975	0.500	12.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
6.006	5.575	0.160	34.8	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
11.000	1.000	0.020	50.0	0.013	4.00	0.0	0.600	o	100	Pipe/Conduit	
11.001	9.935	0.780	12.7	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
6.007	7.954	0.229	34.7	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
6.008	9.917	1.449	6.8	0.015	0.00	0.0	0.600	o	150	Pipe/Conduit	
1.009	48.885	0.235	208.0	0.056	0.00	0.0	0.600	o	375	Pipe/Conduit	
12.000	1.550	0.030	51.7	0.010	4.00	0.0	0.600	o	100	Pipe/Conduit	
12.001	4.297	0.455	9.4	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
12.002	15.280	0.191	80.0	0.006	0.00	0.0	0.600	o	150	Pipe/Conduit	
13.000	1.000	0.020	50.0	0.019	4.00	0.0	0.600	o	100	Pipe/Conduit	
13.001	6.156	0.711	8.7	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
8.000	50.00	4.02	139.875	0.013	0.0	0.0	0.0	1.09	8.6	1.8
8.001	50.00	4.06	139.855	0.013	0.0	0.0	0.0	2.24	17.6	1.8
6.004	50.00	4.37	139.360	0.080	0.0	0.0	0.0	2.07	36.6	10.8
9.000	50.00	4.02	139.350	0.013	0.0	0.0	0.0	1.09	8.6	1.8
9.001	50.00	4.06	139.330	0.013	0.0	0.0	0.0	2.26	17.7	1.8
6.005	50.00	4.53	138.750	0.093	0.0	0.0	0.0	1.69	29.9	12.6
10.000	50.00	4.03	138.890	0.013	0.0	0.0	0.0	1.16	9.1	1.8
10.001	50.00	4.07	138.850	0.013	0.0	0.0	0.0	2.25	17.7	1.8
6.006	50.00	4.59	138.300	0.106	0.0	0.0	0.0	1.71	30.2	14.4
11.000	50.00	4.02	138.990	0.013	0.0	0.0	0.0	1.09	8.6	1.8
11.001	50.00	4.09	138.970	0.013	0.0	0.0	0.0	2.18	17.1	1.8
6.007	50.00	4.66	138.140	0.119	0.0	0.0	0.0	1.71	30.3	16.1
6.008	50.00	4.71	137.911	0.134	0.0	0.0	0.0	3.88	68.5	18.1
1.009	50.00	5.48	136.237	0.327	0.0	0.0	0.0	1.25	138.3	44.3
12.000	50.00	4.02	138.425	0.010	0.0	0.0	0.0	1.07	8.4	1.4
12.001	50.00	4.05	138.395	0.010	0.0	0.0	0.0	2.53	19.9	1.4
12.002	50.00	4.28	137.890	0.016	0.0	0.0	0.0	1.12	19.9	2.2
13.000	50.00	4.02	138.480	0.019	0.0	0.0	0.0	1.09	8.6	2.6
13.001	50.00	4.05	138.460	0.019	0.0	0.0	0.0	2.64	20.8	2.6

Jubb Consulting Engineers Limited		Page 4
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
12.003	15.299	0.191	80.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
14.000	1.000	0.020	50.0	0.019	4.00	0.0	0.600	o	100	Pipe/Conduit	
14.001	5.138	1.122	4.6	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
12.004	15.953	0.199	80.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
12.005	11.218	0.178	62.9	0.019	0.00	0.0	0.600	o	225	Pipe/Conduit	
15.000	1.000	0.020	50.0	0.012	4.00	0.0	0.600	o	100	Pipe/Conduit	
15.001	6.716	1.619	4.1	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
12.006	15.689	0.249	63.0	0.006	0.00	0.0	0.600	o	225	Pipe/Conduit	
16.000	1.000	0.020	50.0	0.018	4.00	0.0	0.600	o	100	Pipe/Conduit	
16.001	5.829	1.658	3.5	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
12.007	17.988	0.286	62.9	0.060	0.00	0.0	0.600	o	225	Pipe/Conduit	
17.000	1.000	0.020	50.0	0.018	4.00	0.0	0.600	o	100	Pipe/Conduit	
17.001	5.516	1.709	3.2	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
12.008	23.129	0.369	62.7	0.016	0.00	0.0	0.600	o	225	Pipe/Conduit	
18.000	1.000	0.020	50.0	0.011	4.00	0.0	0.600	o	100	Pipe/Conduit	
18.001	6.574	1.963	3.3	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
1.010	10.672	0.024	450.0	0.050	0.00	0.0	0.600	o	600	Pipe/Conduit	
1.011	27.837	0.062	450.0	0.069	0.00	0.0	0.600	o	600	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
12.003	50.00	4.51	137.699	0.035	0.0	0.0	0.0	1.12	19.9	4.7
14.000	50.00	4.02	138.700	0.019	0.0	0.0	0.0	1.09	8.6	2.6
14.001	50.00	4.04	138.680	0.019	0.0	0.0	0.0	3.64	28.6	2.6
12.004	50.00	4.74	137.508	0.054	0.0	0.0	0.0	1.12	19.9	7.3
12.005	50.00	4.85	137.234	0.073	0.0	0.0	0.0	1.65	65.7	9.9
15.000	50.00	4.02	138.820	0.012	0.0	0.0	0.0	1.09	8.6	1.6
15.001	50.00	4.04	138.800	0.012	0.0	0.0	0.0	3.82	30.0	1.6
12.006	50.00	5.01	137.056	0.091	0.0	0.0	0.0	1.65	65.6	12.3
16.000	50.00	4.02	138.610	0.018	0.0	0.0	0.0	1.09	8.6	2.4
16.001	50.00	4.04	138.590	0.018	0.0	0.0	0.0	4.16	32.6	2.4
12.007	50.00	5.19	136.807	0.169	0.0	0.0	0.0	1.65	65.7	22.9
17.000	50.00	4.02	138.375	0.018	0.0	0.0	0.0	1.09	8.6	2.4
17.001	50.00	4.04	138.355	0.018	0.0	0.0	0.0	4.34	34.1	2.4
12.008	50.00	5.43	136.521	0.203	0.0	0.0	0.0	1.65	65.8	27.5
18.000	50.00	4.02	138.260	0.011	0.0	0.0	0.0	1.09	8.6	1.5
18.001	50.00	4.04	138.240	0.011	0.0	0.0	0.0	4.26	33.4	1.5
1.010	50.00	5.63	135.777	0.591	0.0	0.0	0.0	1.14	322.7	80.0
1.011	50.00	6.04	135.753	0.660	0.0	0.0	0.0	1.14	322.7	89.4

Jubb Consulting Engineers Limited		Page 5
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
19.000	1.000	0.020	50.0	0.011	4.00	0.0	0.600	o	100	Pipe/Conduit	
19.001	5.505	0.505	10.9	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
19.002	8.366	0.085	98.4	0.017	0.00	0.0	0.600	o	150	Pipe/Conduit	
20.000	1.000	0.020	50.0	0.010	4.00	0.0	0.600	o	100	Pipe/Conduit	
20.001	5.123	0.690	7.4	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
19.003	10.641	0.108	98.5	0.013	0.00	0.0	0.600	o	150	Pipe/Conduit	
21.000	1.000	0.020	50.0	0.011	4.00	0.0	0.600	o	100	Pipe/Conduit	
21.001	4.539	1.063	4.3	0.003	0.00	0.0	0.600	o	100	Pipe/Conduit	
19.004	8.742	0.090	97.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
22.000	1.000	0.020	50.0	0.012	4.00	0.0	0.600	o	100	Pipe/Conduit	
22.001	5.941	1.503	4.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
19.005	11.645	0.120	97.0	0.003	0.00	0.0	0.600	o	150	Pipe/Conduit	
23.000	1.000	0.020	50.0	0.010	4.00	0.0	0.600	o	100	Pipe/Conduit	
23.001	5.573	1.863	3.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
19.006	17.809	0.183	97.3	0.018	0.00	0.0	0.600	o	150	Pipe/Conduit	
19.007	10.569	0.109	97.1	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
24.000	2.000	0.040	50.0	0.012	4.00	0.0	0.600	o	100	Pipe/Conduit	
24.001	3.210	0.060	53.5	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
24.002	7.966	0.080	99.6	0.010	0.00	0.0	0.600	o	150	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
19.000	50.00	4.02	139.920	0.011	0.0	0.0	0.0	1.09	8.6	1.5
19.001	50.00	4.05	139.900	0.011	0.0	0.0	0.0	2.35	18.5	1.5
19.002	50.00	4.19	139.345	0.028	0.0	0.0	0.0	1.01	17.9	3.8
20.000	50.00	4.02	140.020	0.010	0.0	0.0	0.0	1.09	8.6	1.4
20.001	50.00	4.05	140.000	0.010	0.0	0.0	0.0	2.86	22.4	1.4
19.003	50.00	4.37	139.260	0.051	0.0	0.0	0.0	1.01	17.9	6.9
21.000	50.00	4.02	140.285	0.011	0.0	0.0	0.0	1.09	8.6	1.5
21.001	50.00	4.04	140.265	0.014	0.0	0.0	0.0	3.77	29.6	1.9
19.004	50.00	4.51	139.152	0.065	0.0	0.0	0.0	1.02	18.0	8.8
22.000	50.00	4.02	140.635	0.012	0.0	0.0	0.0	1.09	8.6	1.6
22.001	50.00	4.04	140.615	0.012	0.0	0.0	0.0	3.92	30.8	1.6
19.005	50.00	4.70	139.062	0.080	0.0	0.0	0.0	1.02	18.0	10.8
23.000	50.00	4.02	140.875	0.010	0.0	0.0	0.0	1.09	8.6	1.4
23.001	50.00	4.04	140.855	0.010	0.0	0.0	0.0	4.51	35.4	1.4
19.006	50.00	4.99	138.942	0.108	0.0	0.0	0.0	1.02	18.0	14.6
19.007	50.00	5.16	138.759	0.108	0.0	0.0	0.0	1.02	18.0	14.6
24.000	50.00	4.03	141.275	0.012	0.0	0.0	0.0	1.09	8.6	1.6
24.001	50.00	4.08	141.235	0.012	0.0	0.0	0.0	1.06	8.3	1.6
24.002	50.00	4.21	141.125	0.022	0.0	0.0	0.0	1.01	17.8	3.0

Jubb Consulting Engineers Limited		Page 7
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
30.002	14.939	0.185	80.8	0.004	0.00	0.0	0.600	o	150	Pipe/Conduit	
31.000	1.000	0.020	50.0	0.011	4.00	0.0	0.600	o	100	Pipe/Conduit	
31.001	5.504	0.510	10.8	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
30.003	8.415	0.105	80.0	0.004	0.00	0.0	0.600	o	150	Pipe/Conduit	
30.004	2.616	0.083	31.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
32.000	1.000	0.020	50.0	0.013	4.00	0.0	0.600	o	100	Pipe/Conduit	
32.001	6.676	0.333	20.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
30.005	17.093	0.542	31.5	0.016	0.00	0.0	0.600	o	150	Pipe/Conduit	
33.000	10.000	0.100	100.0	0.027	4.00	0.0	0.600	o	150	Pipe/Conduit	
30.006	22.892	0.870	26.3	0.017	0.00	0.0	0.600	o	225	Pipe/Conduit	
34.000	1.000	0.020	50.0	0.009	4.00	0.0	0.600	o	100	Pipe/Conduit	
34.001	6.997	1.175	6.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
30.007	1.020	0.039	26.2	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
35.000	1.000	0.020	50.0	0.009	4.00	0.0	0.600	o	100	Pipe/Conduit	
35.001	5.500	1.299	4.2	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	
30.008	11.314	0.430	26.3	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
36.000	1.000	0.020	50.0	0.009	4.00	0.0	0.600	o	100	Pipe/Conduit	
36.001	6.997	1.604	4.4	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
30.002	50.00	4.33	141.625	0.026	0.0	0.0	0.0	1.12	19.8	3.5
31.000	50.00	4.02	142.020	0.011	0.0	0.0	0.0	1.09	8.6	1.5
31.001	50.00	4.05	142.000	0.011	0.0	0.0	0.0	2.37	18.6	1.5
30.003	50.00	4.45	141.440	0.041	0.0	0.0	0.0	1.12	19.9	5.6
30.004	50.00	4.48	141.335	0.041	0.0	0.0	0.0	1.80	31.8	5.6
32.000	50.00	4.02	141.655	0.013	0.0	0.0	0.0	1.09	8.6	1.8
32.001	50.00	4.08	141.635	0.013	0.0	0.0	0.0	1.73	13.6	1.8
30.005	50.00	4.64	141.252	0.070	0.0	0.0	0.0	1.80	31.8	9.5
33.000	50.00	4.17	140.810	0.027	0.0	0.0	0.0	1.00	17.8	3.7
30.006	50.00	4.79	140.635	0.114	0.0	0.0	0.0	2.56	101.8	15.4
34.000	50.00	4.02	141.085	0.009	0.0	0.0	0.0	1.09	8.6	1.2
34.001	50.00	4.05	141.065	0.009	0.0	0.0	0.0	3.19	25.1	1.2
30.007	50.00	4.79	139.765	0.123	0.0	0.0	0.0	2.57	102.1	16.7
35.000	50.00	4.02	141.170	0.009	0.0	0.0	0.0	1.09	8.6	1.2
35.001	50.00	4.04	141.150	0.009	0.0	0.0	0.0	3.79	29.7	1.2
30.008	50.00	4.87	139.726	0.132	0.0	0.0	0.0	2.56	101.8	17.9
36.000	50.00	4.02	141.045	0.009	0.0	0.0	0.0	1.09	8.6	1.2
36.001	50.00	4.05	141.025	0.009	0.0	0.0	0.0	3.73	29.3	1.2

Jubb Consulting Engineers Limited		Page 8
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
30.009	2.476	0.094	26.3	0.017	0.00	0.0	0.600	o	225	Pipe/Conduit	🟢
37.000	1.000	0.020	50.0	0.009	4.00	0.0	0.600	o	100	Pipe/Conduit	🟡
37.001	6.100	1.773	3.4	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	🟢
30.010	27.427	1.037	26.4	0.023	0.00	0.0	0.600	o	225	Pipe/Conduit	🟡
19.012	15.382	0.154	99.9	0.005	0.00	0.0	0.600	o	300	Pipe/Conduit	🔴
38.000	1.000	0.020	50.0	0.014	4.00	0.0	0.600	o	100	Pipe/Conduit	🟡
38.001	5.000	1.684	3.0	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	🟢
19.013	25.832	0.258	100.1	0.069	0.00	0.0	0.600	o	300	Pipe/Conduit	🔴
1.012	23.589	0.052	453.6	0.031	0.00	0.0	0.600	o	600	Pipe/Conduit	🔴
1.013	31.370	0.069	454.6	0.058	0.00	0.0	0.600	o	600	Pipe/Conduit	🔴
1.014	6.875	0.015	458.3	0.011	0.00	0.0	0.600	o	600	Pipe/Conduit	🔴
39.000	1.000	0.020	50.0	0.026	4.00	0.0	0.600	o	100	Pipe/Conduit	🟡
39.001	6.100	1.635	3.7	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	🟢
1.015	9.789	0.022	445.0	0.023	0.00	0.0	0.600	o	600	Pipe/Conduit	🔴
40.000	1.000	0.020	50.0	0.016	4.00	0.0	0.600	o	100	Pipe/Conduit	🟡
40.001	5.568	0.825	6.7	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	🟢
41.000	1.000	0.020	50.0	0.012	4.00	0.0	0.600	o	100	Pipe/Conduit	🟡
41.001	4.084	0.635	6.4	0.000	0.00	0.0	0.600	o	100	Pipe/Conduit	🟢

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
30.009	50.00	4.88	139.296	0.158	0.0	0.0	0.0	2.56	101.8	21.4
37.000	50.00	4.02	141.120	0.009	0.0	0.0	0.0	1.09	8.6	1.2
37.001	50.00	4.04	141.100	0.009	0.0	0.0	0.0	4.20	33.0	1.2
30.010	50.00	5.06	139.202	0.190	0.0	0.0	0.0	2.55	101.6	25.7
19.012	50.00	5.85	138.090	0.462	0.0	0.0	0.0	1.57	111.2	62.6
38.000	50.00	4.02	139.840	0.014	0.0	0.0	0.0	1.09	8.6	1.9
38.001	50.00	4.03	139.820	0.014	0.0	0.0	0.0	4.52	35.5	1.9
19.013	50.00	6.12	137.936	0.545	0.0	0.0	0.0	1.57	111.1	73.8
1.012	50.00	6.47	135.691	1.236	0.0	0.0	0.0	1.14	321.4	167.4
1.013	50.00	6.93	135.639	1.294	0.0	0.0	0.0	1.14	321.1	175.2
1.014	50.00	7.03	135.570	1.305	0.0	0.0	0.0	1.13	319.7	176.7
39.000	50.00	4.02	137.710	0.026	0.0	0.0	0.0	1.09	8.6	3.5
39.001	50.00	4.04	137.690	0.026	0.0	0.0	0.0	4.03	31.7	3.5
1.015	50.00	7.17	135.555	1.354	0.0	0.0	0.0	1.15	324.6	183.3
40.000	50.00	4.02	139.370	0.016	0.0	0.0	0.0	1.09	8.6	2.2
40.001	50.00	4.05	139.350	0.016	0.0	0.0	0.0	3.00	23.5	2.2
41.000	50.00	4.02	139.180	0.012	0.0	0.0	0.0	1.09	8.6	1.6
41.001	50.00	4.04	139.160	0.012	0.0	0.0	0.0	3.07	24.1	1.6

Jubb Consulting Engineers Limited								Page 11			
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR				VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC							
Date 15/07/2025				Designed by EPH							
File SWD NETWORK - POND A - 100 YR...				Checked by							
Innovyze				Network 2019.1							
<u>Manhole Schedules for Storm</u>											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam.,L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
DIST TANK	138.865	0.595	Open Manhole	450	1.000	138.270	100				
SIC 206-1	138.865	0.615	Open Manhole	1200	1.001	138.250	100	1.000	138.250	100	
SMH 14	138.805	1.725	Junction		1.002	137.080	225	1.001	137.205	100	
DIST TANK 1	138.865	0.605	Open Manhole	450	2.000	138.260	100				
SIC 207-1	138.940	0.700	Open Manhole	450	2.001	138.240	100	2.000	138.240	100	
JUNCTION	138.705	1.845	Junction		1.003	136.860	225	1.002	136.860	225	
								2.001	136.985	100	
SMH 13	138.735	1.987	Open Manhole	1200	1.004	136.748	300	1.003	136.823	225	
DIST TK 1	139.020	0.700	Open Manhole	450	3.000	138.320	100				
SIC 208-1	139.020	0.720	Open Manhole	450	3.001	138.300	100	3.000	138.300	100	
JUNCTION	138.770	2.055	Junction		1.005	136.715	300	1.004	136.715	300	
								3.001	136.915	100	
DIST TANK 1	139.065	0.600	Open Manhole	450	4.000	138.465	100				
SIC 209-1	139.080	0.635	Open Manhole	450	4.001	138.445	100	4.000	138.445	100	
JUNCTION	138.913	2.307	Junction		1.006	136.606	300	1.005	136.606	300	
								4.001	136.806	100	
DIST TANK 1	139.150	0.600	Open Manhole	450	5.000	138.550	100				
SIC 210-1	139.175	0.645	Open Manhole	450	5.001	138.530	100	5.000	138.530	100	
JUNCTION	139.040	2.537	Junction		1.007	136.503	300	1.006	136.503	300	
								5.001	136.703	100	
SMH 12	139.230	2.844	Open Manhole	1200	1.008	136.386	300	1.007	136.386	300	
DIST TANK	141.980	0.820	Open Manhole	450	6.000	141.160	100				
SIC 188-1	142.115	0.975	Open Manhole	450	6.001	141.140	100	6.000	141.140	100	
SMH 22	141.650	1.350	Open Manhole	1200	6.002	140.300	150	6.001	140.350	100	
DIST TANK	141.220	0.825	Open Manhole	450	7.000	140.395	100				
SIC 187-1	141.300	0.925	Open Manhole	450	7.001	140.375	100	7.000	140.375	100	
JUNCTION	141.105	1.295	Junction		6.003	139.810	150	6.002	139.810	150	
								7.001	139.860	100	
DIST TANK	140.755	0.880	Open Manhole	450	8.000	139.875	100				
SIC 186-1	140.865	1.010	Open Manhole	450	8.001	139.855	100	8.000	139.855	100	
JUNCTION	140.690	1.330	Junction		6.004	139.360	150	6.003	139.360	150	
								8.001	139.410	100	
DIST TANK	140.255	0.905	Open Manhole	450	9.000	139.350	100				
SIC 185-1	140.300	0.970	Open Manhole	450	9.001	139.330	100	9.000	139.330	100	
SMH 21	140.100	1.350	Open Manhole	1200	6.005	138.750	150	6.004	138.750	150	
								9.001	138.800	100	
DIST TANK	139.825	0.935	Open Manhole	450	10.000	138.890	100				
SIC 205-1	139.860	1.010	Open Manhole	450	10.001	138.850	100	10.000	138.850	100	
SMH 20	139.650	1.350	Open Manhole	1200	6.006	138.300	150	6.005	138.300	150	
								10.001	138.350	100	
DIST TANK	139.570	0.580	Open Manhole	450	11.000	138.990	100				
SIC 204-1	139.650	0.680	Open Manhole	450	11.001	138.970	100	11.000	138.970	100	
JUNCTION	139.520	1.380	Junction		6.007	138.140	150	6.006	138.140	150	
								11.001	138.190	100	
SMH 19	139.480	1.569	Open Manhole	1200	6.008	137.911	150	6.007	137.911	150	
SMH 11	139.230	2.993	Open Manhole	1350	1.009	136.237	375	1.008	136.312	300	
								6.008	136.462	150	
©1982-2019 Innovyze											

Jubb Consulting Engineers Limited										Page 12	
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR					VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC						
Date 15/07/2025					Designed by EPH						
File SWD NETWORK - POND A - 100 YR...					Checked by						
Innovyze					Network 2019.1						
<u>Manhole Schedules for Storm</u>											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
DIST TANK	139.155	0.730	Open Manhole	450	12.000	138.425	100				
SIC 222-1	139.180	0.785	Open Manhole	450	12.001	138.395	100	12.000	138.395	100	
SMH 18	139.240	1.350	Open Manhole	1200	12.002	137.890	150	12.001	137.940	100	
DIS TANK	139.210	0.730	Open Manhole	450	13.000	138.480	100				
SIC 220-1	139.320	0.860	Open Manhole	450	13.001	138.460	100	13.000	138.460	100	
JUNCTION	139.435	1.736	Junction		12.003	137.699	150	12.002	137.699	150	
								13.001	137.749	100	
DIST TANK	139.430	0.730	Open Manhole	450	14.000	138.700	100				
SIC 219-1	139.505	0.825	Open Manhole	450	14.001	138.680	100	14.000	138.680	100	
JUNCTION	139.635	2.127	Junction		12.004	137.508	150	12.003	137.508	150	
								14.001	137.558	100	
SMH 17	139.600	2.366	Open Manhole	1200	12.005	137.234	225	12.004	137.309	150	
DIST TANK	139.460	0.640	Open Manhole	450	15.000	138.820	100				
SIC 136-1	139.515	0.715	Open Manhole	450	15.001	138.800	100	15.000	138.800	100	
JUNCTION	139.510	2.454	Junction		12.006	137.056	225	12.005	137.056	225	
								15.001	137.181	100	
DIST TANK	139.250	0.640	Open Manhole	450	16.000	138.610	100				
SIC 138-1	139.355	0.765	Open Manhole	450	16.001	138.590	100	16.000	138.590	100	
JUNCTION	139.370	2.563	Junction		12.007	136.807	225	12.006	136.807	225	
								16.001	136.932	100	
DIST TANK	139.015	0.640	Open Manhole	450	17.000	138.375	100				
SIC 140-1	139.130	0.775	Open Manhole	450	17.001	138.355	100	17.000	138.355	100	
JUNCTION	139.085	2.564	Junction		12.008	136.521	225	12.007	136.521	225	
								17.001	136.646	100	
DIST TANK	138.900	0.640	Open Manhole	450	18.000	138.260	100				
SIC 141-1	138.900	0.660	Open Manhole	450	18.001	138.240	100	18.000	138.240	100	
SMH 10	138.885	3.108	Open Manhole	1500	1.010	135.777	600	1.009	136.002	375	
								12.008	136.152	225	
								18.001	136.277	100	
SMH 9	139.135	3.382	Open Manhole	1500	1.011	135.753	600	1.010	135.753	600	
DIST TANK	140.580	0.660	Open Manhole	450	19.000	139.920	100				
SIC 173-1	140.580	0.680	Open Manhole	450	19.001	139.900	100	19.000	139.900	100	
SMH 32	140.715	1.370	Open Manhole	1200	19.002	139.345	150	19.001	139.395	100	
DIST TANK	140.660	0.640	Open Manhole	450	20.000	140.020	100				
SIC 172-1	140.660	0.660	Open Manhole	450	20.001	140.000	100	20.000	140.000	100	
JUNCTION	140.925	1.665	Junction		19.003	139.260	150	19.002	139.260	150	
								20.001	139.310	100	
DIST TANK	140.925	0.640	Open Manhole	450	21.000	140.285	100				
SIC 171-1	140.925	0.660	Open Manhole	450	21.001	140.265	100	21.000	140.265	100	
SMH 31	141.190	2.038	Open Manhole	1200	19.004	139.152	150	19.003	139.152	150	
								21.001	139.202	100	
DIST TANK	141.275	0.640	Open Manhole	450	22.000	140.635	100				
SIC 170-1	141.275	0.660	Open Manhole	450	22.001	140.615	100	22.000	140.615	100	
JUNCTION	141.410	2.348	Junction		19.005	139.062	150	19.004	139.062	150	
								22.001	139.112	100	
DIST TANK	141.515	0.640	Open Manhole	450	23.000	140.875	100				
SIC 167-1	141.515	0.660	Open Manhole	450	23.001	140.855	100	23.000	140.855	100	
©1982-2019 Innovyze											

Jubb Consulting Engineers Limited		Page 15
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...	Designed by EPH Checked by	
Innovyze	Network 2019.1	

Manhole Schedules for Storm

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
SMH 4	138.060	2.569	Open Manhole	1500	1.018	135.491	600	1.017	135.491	600	
DIST TANK	138.030	0.640	Open Manhole	450	45.000	137.390	100				
SIC 150-1	138.030	0.660	Open Manhole	450	45.001	137.370	100	45.000	137.370	100	
JUNCTION	138.080	2.598	Junction		1.019	135.482	600	1.018	135.482	600	
								45.001	135.982	100	
SMH 3	138.010	2.554	Open Manhole	1500	1.020	135.456	600	1.019	135.456	600	
DIST TANK	137.850	0.640	Open Manhole	450	46.000	137.210	100				
SIC 111-1	137.850	0.660	Open Manhole	450	46.001	137.190	100	46.000	137.190	100	
JUNCTION	137.950	2.504	Junction		1.021	135.446	600	1.020	135.446	600	
								46.001	135.946	100	
DIST TANK	137.500	0.640	Open Manhole	450	47.000	136.860	100				
SIC 113-1	137.500	0.660	Open Manhole	450	47.001	136.840	100	47.000	136.840	100	
JUNCTION	137.700	2.291	Junction		1.022	135.409	600	1.021	135.409	600	
								47.001	135.909	100	
SWMH 114-3	138.825	1.350	Open Manhole	1200	48.000	137.475	150				
SWMH 114-2	137.865	1.425	Open Manhole	1200	48.001	136.440	225	48.000	136.515	150	
DIST TANK	137.140	0.640	Open Manhole	450	49.000	136.500	100				
SIC 115-1	137.140	0.660	Open Manhole	450	49.001	136.480	100	49.000	136.480	100	
SWMH 114-1	137.350	1.425	Open Manhole	1200	48.002	135.925	225	48.001	135.925	225	
								49.001	136.050	100	
SMH 2	137.190	1.821	Open Manhole	1500	1.023	135.369	600	1.022	135.369	600	
								48.002	135.744	225	
DIST TANK	137.010	0.640	Open Manhole	450	50.000	136.370	100				
SIC 116-1	137.010	0.660	Open Manhole	450	50.001	136.350	100	50.000	136.350	100	
JUNCTION	137.000	1.649	Junction		1.024	135.351	600	1.023	135.351	600	
								50.001	135.839	100	
SMH 1	136.780	1.471	Open Manhole	1500	1.025	135.309	600	1.024	135.309	600	
POND	136.578	1.300	Open Manhole	1500	1.026	135.278	300	1.025	135.278	600	
FC	136.350	1.150	Open Manhole	1200	1.027	135.200	150	1.026	135.200	300	
	135.770	1.651	Open Manhole	0		OUTFALL		1.027	134.119	150	

No coordinates have been specified, layout information cannot be produced.

Jubb Consulting Engineers Limited		Page 16
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	o	100	DIST TANK	138.865	138.270	0.495	Open Manhole	450
1.001	o	100	SIC 206-1	138.865	138.250	0.515	Open Manhole	1200
1.002	o	225	SMH 14	138.805	137.080	1.500	Junction	
2.000	o	100	DIST TANK 1	138.865	138.260	0.505	Open Manhole	450
2.001	o	100	SIC 207-1	138.940	138.240	0.600	Open Manhole	450
1.003	o	225	JUNCTION	138.705	136.860	1.620	Junction	
1.004	o	300	SMH 13	138.735	136.748	1.687	Open Manhole	1200
3.000	o	100	DIST TK 1	139.020	138.320	0.600	Open Manhole	450
3.001	o	100	SIC 208-1	139.020	138.300	0.620	Open Manhole	450
1.005	o	300	JUNCTION	138.770	136.715	1.755	Junction	
4.000	o	100	DIST TANK 1	139.065	138.465	0.500	Open Manhole	450
4.001	o	100	SIC 209-1	139.080	138.445	0.535	Open Manhole	450
1.006	o	300	JUNCTION	138.913	136.606	2.007	Junction	
5.000	o	100	DIST TANK 1	139.150	138.550	0.500	Open Manhole	450
5.001	o	100	SIC 210-1	139.175	138.530	0.545	Open Manhole	450
1.007	o	300	JUNCTION	139.040	136.503	2.237	Junction	
1.008	o	300	SMH 12	139.230	136.386	2.544	Open Manhole	1200
6.000	o	100	DIST TANK	141.980	141.160	0.720	Open Manhole	450
6.001	o	100	SIC 188-1	142.115	141.140	0.875	Open Manhole	450

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.000	1.000	50.0	SIC 206-1	138.865	138.250	0.515	Open Manhole	1200
1.001	14.185	13.6	SMH 14	138.805	137.205	1.500	Junction	
1.002	17.662	80.3	JUNCTION	138.705	136.860	1.620	Junction	
2.000	1.000	50.0	SIC 207-1	138.940	138.240	0.600	Open Manhole	450
2.001	6.793	5.4	JUNCTION	138.705	136.985	1.620	Junction	
1.003	2.967	80.3	SMH 13	138.735	136.823	1.687	Open Manhole	1200
1.004	3.349	101.5	JUNCTION	138.770	136.715	1.755	Junction	
3.000	1.000	50.0	SIC 208-1	139.020	138.300	0.620	Open Manhole	450
3.001	7.899	5.7	JUNCTION	138.770	136.915	1.755	Junction	
1.005	10.872	99.7	JUNCTION	138.913	136.606	2.007	Junction	
4.000	1.000	50.0	SIC 209-1	139.080	138.445	0.535	Open Manhole	450
4.001	7.533	4.6	JUNCTION	138.913	136.806	2.007	Junction	
1.006	10.269	99.7	JUNCTION	139.040	136.503	2.237	Junction	
5.000	1.000	50.0	SIC 210-1	139.175	138.530	0.545	Open Manhole	450
5.001	7.162	3.9	JUNCTION	139.040	136.703	2.237	Junction	
1.007	11.677	99.8	SMH 12	139.230	136.386	2.544	Open Manhole	1200
1.008	7.447	100.6	SMH 11	139.230	136.312	2.618	Open Manhole	1350
6.000	1.000	50.0	SIC 188-1	142.115	141.140	0.875	Open Manhole	450
6.001	8.779	11.1	SMH 22	141.650	140.350	1.200	Open Manhole	1200

Jubb Consulting Engineers Limited

Unit 1, Ensign House
Parkway Court, Longbridge Road
Plymouth, PL6 8LR

Date 15/07/2025
File SWD NETWORK - POND A - 100 YR...

Innovyze

VICTORIA ROAD
SWD NETWORK- POND A
100 YEAR PLUS 45 CC

Designed by EPH
Checked by

Network 2019.1

Page 17



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
6.002	o	150	SMH 22	141.650	140.300	1.200	Open Manhole	1200
7.000	o	100	DIST TANK	141.220	140.395	0.725	Open Manhole	450
7.001	o	100	SIC 187-1	141.300	140.375	0.825	Open Manhole	450
6.003	o	150	JUNCTION	141.105	139.810	1.145	Junction	
8.000	o	100	DIST TANK	140.755	139.875	0.780	Open Manhole	450
8.001	o	100	SIC 186-1	140.865	139.855	0.910	Open Manhole	450
6.004	o	150	JUNCTION	140.690	139.360	1.180	Junction	
9.000	o	100	DIST TANK	140.255	139.350	0.805	Open Manhole	450
9.001	o	100	SIC 185-1	140.300	139.330	0.870	Open Manhole	450
6.005	o	150	SMH 21	140.100	138.750	1.200	Open Manhole	1200
10.000	o	100	DIST TANK	139.825	138.890	0.835	Open Manhole	450
10.001	o	100	SIC 205-1	139.860	138.850	0.910	Open Manhole	450
6.006	o	150	SMH 20	139.650	138.300	1.200	Open Manhole	1200
11.000	o	100	DIST TANK	139.570	138.990	0.480	Open Manhole	450
11.001	o	100	SIC 204-1	139.650	138.970	0.580	Open Manhole	450
6.007	o	150	JUNCTION	139.520	138.140	1.230	Junction	
6.008	o	150	SMH 19	139.480	137.911	1.419	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
6.002	11.630	23.7	JUNCTION	141.105	139.810	1.145	Junction	
7.000	1.000	50.0	SIC 187-1	141.300	140.375	0.825	Open Manhole	450
7.001	5.711	11.1	JUNCTION	141.105	139.860	1.145	Junction	
6.003	10.709	23.8	JUNCTION	140.690	139.360	1.180	Junction	
8.000	1.000	50.0	SIC 186-1	140.865	139.855	0.910	Open Manhole	450
8.001	5.359	12.0	JUNCTION	140.690	139.410	1.180	Junction	
6.004	14.513	23.8	SMH 21	140.100	138.750	1.200	Open Manhole	1200
9.000	1.000	50.0	SIC 185-1	140.300	139.330	0.870	Open Manhole	450
9.001	6.287	11.9	SMH 21	140.100	138.800	1.200	Open Manhole	1200
6.005	16.038	35.6	SMH 20	139.650	138.300	1.200	Open Manhole	1200
10.000	1.775	44.4	SIC 205-1	139.860	138.850	0.910	Open Manhole	450
10.001	5.975	12.0	SMH 20	139.650	138.350	1.200	Open Manhole	1200
6.006	5.575	34.8	JUNCTION	139.520	138.140	1.230	Junction	
11.000	1.000	50.0	SIC 204-1	139.650	138.970	0.580	Open Manhole	450
11.001	9.935	12.7	JUNCTION	139.520	138.190	1.230	Junction	
6.007	7.954	34.7	SMH 19	139.480	137.911	1.419	Open Manhole	1200
6.008	9.917	6.8	SMH 11	139.230	136.462	2.618	Open Manhole	1350

©1982-2019 Innovyze

Jubb Consulting Engineers Limited		Page 18
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.009	o	375	SMH 11	139.230	136.237	2.618	Open Manhole	1350
12.000	o	100	DIST TANK	139.155	138.425	0.630	Open Manhole	450
12.001	o	100	SIC 222-1	139.180	138.395	0.685	Open Manhole	450
12.002	o	150	SMH 18	139.240	137.890	1.200	Open Manhole	1200
13.000	o	100	DIS TANK	139.210	138.480	0.630	Open Manhole	450
13.001	o	100	SIC 220-1	139.320	138.460	0.760	Open Manhole	450
12.003	o	150	JUNCTION	139.435	137.699	1.586	Junction	
14.000	o	100	DIST TANK	139.430	138.700	0.630	Open Manhole	450
14.001	o	100	SIC 219-1	139.505	138.680	0.725	Open Manhole	450
12.004	o	150	JUNCTION	139.635	137.508	1.977	Junction	
12.005	o	225	SMH 17	139.600	137.234	2.141	Open Manhole	1200
15.000	o	100	DIST TANK	139.460	138.820	0.540	Open Manhole	450
15.001	o	100	SIC 136-1	139.515	138.800	0.615	Open Manhole	450
12.006	o	225	JUNCTION	139.510	137.056	2.229	Junction	
16.000	o	100	DIST TANK	139.250	138.610	0.540	Open Manhole	450
16.001	o	100	SIC 138-1	139.355	138.590	0.665	Open Manhole	450
12.007	o	225	JUNCTION	139.370	136.807	2.338	Junction	
17.000	o	100	DIST TANK	139.015	138.375	0.540	Open Manhole	450

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.009	48.885	208.0	SMH 10	138.885	136.002	2.508	Open Manhole	1500
12.000	1.550	51.7	SIC 222-1	139.180	138.395	0.685	Open Manhole	450
12.001	4.297	9.4	SMH 18	139.240	137.940	1.200	Open Manhole	1200
12.002	15.280	80.0	JUNCTION	139.435	137.699	1.586	Junction	
13.000	1.000	50.0	SIC 220-1	139.320	138.460	0.760	Open Manhole	450
13.001	6.156	8.7	JUNCTION	139.435	137.749	1.586	Junction	
12.003	15.299	80.0	JUNCTION	139.635	137.508	1.977	Junction	
14.000	1.000	50.0	SIC 219-1	139.505	138.680	0.725	Open Manhole	450
14.001	5.138	4.6	JUNCTION	139.635	137.558	1.977	Junction	
12.004	15.953	80.0	SMH 17	139.600	137.309	2.141	Open Manhole	1200
12.005	11.218	62.9	JUNCTION	139.510	137.056	2.229	Junction	
15.000	1.000	50.0	SIC 136-1	139.515	138.800	0.615	Open Manhole	450
15.001	6.716	4.1	JUNCTION	139.510	137.181	2.229	Junction	
12.006	15.689	63.0	JUNCTION	139.370	136.807	2.338	Junction	
16.000	1.000	50.0	SIC 138-1	139.355	138.590	0.665	Open Manhole	450
16.001	5.829	3.5	JUNCTION	139.370	136.932	2.338	Junction	
12.007	17.988	62.9	JUNCTION	139.085	136.521	2.339	Junction	
17.000	1.000	50.0	SIC 140-1	139.130	138.355	0.675	Open Manhole	450

Jubb Consulting Engineers Limited		Page 19	
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR		VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...		Designed by EPH Checked by	
Innovyze		Network 2019.1	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
17.001	o	100	SIC 140-1	139.130	138.355	0.675	Open Manhole		450
12.008	o	225	JUNCTION	139.085	136.521	2.414	Junction		
18.000	o	100	DIST TANK	138.900	138.260	0.540	Open Manhole		450
18.001	o	100	SIC 141-1	138.900	138.240	0.560	Open Manhole		450
1.010	o	600	SMH 10	138.885	135.777	2.508	Open Manhole		1500
1.011	o	600	SMH 9	139.135	135.753	2.782	Open Manhole		1500
19.000	o	100	DIST TANK	140.580	139.920	0.560	Open Manhole		450
19.001	o	100	SIC 173-1	140.580	139.900	0.580	Open Manhole		450
19.002	o	150	SMH 32	140.715	139.345	1.220	Open Manhole		1200
20.000	o	100	DIST TANK	140.660	140.020	0.540	Open Manhole		450
20.001	o	100	SIC 172-1	140.660	140.000	0.560	Open Manhole		450
19.003	o	150	JUNCTION	140.925	139.260	1.515	Junction		
21.000	o	100	DIST TANK	140.925	140.285	0.540	Open Manhole		450
21.001	o	100	SIC 171-1	140.925	140.265	0.560	Open Manhole		450
19.004	o	150	SMH 31	141.190	139.152	1.888	Open Manhole		1200
22.000	o	100	DIST TANK	141.275	140.635	0.540	Open Manhole		450
22.001	o	100	SIC 170-1	141.275	140.615	0.560	Open Manhole		450
19.005	o	150	JUNCTION	141.410	139.062	2.198	Junction		

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
17.001	5.516	3.2	JUNCTION	139.085	136.646	2.339	Junction		
12.008	23.129	62.7	SMH 10	138.885	136.152	2.583	Open Manhole		1500
18.000	1.000	50.0	SIC 141-1	138.900	138.240	0.560	Open Manhole		450
18.001	6.574	3.3	SMH 10	138.885	136.277	2.508	Open Manhole		1500
1.010	10.672	450.0	SMH 9	139.135	135.753	2.782	Open Manhole		1500
1.011	27.837	450.0	SMH 8	139.965	135.691	3.674	Open Manhole		1500
19.000	1.000	50.0	SIC 173-1	140.580	139.900	0.580	Open Manhole		450
19.001	5.505	10.9	SMH 32	140.715	139.395	1.220	Open Manhole		1200
19.002	8.366	98.4	JUNCTION	140.925	139.260	1.515	Junction		
20.000	1.000	50.0	SIC 172-1	140.660	140.000	0.560	Open Manhole		450
20.001	5.123	7.4	JUNCTION	140.925	139.310	1.515	Junction		
19.003	10.641	98.5	SMH 31	141.190	139.152	1.888	Open Manhole		1200
21.000	1.000	50.0	SIC 171-1	140.925	140.265	0.560	Open Manhole		450
21.001	4.539	4.3	SMH 31	141.190	139.202	1.888	Open Manhole		1200
19.004	8.742	97.1	JUNCTION	141.410	139.062	2.198	Junction		
22.000	1.000	50.0	SIC 170-1	141.275	140.615	0.560	Open Manhole		450
22.001	5.941	4.0	JUNCTION	141.410	139.112	2.198	Junction		
19.005	11.645	97.0	JUNCTION	141.830	138.942	2.738	Junction		

©1982-2019 Innovyze

Jubb Consulting Engineers Limited

Unit 1, Ensign House
Parkway Court, Longbridge Road
Plymouth, PL6 8LR

Date 15/07/2025
File SWD NETWORK - POND A - 100 YR...

Innovyze

VICTORIA ROAD
SWD NETWORK- POND A
100 YEAR PLUS 45 CC

Designed by EPH
Checked by

Network 2019.1

Page 20



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
23.000	o	100	DIST TANK	141.515	140.875	0.540	Open Manhole	450
23.001	o	100	SIC 167-1	141.515	140.855	0.560	Open Manhole	450
19.006	o	150	JUNCTION	141.830	138.942	2.738	Junction	
19.007	o	150	SMH 30	142.825	138.759	3.916	Open Manhole	1200
24.000	o	100	DIST TANK	142.425	141.275	1.050	Open Manhole	450
24.001	o	100	SIC 174-1	142.500	141.235	1.165	Open Manhole	450
24.002	o	150	SMH 34	142.610	141.125	1.335	Open Manhole	1200
25.000	o	100	DIST TANK	142.590	141.440	1.050	Open Manhole	450
25.001	o	100	SIC 175-1	142.630	141.400	1.130	Open Manhole	450
24.003	o	150	JUNCTION	142.710	141.045	1.515	Junction	
24.004	o	150	SMH 33	142.960	140.854	1.956	Open Manhole	1200
19.008	o	225	SMH 29	143.175	138.575	4.375	Open Manhole	1200
26.000	o	100	DIST TANK	142.730	142.090	0.540	Open Manhole	450
26.001	o	100	SIC 176-1	142.730	142.070	0.560	Open Manhole	450
19.009	o	225	JUNCTION	142.750	138.425	4.100	Junction	
27.000	o	100	DIST TANK	142.647	142.007	0.540	Open Manhole	450
27.001	o	100	SIC 169-1	142.647	141.987	0.560	Open Manhole	450
19.010	o	225	SMH 28	142.600	138.381	3.994	Open Manhole	450

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
23.000	1.000	50.0	SIC 167-1	141.515	140.855	0.560	Open Manhole	450
23.001	5.573	3.0	JUNCTION	141.830	138.992	2.738	Junction	
19.006	17.809	97.3	SMH 30	142.825	138.759	3.916	Open Manhole	1200
19.007	10.569	97.1	SMH 29	143.175	138.650	4.375	Open Manhole	1200
24.000	2.000	50.0	SIC 174-1	142.500	141.235	1.165	Open Manhole	450
24.001	3.210	53.5	SMH 34	142.610	141.175	1.335	Open Manhole	1200
24.002	7.966	99.6	JUNCTION	142.710	141.045	1.515	Junction	
25.000	2.000	50.0	SIC 175-1	142.630	141.400	1.130	Open Manhole	450
25.001	3.340	11.0	JUNCTION	142.710	141.095	1.515	Junction	
24.003	19.055	99.8	SMH 33	142.960	140.854	1.956	Open Manhole	1200
24.004	21.260	38.3	SMH 29	143.175	140.299	2.726	Open Manhole	1200
19.008	14.694	98.0	JUNCTION	142.750	138.425	4.100	Junction	
26.000	1.000	50.0	SIC 176-1	142.730	142.070	0.560	Open Manhole	450
26.001	7.163	2.0	JUNCTION	142.750	138.550	4.100	Junction	
19.009	4.331	98.4	SMH 28	142.600	138.381	3.994	Open Manhole	450
27.000	1.000	50.0	SIC 169-1	142.647	141.987	0.560	Open Manhole	450
27.001	5.718	3.3	SMH 28	142.600	140.231	2.269	Open Manhole	450
19.010	7.021	100.3	JUNCTION	142.250	138.311	3.714	Junction	

©1982-2019 Innovyze

Jubb Consulting Engineers Limited

Page 21

Unit 1, Ensign House

Parkway Court, Longbridge Road

Plymouth, PL6 8LR

VICTORIA ROAD

SWD NETWORK- POND A

100 YEAR PLUS 45 CC

Date 15/07/2025

File SWD NETWORK - POND A - 100 YR...

Designed by EPH

Checked by

Innovyze

Network 2019.1

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
28.000	o	100	DIST TANK	141.925	141.285	0.540	Open Manhole	450
28.001	o	100	SIC 178-1	141.925	141.265	0.560	Open Manhole	450
19.011	o	225	JUNCTION	142.250	138.311	3.714	Junction	
29.000	o	100	DIST TANK	141.489	140.849	0.540	Open Manhole	450
29.001	o	100	SIC 166-1	141.489	140.829	0.560	Open Manhole	450
30.000	o	100	DIST TANK	142.815	141.815	0.900	Open Manhole	450
30.001	o	100	SIC 184-1	142.910	141.795	1.015	Open Manhole	450
30.002	o	150	SMH 27	142.975	141.625	1.200	Open Manhole	1200
31.000	o	100	DIST TANK	142.700	142.020	0.580	Open Manhole	450
31.001	o	100	SIC 182-1	142.850	142.000	0.750	Open Manhole	450
30.003	o	150	SMH 26	142.790	141.440	1.200	Open Manhole	1200
30.004	o	150	SMH 25	142.700	141.335	1.215	Open Manhole	1200
32.000	o	100	DIST TANK	142.635	141.655	0.880	Open Manhole	450
32.001	o	100	SIC 181-1	142.750	141.635	1.015	Open Manhole	450
30.005	o	150	JUNCTION	142.660	141.252	1.258	Junction	
33.000	o	150	HD CP1	142.160	140.810	1.200	Open Manhole	1200
30.006	o	225	SMH 24	142.350	140.635	1.490	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
28.000	1.000	50.0	SIC 178-1	141.925	141.265	0.560	Open Manhole	450
28.001	9.295	3.3	JUNCTION	142.250	138.436	3.714	Junction	
19.011	14.785	101.3	SMH 23	141.400	138.165	3.010	Open Manhole	1200
29.000	1.000	50.0	SIC 166-1	141.489	140.829	0.560	Open Manhole	450
29.001	4.575	4.8	SMH 23	141.400	139.869	1.431	Open Manhole	1200
30.000	1.000	50.0	SIC 184-1	142.910	141.795	1.015	Open Manhole	450
30.001	5.994	50.0	SMH 27	142.975	141.675	1.200	Open Manhole	1200
30.002	14.939	80.8	SMH 26	142.790	141.440	1.200	Open Manhole	1200
31.000	1.000	50.0	SIC 182-1	142.850	142.000	0.750	Open Manhole	450
31.001	5.504	10.8	SMH 26	142.790	141.490	1.200	Open Manhole	1200
30.003	8.415	80.0	SMH 25	142.700	141.335	1.215	Open Manhole	1200
30.004	2.616	31.5	JUNCTION	142.660	141.252	1.258	Junction	
32.000	1.000	50.0	SIC 181-1	142.750	141.635	1.015	Open Manhole	450
32.001	6.676	20.0	JUNCTION	142.660	141.302	1.258	Junction	
30.005	17.093	31.5	SMH 24	142.350	140.710	1.490	Open Manhole	1200
33.000	10.000	100.0	SMH 24	142.350	140.710	1.490	Open Manhole	1200
30.006	22.892	26.3	JUNCTION	141.810	139.765	1.820	Junction	

©1982-2019 Innovyze

Jubb Consulting Engineers Limited		Page 22							
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR		VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC							
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...		Designed by EPH Checked by							
Innovyze		Network 2019.1							
PIPELINE SCHEDULES for Storm									
Upstream Manhole									
PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
34.000	o	100	DIST TANK	141.725	141.085	0.540	Open Manhole		450
34.001	o	100	SIC 190-1	141.750	141.065	0.585	Open Manhole		450
30.007	o	225	JUNCTION	141.810	139.765	1.820	Junction		
35.000	o	100	DIST TANK	141.810	141.170	0.540	Open Manhole		450
35.001	o	100	SIC 180-1	141.900	141.150	0.650	Open Manhole		450
30.008	o	225	JUNCTION	141.795	139.726	1.844	Junction		
36.000	o	100	DIST TANK	141.685	141.045	0.540	Open Manhole		450
36.001	o	100	SIC 191-1	141.700	141.025	0.575	Open Manhole		450
30.009	o	225	JUNCTION	141.630	139.296	2.109	Junction		
37.000	o	100	DIST TANK	141.760	141.120	0.540	Open Manhole		450
37.001	o	100	SIC 179-1	141.785	141.100	0.585	Open Manhole		450
30.010	o	225	JUNCTION	141.600	139.202	2.173	Junction		
19.012	o	300	SMH 23	141.400	138.090	3.010	Open Manhole		1200
38.000	o	100	DIST TANK	140.480	139.840	0.540	Open Manhole		450
38.001	o	100	SIC 165-1	140.810	139.820	0.890	Open Manhole		450
19.013	o	300	JUNCTION	140.925	137.936	2.689	Junction		
1.012	o	600	SMH 8	139.965	135.691	3.674	Open Manhole		1500
Downstream Manhole									
PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., (mm)	L*W
34.000	1.000	50.0	SIC 190-1	141.750	141.065	0.585	Open Manhole		450
34.001	6.997	6.0	JUNCTION	141.810	139.890	1.820	Junction		
30.007	1.020	26.2	JUNCTION	141.795	139.726	1.844	Junction		
35.000	1.000	50.0	SIC 180-1	141.900	141.150	0.650	Open Manhole		450
35.001	5.500	4.2	JUNCTION	141.795	139.851	1.844	Junction		
30.008	11.314	26.3	JUNCTION	141.630	139.296	2.109	Junction		
36.000	1.000	50.0	SIC 191-1	141.700	141.025	0.575	Open Manhole		450
36.001	6.997	4.4	JUNCTION	141.630	139.421	2.109	Junction		
30.009	2.476	26.3	JUNCTION	141.600	139.202	2.173	Junction		
37.000	1.000	50.0	SIC 179-1	141.785	141.100	0.585	Open Manhole		450
37.001	6.100	3.4	JUNCTION	141.600	139.327	2.173	Junction		
30.010	27.427	26.4	SMH 23	141.400	138.165	3.010	Open Manhole		1200
19.012	15.382	99.9	JUNCTION	140.925	137.936	2.689	Junction		
38.000	1.000	50.0	SIC 165-1	140.810	139.820	0.890	Open Manhole		450
38.001	5.000	3.0	JUNCTION	140.925	138.136	2.689	Junction		
19.013	25.832	100.1	SMH 8	139.965	137.678	1.987	Open Manhole		1500
1.012	23.589	453.6	SMH 7	139.400	135.639	3.161	Open Manhole		1500
©1982-2019 Innovyze									

Jubb Consulting Engineers Limited

Unit 1, Ensign House
Parkway Court, Longbridge Road
Plymouth, PL6 8LR

Date 15/07/2025
File SWD NETWORK - POND A - 100 YR...

Innovyze

VICTORIA ROAD
SWD NETWORK- POND A
100 YEAR PLUS 45 CC

Designed by EPH
Checked by

Network 2019.1

Page 23



PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.013	o	600	SMH 7	139.400	135.639	3.161	Open Manhole	1500
1.014	o	600	SMH 6	138.640	135.570	2.470	Open Manhole	1500
39.000	o	100	DIST TANK	138.350	137.710	0.540	Open Manhole	450
39.001	o	100	SIC 146-1	138.400	137.690	0.610	Open Manhole	450
1.015	o	600	JUNCTION	138.450	135.555	2.295	Junction	
40.000	o	100	DIST TANK	140.010	139.370	0.540	Open Manhole	450
40.001	o	100	SIC 152_1	140.080	139.350	0.630	Open Manhole	450
41.000	o	100	DIST TANK	139.820	139.180	0.540	Open Manhole	450
41.001	o	100	SIC 153-1	139.900	139.160	0.640	Open Manhole	450
40.002	o	150	SMH 36	139.825	138.475	1.200	Open Manhole	1200
42.000	o	100	DIST TANK	139.465	138.825	0.540	Open Manhole	450
42.001	o	100	SIC 154-1	139.560	138.805	0.655	Open Manhole	450
40.003	o	150	JUNCTION	139.475	138.127	1.198	Junction	
43.000	o	100	DIST TANK	138.975	138.335	0.540	Open Manhole	450
43.001	o	100	SIC 155-1	139.090	138.315	0.675	Open Manhole	450
40.004	o	150	JUNCTION	138.980	137.659	1.171	Junction	
40.005	o	150	SMH 35	138.775	137.423	1.202	Open Manhole	1200
1.016	o	600	SMH 5	138.225	135.533	2.092	Open Manhole	1500

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
1.013	31.370	454.6	SMH 6	138.640	135.570	2.470	Open Manhole	1500
1.014	6.875	458.3	JUNCTION	138.450	135.555	2.295	Junction	
39.000	1.000	50.0	SIC 146-1	138.400	137.690	0.610	Open Manhole	450
39.001	6.100	3.7	JUNCTION	138.450	136.055	2.295	Junction	
1.015	9.789	445.0	SMH 5	138.225	135.533	2.092	Open Manhole	1500
40.000	1.000	50.0	SIC 152_1	140.080	139.350	0.630	Open Manhole	450
40.001	5.568	6.7	SMH 36	139.825	138.525	1.200	Open Manhole	1200
41.000	1.000	50.0	SIC 153-1	139.900	139.160	0.640	Open Manhole	450
41.001	4.084	6.4	SMH 36	139.825	138.525	1.200	Open Manhole	1200
40.002	10.715	30.8	JUNCTION	139.475	138.127	1.198	Junction	
42.000	1.000	50.0	SIC 154-1	139.560	138.805	0.655	Open Manhole	450
42.001	4.084	6.5	JUNCTION	139.475	138.177	1.198	Junction	
40.003	14.419	30.8	JUNCTION	138.980	137.659	1.171	Junction	
43.000	1.000	50.0	SIC 155-1	139.090	138.315	0.675	Open Manhole	450
43.001	4.084	6.7	JUNCTION	138.980	137.709	1.171	Junction	
40.004	7.268	30.8	SMH 35	138.775	137.423	1.202	Open Manhole	1200
40.005	20.658	14.3	SMH 5	138.225	135.983	2.092	Open Manhole	1500
1.016	6.192	455.0	JUNCTION	138.075	135.519	1.956	Junction	

©1982-2019 Innovyze

Jubb Consulting Engineers Limited							Page 24	
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR				VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC				
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...				Designed by EPH Checked by				
Innovyze				Network 2019.1				
PIPELINE SCHEDULES for Storm								
Upstream Manhole								
PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
44.000	o	100	DIST TANK	138.030	137.390	0.540	Open Manhole	450
44.001	o	100	SIC 148-1	138.190	137.370	0.720	Open Manhole	450
1.017	o	600	JUNCTION	138.075	135.519	1.956	Junction	
1.018	o	600	SMH 4	138.060	135.491	1.969	Open Manhole	1500
45.000	o	100	DIST TANK	138.030	137.390	0.540	Open Manhole	450
45.001	o	100	SIC 150-1	138.030	137.370	0.560	Open Manhole	450
1.019	o	600	JUNCTION	138.080	135.482	1.998	Junction	
1.020	o	600	SMH 3	138.010	135.456	1.954	Open Manhole	1500
46.000	o	100	DIST TANK	137.850	137.210	0.540	Open Manhole	450
46.001	o	100	SIC 111-1	137.850	137.190	0.560	Open Manhole	450
1.021	o	600	JUNCTION	137.950	135.446	1.904	Junction	
47.000	o	100	DIST TANK	137.500	136.860	0.540	Open Manhole	450
47.001	o	100	SIC 113-1	137.500	136.840	0.560	Open Manhole	450
1.022	o	600	JUNCTION	137.700	135.409	1.691	Junction	
48.000	o	150	SWMH 114-3	138.825	137.475	1.200	Open Manhole	1200
48.001	o	225	SWMH 114-2	137.865	136.440	1.200	Open Manhole	1200
49.000	o	100	DIST TANK	137.140	136.500	0.540	Open Manhole	450
49.001	o	100	SIC 115-1	137.140	136.480	0.560	Open Manhole	450
Downstream Manhole								
PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
44.000	1.000	50.0	SIC 148-1	138.190	137.370	0.720	Open Manhole	450
44.001	7.685	5.7	JUNCTION	138.075	136.019	1.956	Junction	
1.017	12.689	453.2	SMH 4	138.060	135.491	1.969	Open Manhole	1500
1.018	3.967	455.0	JUNCTION	138.080	135.482	1.998	Junction	
45.000	1.000	50.0	SIC 150-1	138.030	137.370	0.560	Open Manhole	450
45.001	6.583	4.7	JUNCTION	138.080	135.982	1.998	Junction	
1.019	12.038	463.0	SMH 3	138.010	135.456	1.954	Open Manhole	1500
1.020	4.751	455.0	JUNCTION	137.950	135.446	1.904	Junction	
46.000	1.000	50.0	SIC 111-1	137.850	137.190	0.560	Open Manhole	450
46.001	6.200	5.0	JUNCTION	137.950	135.946	1.904	Junction	
1.021	16.787	453.7	JUNCTION	137.700	135.409	1.691	Junction	
47.000	1.000	50.0	SIC 113-1	137.500	136.840	0.560	Open Manhole	450
47.001	6.955	7.5	JUNCTION	137.700	135.909	1.691	Junction	
1.022	18.318	458.0	SMH 2	137.190	135.369	1.221	Open Manhole	1500
48.000	38.846	40.5	SWMH 114-2	137.865	136.515	1.200	Open Manhole	1200
48.001	22.929	44.5	SWMH 114-1	137.350	135.925	1.200	Open Manhole	1200
49.000	1.000	50.0	SIC 115-1	137.140	136.480	0.560	Open Manhole	450
49.001	4.470	10.4	SWMH 114-1	137.350	136.050	1.200	Open Manhole	1200
©1982-2019 Innovyze								

Jubb Consulting Engineers Limited		Page 25
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR		VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...		Designed by EPH Checked by
Innovyze		Network 2019.1

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
48.002	o	225	SWMH 114-1	137.350	135.925	1.200	Open Manhole	1200
1.023	o	600	SMH 2	137.190	135.369	1.221	Open Manhole	1500
50.000	o	100	DIST TANK	137.010	136.370	0.540	Open Manhole	450
50.001	o	100	SIC 116-1	137.010	136.350	0.560	Open Manhole	450
1.024	o	600	JUNCTION	137.000	135.351	1.049	Junction	
1.025	o	600	SMH 1	136.780	135.309	0.871	Open Manhole	1500
1.026	o	300	POND	136.578	135.278	1.000	Open Manhole	1500
1.027	o	150	FC	136.350	135.200	1.000	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
48.002	5.083	28.1	SMH 2	137.190	135.744	1.221	Open Manhole	1500
1.023	8.042	455.0	JUNCTION	137.000	135.351	1.049	Junction	
50.000	1.000	50.0	SIC 116-1	137.010	136.350	0.560	Open Manhole	450
50.001	8.248	16.1	JUNCTION	137.000	135.839	1.061	Junction	
1.024	19.192	457.0	SMH 1	136.780	135.309	0.871	Open Manhole	1500
1.025	13.188	425.4	POND	136.578	135.278	0.700	Open Manhole	1500
1.026	7.176	92.0	FC	136.350	135.200	0.850	Open Manhole	1200
1.027	8.622	8.0		135.770	134.119	1.501	Open Manhole	0

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.027		135.770	134.119	0.000	0	0

Simulation Criteria for Storm

Volumetric Runoff Coeff	0.840	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	0.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	48	Number of Storage Structures	48	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH	D2 (1km)	0.417
Return Period (years)	1	D3 (1km)	0.273
FEH Rainfall Version	1999	E (1km)	0.289
Site Location	GB 386850 145550 ST 86850 45550	F (1km)	2.484
C (1km)	-0.027	Summer Storms	No
D1 (1km)	0.363	Winter Storms	Yes

©1982-2019 Innovyze

Jubb Consulting Engineers Limited		Page 26
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Synthetic Rainfall Details</u> Cv (Summer) 0.750 Storm Duration (mins) 15 Cv (Winter) 0.840		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 27
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Online Controls for Storm</u> <u>Orifice Manhole: SIC 206-1, DS/PN: 1.001, Volume (m³): 0.7</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.250 <u>Orifice Manhole: SIC 207-1, DS/PN: 2.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.240 <u>Orifice Manhole: SIC 208-1, DS/PN: 3.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.300 <u>Orifice Manhole: SIC 209-1, DS/PN: 4.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.445 <u>Orifice Manhole: SIC 210-1, DS/PN: 5.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.530 <u>Orifice Manhole: SIC 188-1, DS/PN: 6.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.140 <u>Orifice Manhole: SIC 187-1, DS/PN: 7.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 140.375 <u>Orifice Manhole: SIC 186-1, DS/PN: 8.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 139.855 <u>Orifice Manhole: SIC 185-1, DS/PN: 9.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 139.330 <u>Orifice Manhole: SIC 205-1, DS/PN: 10.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.850 <u>Orifice Manhole: SIC 204-1, DS/PN: 11.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.970 <u>Orifice Manhole: SIC 222-1, DS/PN: 12.001, Volume (m³): 0.1</u> Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 138.395 <u>Orifice Manhole: SIC 220-1, DS/PN: 13.001, Volume (m³): 0.1</u> Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 138.460 <u>Orifice Manhole: SIC 219-1, DS/PN: 14.001, Volume (m³): 0.1</u> Diameter (m) 0.050 Discharge Coefficient 0.600 Invert Level (m) 138.680		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 28
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...	Designed by EPH Checked by	
Innovyze	Network 2019.1	
<u>Orifice Manhole: SIC 136-1, DS/PN: 15.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.800 <u>Orifice Manhole: SIC 138-1, DS/PN: 16.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.590 <u>Orifice Manhole: SIC 140-1, DS/PN: 17.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.355 <u>Orifice Manhole: SIC 141-1, DS/PN: 18.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.240 <u>Orifice Manhole: SIC 173-1, DS/PN: 19.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 139.900 <u>Orifice Manhole: SIC 172-1, DS/PN: 20.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 140.000 <u>Orifice Manhole: SIC 171-1, DS/PN: 21.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 140.265 <u>Orifice Manhole: SIC 170-1, DS/PN: 22.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 140.615 <u>Orifice Manhole: SIC 167-1, DS/PN: 23.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 140.855 <u>Orifice Manhole: SIC 174-1, DS/PN: 24.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.235 <u>Orifice Manhole: SIC 175-1, DS/PN: 25.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.400 <u>Orifice Manhole: SIC 176-1, DS/PN: 26.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 142.070 <u>Orifice Manhole: SIC 169-1, DS/PN: 27.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.987 <u>Orifice Manhole: SIC 178-1, DS/PN: 28.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.265		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 29
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...	Designed by EPH Checked by	
Innovyze	Network 2019.1	
<u>Orifice Manhole: SIC 166-1, DS/PN: 29.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 140.829 <u>Orifice Manhole: SIC 184-1, DS/PN: 30.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.795 <u>Orifice Manhole: SIC 182-1, DS/PN: 31.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 142.000 <u>Orifice Manhole: SIC 181-1, DS/PN: 32.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.635 <u>Orifice Manhole: SIC 190-1, DS/PN: 34.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.065 <u>Orifice Manhole: SIC 180-1, DS/PN: 35.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.150 <u>Orifice Manhole: SIC 191-1, DS/PN: 36.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.025 <u>Orifice Manhole: SIC 179-1, DS/PN: 37.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 141.100 <u>Orifice Manhole: SIC 165-1, DS/PN: 38.001, Volume (m³): 0.2</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 139.820 <u>Orifice Manhole: SIC 146-1, DS/PN: 39.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 137.690 <u>Orifice Manhole: SIC 152-1, DS/PN: 40.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 139.350 <u>Orifice Manhole: SIC 153-1, DS/PN: 41.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 139.160 <u>Orifice Manhole: SIC 154-1, DS/PN: 42.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.805 <u>Orifice Manhole: SIC 155-1, DS/PN: 43.001, Volume (m³): 0.1</u> Diameter (m) 0.025 Discharge Coefficient 0.600 Invert Level (m) 138.315		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 31
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Storage Structures for Storm</u>		
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 1.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 6.0
Membrane Percolation (mm/hr)	1000	Length (m) 9.6
Max Percolation (l/s)	16.0	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	138.270	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: DIST TANK 1, DS/PN: 2.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 3.0
Membrane Percolation (mm/hr)	1000	Length (m) 9.6
Max Percolation (l/s)	8.0	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	138.260	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: DIST TK 1, DS/PN: 3.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 3.4
Membrane Percolation (mm/hr)	1000	Length (m) 11.9
Max Percolation (l/s)	11.2	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	138.320	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: DIST TANK 1, DS/PN: 4.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 3.4
Membrane Percolation (mm/hr)	1000	Length (m) 11.9
Max Percolation (l/s)	11.2	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	138.465	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: DIST TANK 1, DS/PN: 5.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 3.4
Membrane Percolation (mm/hr)	1000	Length (m) 11.6
Max Percolation (l/s)	11.0	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	138.550	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 6.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 6.4
Membrane Percolation (mm/hr)	1000	Length (m) 10.8
Max Percolation (l/s)	19.2	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	141.160	Membrane Depth (mm) 0
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 7.000</u>		
Infiltration Coefficient Base (m/hr)	0.01080	Width (m) 5.5
Membrane Percolation (mm/hr)	1000	Length (m) 5.7
Max Percolation (l/s)	8.7	Slope (1:X) 0.0
Safety Factor	5.0	Depression Storage (mm) 5
Porosity	0.30	Evaporation (mm/day) 3
Invert Level (m)	140.395	Membrane Depth (mm) 0
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 32																																																																																																																																																																								
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC																																																																																																																																																																									
Date 15/07/2025	Designed by EPH																																																																																																																																																																									
File SWD NETWORK - POND A - 100 YR...	Checked by																																																																																																																																																																									
Innovyze	Network 2019.1																																																																																																																																																																									
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 8.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>5.5</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>5.7</td></tr><tr><td>Max Percolation (l/s)</td><td>8.7</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>139.875</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 9.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>5.5</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>5.7</td></tr><tr><td>Max Percolation (l/s)</td><td>8.7</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>139.350</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 10.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>5.5</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>6.0</td></tr><tr><td>Max Percolation (l/s)</td><td>9.2</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>138.890</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 11.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>3.4</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>10.8</td></tr><tr><td>Max Percolation (l/s)</td><td>10.2</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>138.990</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 12.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>3.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>10.2</td></tr><tr><td>Max Percolation (l/s)</td><td>8.5</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>138.425</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIS TANK, DS/PN: 13.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>6.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>9.6</td></tr><tr><td>Max Percolation (l/s)</td><td>16.0</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>138.480</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 14.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>3.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>9.6</td></tr><tr><td>Max Percolation (l/s)</td><td>8.0</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>138.700</td><td>Membrane Depth (mm)</td><td>0</td></tr></table>			Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	5.5	Membrane Percolation (mm/hr)	1000	Length (m)	5.7	Max Percolation (l/s)	8.7	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	139.875	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	5.5	Membrane Percolation (mm/hr)	1000	Length (m)	5.7	Max Percolation (l/s)	8.7	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	139.350	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	5.5	Membrane Percolation (mm/hr)	1000	Length (m)	6.0	Max Percolation (l/s)	9.2	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	138.890	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.4	Membrane Percolation (mm/hr)	1000	Length (m)	10.8	Max Percolation (l/s)	10.2	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	138.990	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.0	Membrane Percolation (mm/hr)	1000	Length (m)	10.2	Max Percolation (l/s)	8.5	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	138.425	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	9.6	Max Percolation (l/s)	16.0	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	138.480	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.0	Membrane Percolation (mm/hr)	1000	Length (m)	9.6	Max Percolation (l/s)	8.0	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	138.700	Membrane Depth (mm)	0
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	5.5																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	5.7																																																																																																																																																																							
Max Percolation (l/s)	8.7	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	139.875	Membrane Depth (mm)	0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	5.5																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	5.7																																																																																																																																																																							
Max Percolation (l/s)	8.7	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	139.350	Membrane Depth (mm)	0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	5.5																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	6.0																																																																																																																																																																							
Max Percolation (l/s)	9.2	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	138.890	Membrane Depth (mm)	0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.4																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	10.8																																																																																																																																																																							
Max Percolation (l/s)	10.2	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	138.990	Membrane Depth (mm)	0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.0																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	10.2																																																																																																																																																																							
Max Percolation (l/s)	8.5	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	138.425	Membrane Depth (mm)	0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	9.6																																																																																																																																																																							
Max Percolation (l/s)	16.0	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	138.480	Membrane Depth (mm)	0																																																																																																																																																																							
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.0																																																																																																																																																																							
Membrane Percolation (mm/hr)	1000	Length (m)	9.6																																																																																																																																																																							
Max Percolation (l/s)	8.0	Slope (1:X)	0.0																																																																																																																																																																							
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																																																																							
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																																							
Invert Level (m)	138.700	Membrane Depth (mm)	0																																																																																																																																																																							
©1982-2019 Innovyze																																																																																																																																																																										

Jubb Consulting Engineers Limited		Page 33
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 15.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.0 Membrane Percolation (mm/hr) 1000 Length (m) 11.7 Max Percolation (l/s) 9.8 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 138.820 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 16.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 6.0 Membrane Percolation (mm/hr) 1000 Length (m) 11.2 Max Percolation (l/s) 18.7 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 138.610 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 17.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 6.0 Membrane Percolation (mm/hr) 1000 Length (m) 11.0 Max Percolation (l/s) 18.3 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 138.375 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 18.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 6.0 Membrane Percolation (mm/hr) 1000 Length (m) 9.6 Max Percolation (l/s) 16.0 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 138.260 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 19.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 9.9 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 139.920 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 20.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 9.9 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 140.020 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 21.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 9.9 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 140.285 Membrane Depth (mm) 0		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 34
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 22.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 9.9 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 140.635 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 23.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 6.0 Membrane Percolation (mm/hr) 1000 Length (m) 9.6 Max Percolation (l/s) 16.0 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 140.875 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 24.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 5.5 Membrane Percolation (mm/hr) 1000 Length (m) 6.2 Max Percolation (l/s) 9.5 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.275 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 25.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 5.5 Membrane Percolation (mm/hr) 1000 Length (m) 6.2 Max Percolation (l/s) 9.5 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.440 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 26.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 11.7 Max Percolation (l/s) 10.7 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 142.090 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 27.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 13.0 Max Percolation (l/s) 11.9 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 142.007 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 28.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 6.3 Membrane Percolation (mm/hr) 1000 Length (m) 11.2 Max Percolation (l/s) 19.6 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.285 Membrane Depth (mm) 0		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 35
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 29.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.0 Membrane Percolation (mm/hr) 1000 Length (m) 11.3 Max Percolation (l/s) 9.4 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 140.849 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 30.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 6.4 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 19.2 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.815 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 31.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.4 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 10.2 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 142.020 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 32.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.4 Membrane Percolation (mm/hr) 1000 Length (m) 10.8 Max Percolation (l/s) 10.2 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.655 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 34.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.0 Membrane Percolation (mm/hr) 1000 Length (m) 9.6 Max Percolation (l/s) 8.0 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.085 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 35.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.0 Membrane Percolation (mm/hr) 1000 Length (m) 9.6 Max Percolation (l/s) 8.0 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.170 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 36.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.0 Membrane Percolation (mm/hr) 1000 Length (m) 10.5 Max Percolation (l/s) 8.8 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.045 Membrane Depth (mm) 0		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 36
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 37.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.0 Membrane Percolation (mm/hr) 1000 Length (m) 10.3 Max Percolation (l/s) 8.6 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 141.120 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 38.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 9.0 Membrane Percolation (mm/hr) 1000 Length (m) 10.0 Max Percolation (l/s) 25.0 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 139.840 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 39.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 9.0 Membrane Percolation (mm/hr) 1000 Length (m) 10.6 Max Percolation (l/s) 26.5 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 137.710 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 40.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 3.3 Membrane Percolation (mm/hr) 1000 Length (m) 17.6 Max Percolation (l/s) 16.1 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 139.370 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 41.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 5.5 Membrane Percolation (mm/hr) 1000 Length (m) 5.7 Max Percolation (l/s) 8.7 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 139.180 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 42.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 5.5 Membrane Percolation (mm/hr) 1000 Length (m) 5.7 Max Percolation (l/s) 8.7 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 138.825 Membrane Depth (mm) 0 <u>Porous Car Park Manhole: DIST TANK, DS/PN: 43.000</u> Infiltration Coefficient Base (m/hr) 0.01080 Width (m) 5.5 Membrane Percolation (mm/hr) 1000 Length (m) 5.7 Max Percolation (l/s) 8.7 Slope (1:X) 0.0 Safety Factor 5.0 Depression Storage (mm) 5 Porosity 0.30 Evaporation (mm/day) 3 Invert Level (m) 138.335 Membrane Depth (mm) 0		
©1982-2019 Innovyze		

Jubb Consulting Engineers Limited		Page 37																																																																																																																																
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC																																																																																																																																	
Date 15/07/2025	Designed by EPH																																																																																																																																	
File SWD NETWORK - POND A - 100 YR...	Checked by																																																																																																																																	
Innovyze	Network 2019.1																																																																																																																																	
<u>Porous Car Park Manhole: DIST TANK, DS/PN: 44.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>6.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>10.0</td></tr><tr><td>Max Percolation (l/s)</td><td>16.7</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>137.390</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 45.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>6.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>9.6</td></tr><tr><td>Max Percolation (l/s)</td><td>16.0</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>137.390</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 46.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>6.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>9.6</td></tr><tr><td>Max Percolation (l/s)</td><td>16.0</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>137.210</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 47.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>6.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>9.6</td></tr><tr><td>Max Percolation (l/s)</td><td>16.0</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>136.860</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Porous Car Park Manhole: DIST TANK, DS/PN: 49.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.01080</td><td>Width (m)</td><td>3.3</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>10.7</td></tr><tr><td>Max Percolation (l/s)</td><td>9.8</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>5.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>136.500</td><td>Membrane Depth (mm)</td><td>0</td></tr></table> <u>Tank or Pond Manhole: POND, DS/PN: 1.026</u> Invert Level (m) 135.278 <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th></tr><tr><td>0.000</td><td>1637.2</td><td>1.300</td><td>2298.1</td></tr></table>			Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	10.0	Max Percolation (l/s)	16.7	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	137.390	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	9.6	Max Percolation (l/s)	16.0	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	137.390	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	9.6	Max Percolation (l/s)	16.0	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	137.210	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0	Membrane Percolation (mm/hr)	1000	Length (m)	9.6	Max Percolation (l/s)	16.0	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	136.860	Membrane Depth (mm)	0	Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.3	Membrane Percolation (mm/hr)	1000	Length (m)	10.7	Max Percolation (l/s)	9.8	Slope (1:X)	0.0	Safety Factor	5.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	136.500	Membrane Depth (mm)	0	Depth (m)	Area (m²)	Depth (m)	Area (m²)	0.000	1637.2	1.300	2298.1
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0																																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	10.0																																																																																																																															
Max Percolation (l/s)	16.7	Slope (1:X)	0.0																																																																																																																															
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																															
Invert Level (m)	137.390	Membrane Depth (mm)	0																																																																																																																															
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0																																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	9.6																																																																																																																															
Max Percolation (l/s)	16.0	Slope (1:X)	0.0																																																																																																																															
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																															
Invert Level (m)	137.390	Membrane Depth (mm)	0																																																																																																																															
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0																																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	9.6																																																																																																																															
Max Percolation (l/s)	16.0	Slope (1:X)	0.0																																																																																																																															
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																															
Invert Level (m)	137.210	Membrane Depth (mm)	0																																																																																																																															
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	6.0																																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	9.6																																																																																																																															
Max Percolation (l/s)	16.0	Slope (1:X)	0.0																																																																																																																															
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																															
Invert Level (m)	136.860	Membrane Depth (mm)	0																																																																																																																															
Infiltration Coefficient Base (m/hr)	0.01080	Width (m)	3.3																																																																																																																															
Membrane Percolation (mm/hr)	1000	Length (m)	10.7																																																																																																																															
Max Percolation (l/s)	9.8	Slope (1:X)	0.0																																																																																																																															
Safety Factor	5.0	Depression Storage (mm)	5																																																																																																																															
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																															
Invert Level (m)	136.500	Membrane Depth (mm)	0																																																																																																																															
Depth (m)	Area (m²)	Depth (m)	Area (m²)																																																																																																																															
0.000	1637.2	1.300	2298.1																																																																																																																															
©1982-2019 Innovyze																																																																																																																																		

Jubb Consulting Engineers Limited

Unit 1, Ensign House
Parkway Court, Longbridge Road
Plymouth, PL6 8LR

Date 15/07/2025
File SWD NETWORK - POND A - 100 YR...

Innovyze

VICTORIA ROAD
SWD NETWORK- POND A
100 YEAR PLUS 45 CC

Designed by EPH
Checked by

Network 2019.1

Page 38



Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor

1.000

Additional Flow - % of Total Flow

0.000

Hot Start (mins)

0

MADD Factor * 10m³/ha Storage

0.000

Hot Start Level (mm)

0

Inlet Coefficient

0.800

Manhole Headloss Coeff (Global)

0.500

Flow per Person per Day (l/per/day)

0.000

Foul Sewage per hectare (l/s)

0.000

Number of Input Hydrographs

0

Number of Offline Controls

0

Number of Time/Area Diagrams

0

Number of Online Controls

48

Number of Storage Structures

48

Number of Real Time Controls

0

Synthetic Rainfall Details

Rainfall Model

FEH

D3 (1km)

0.273

FEH Rainfall Version

1999

E (1km)

0.289

Site Location

GB 386850 145550 ST 86850 45550

F (1km)

2.484

C (1km)

-0.027

Cv (Summer)

0.750

D1 (1km)

0.363

Cv (Winter)

0.840

D2 (1km)

0.417

Margin for Flood Risk Warning (mm)

300.0

Analysis Timestep

2.5 Second Increment (Extended)

DTS Status

OFF

DVD Status

ON

Inertia Status

ON

Profile(s)

Summer and Winter

Duration(s) (mins)

15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Period(s) (years)

100

Climate Change (%)

45

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				138.725
1.001	SIC 206-1	120 Winter	100	+45%	100/15 Summer				138.724
1.002	SMH 14	15 Winter	100	+45%					137.305
2.000	DIST TANK 1	60 Winter	100	+45%	100/15 Summer				138.659
2.001	SIC 207-1	15 Winter	100	+45%	100/15 Summer				138.646
1.003	JUNCTION	30 Winter	100	+45%					137.085
1.004	SMH 13	15 Winter	100	+45%	100/15 Summer				138.707
3.000	DIST TK 1	60 Winter	100	+45%	100/15 Summer				138.761
3.001	SIC 208-1	60 Winter	100	+45%	100/15 Summer				138.779
1.005	JUNCTION	30 Winter	100	+45%					137.015
4.000	DIST TANK 1	60 Winter	100	+45%	100/15 Summer				138.906
4.001	SIC 209-1	60 Winter	100	+45%	100/15 Summer				138.924
1.006	JUNCTION	60 Winter	100	+45%					136.906
5.000	DIST TANK 1	60 Winter	100	+45%	100/15 Summer				138.819
5.001	SIC 210-1	30 Winter	100	+45%	100/15 Summer				138.833
1.007	JUNCTION	60 Winter	100	+45%					136.803
1.008	SMH 12	15 Winter	100	+45%	100/15 Summer				138.562
6.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				141.726
6.001	SIC 188-1	120 Winter	100	+45%	100/15 Summer				141.753
6.002	SMH 22	15 Winter	100	+45%					140.366
7.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				140.900
7.001	SIC 187-1	60 Winter	100	+45%	100/15 Summer				140.910
6.003	JUNCTION	15 Winter	100	+45%					139.906
8.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				140.380
8.001	SIC 186-1	60 Winter	100	+45%	100/15 Summer				140.390
6.004	JUNCTION	15 Winter	100	+45%					139.457
9.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.855
9.001	SIC 185-1	60 Winter	100	+45%	100/15 Summer				139.865
6.005	SMH 21	15 Winter	100	+45%	100/15 Summer				138.985
10.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.365
10.001	SIC 205-1	60 Winter	100	+45%	100/15 Summer				139.377
6.006	SMH 20	15 Winter	100	+45%	100/15 Summer				138.858

©1982-2019 Innovyze

Jubb Consulting Engineers Limited		Page 39
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Surcharged		Flooded		Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)			
1.000	DIST TANK	0.355	0.000	0.20		0.8	FLOOD RISK	
1.001	SIC 206-1	0.374	0.000	0.06		0.9	FLOOD RISK	
1.002	SMH 14	0.000	0.000	0.59		34.1	SURCHARGED*	
2.000	DIST TANK 1	0.299	0.000	0.21		0.8	FLOOD RISK	
2.001	SIC 207-1	0.306	0.000	0.03		0.8	FLOOD RISK	
1.003	JUNCTION	0.000	0.000	0.76		22.7	SURCHARGED*	
1.004	SMH 13	1.659	0.000	0.40		24.4	FLOOD RISK	
3.000	DIST TK 1	0.341	0.000	0.22		0.9	FLOOD RISK	
3.001	SIC 208-1	0.379	0.000	0.04		0.9	FLOOD RISK	
1.005	JUNCTION	0.000	0.000	0.36		29.6	SURCHARGED*	
4.000	DIST TANK 1	0.341	0.000	0.22		0.9	FLOOD RISK	
4.001	SIC 209-1	0.379	0.000	0.03		0.9	FLOOD RISK	
1.006	JUNCTION	0.000	0.000	0.35		28.1	SURCHARGED*	
5.000	DIST TANK 1	0.169	0.000	0.17		0.7	SURCHARGED	
5.001	SIC 210-1	0.203	0.000	0.02		0.7	SURCHARGED	
1.007	JUNCTION	0.000	0.000	0.37		31.4	SURCHARGED*	
1.008	SMH 12	1.876	0.000	0.74		50.1	SURCHARGED	
6.000	DIST TANK	0.466	0.000	0.26		1.0	FLOOD RISK	
6.001	SIC 188-1	0.513	0.000	0.06		1.0	SURCHARGED	
6.002	SMH 22	-0.084	0.000	0.40		13.3	OK	
7.000	DIST TANK	0.405	0.000	0.24		0.9	SURCHARGED	
7.001	SIC 187-1	0.435	0.000	0.06		0.9	SURCHARGED	
6.003	JUNCTION	-0.054	0.000	0.73		26.7	OK*	
8.000	DIST TANK	0.405	0.000	0.24		0.9	SURCHARGED	
8.001	SIC 186-1	0.435	0.000	0.06		0.9	SURCHARGED	
6.004	JUNCTION	-0.053	0.000	0.75		27.3	OK*	
9.000	DIST TANK	0.405	0.000	0.24		0.9	SURCHARGED	
9.001	SIC 185-1	0.435	0.000	0.06		0.9	SURCHARGED	
6.005	SMH 21	0.085	0.000	0.97		26.9	SURCHARGED	
10.000	DIST TANK	0.375	0.000	0.17		0.9	SURCHARGED	
10.001	SIC 205-1	0.427	0.000	0.06		0.9	SURCHARGED	
6.006	SMH 20	0.408	0.000	1.05		26.1	SURCHARGED	

Jubb Consulting Engineers Limited									Page 40	
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR					VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC					
Date 15/07/2025					Designed by EPH					
File SWD NETWORK - POND A - 100 YR...					Checked by					
Innovyze					Network 2019.1					
<u>Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>										
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)
11.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.429	0.339
11.001	SIC 204-1	60 Winter	100	+45%	100/15 Summer				139.441	0.371
6.007	JUNCTION	30 Winter	100	+45%					138.290	0.000
6.008	SMH 19	15 Winter	100	+45%	100/15 Summer				138.705	0.644
1.009	SMH 11	15 Winter	100	+45%	100/15 Summer				138.547	1.935
12.000	DIST TANK	15 Winter	100	+45%	100/15 Summer				138.727	0.202
12.001	SIC 222-1	15 Winter	100	+45%	100/15 Summer				138.724	0.229
12.002	SMH 18	15 Winter	100	+45%	100/15 Summer				138.745	0.705
13.000	DIS TANK	15 Winter	100	+45%	100/15 Summer				138.815	0.235
13.001	SIC 220-1	30 Winter	100	+45%	100/15 Summer				138.810	0.250
12.003	JUNCTION	15 Winter	100	+45%					137.849	0.000
14.000	DIST TANK	15 Winter	100	+45%	100/15 Summer				139.279	0.479
14.001	SIC 219-1	15 Winter	100	+45%	100/15 Summer				139.266	0.486
12.004	JUNCTION	30 Winter	100	+45%					137.658	0.000
12.005	SMH 17	15 Winter	100	+45%	100/15 Summer				138.686	1.227
15.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.236	0.316
15.001	SIC 136-1	60 Winter	100	+45%	100/15 Summer				139.237	0.337
12.006	JUNCTION	30 Winter	100	+45%					137.281	0.000
16.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				138.987	0.277
16.001	SIC 138-1	60 Winter	100	+45%	100/15 Summer				139.008	0.318
12.007	JUNCTION	30 Winter	100	+45%					137.032	0.000
17.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				138.758	0.283
17.001	SIC 140-1	60 Winter	100	+45%	100/15 Summer				138.775	0.320
12.008	JUNCTION	60 Winter	100	+45%					136.746	0.000
18.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				138.504	0.144
18.001	SIC 141-1	30 Winter	100	+45%	100/15 Summer				138.503	0.163
1.010	SMH 10	15 Winter	100	+45%	100/15 Summer				138.431	2.054
1.011	SMH 9	15 Winter	100	+45%	100/15 Summer				138.414	2.061
19.000	DIST TANK	15 Winter	100	+45%	100/15 Summer				140.297	0.277
19.001	SIC 173-1	15 Winter	100	+45%	100/15 Summer				140.304	0.304
19.002	SMH 32	15 Winter	100	+45%	100/15 Summer				140.587	1.092
20.000	DIST TANK	15 Winter	100	+45%	100/15 Summer				140.355	0.235
20.001	SIC 172-1	60 Winter	100	+45%	100/15 Summer				140.370	0.270
19.003	JUNCTION	30 Winter	100	+45%					139.410	0.000
21.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				140.772	0.387
21.001	SIC 171-1	60 Winter	100	+45%	100/15 Summer				140.792	0.427
19.004	SMH 31	15 Winter	100	+45%	100/15 Summer				140.518	1.216
22.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.046	0.311
22.001	SIC 170-1	60 Winter	100	+45%	100/15 Summer				141.064	0.349
19.005	JUNCTION	30 Winter	100	+45%					139.212	0.000
23.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.092	0.117
23.001	SIC 167-1	60 Summer	100	+45%	100/15 Summer				141.088	0.133
19.006	JUNCTION	60 Winter	100	+45%					139.092	0.000
19.007	SMH 30	15 Winter	100	+45%	100/15 Summer				140.169	1.260
24.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.696	0.321
24.001	SIC 174-1	30 Winter	100	+45%	100/15 Summer				141.692	0.357
24.002	SMH 34	15 Winter	100	+45%	100/15 Winter				141.275	0.000
25.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.861	0.321
25.001	SIC 175-1	30 Winter	100	+45%	100/15 Summer				141.847	0.347
24.003	JUNCTION	15 Winter	100	+45%					141.195	0.000
24.004	SMH 33	15 Winter	100	+45%					140.950	-0.054
19.008	SMH 29	15 Winter	100	+45%	100/15 Summer				140.007	1.207
26.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				142.549	0.359
26.001	SIC 176-1	60 Winter	100	+45%	100/15 Summer				142.550	0.380
19.009	JUNCTION	60 Winter	100	+45%					138.650	0.000
27.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				142.357	0.250
27.001	SIC 169-1	30 Winter	100	+45%	100/15 Summer				142.359	0.272
19.010	SMH 28	15 Winter	100	+45%	100/15 Summer				139.802	1.196
28.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				141.742	0.357
28.001	SIC 178-1	120 Winter	100	+45%	100/15 Summer				141.769	0.404
19.011	JUNCTION	60 Winter	100	+45%					138.536	0.000
29.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.156	0.207
29.001	SIC 166-1	60 Winter	100	+45%	100/15 Summer				141.158	0.229
30.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				142.281	0.366
©1982-2019 Innovyze										

Jubb Consulting Engineers Limited

Unit 1, Ensign House
Parkway Court, Longbridge Road
Plymouth, PL6 8LR

Date 15/07/2025
File SWD NETWORK - POND A - 100 YR...

Innovyze

VICTORIA ROAD
SWD NETWORK- POND A
100 YEAR PLUS 45 CC

Designed by EPH
Checked by

Network 2019.1

Page 41



Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
11.000	DIST TANK	0.000	0.22		0.9	FLOOD RISK	
11.001	SIC 204-1	0.000	0.05		0.9	FLOOD RISK	
6.007	JUNCTION	0.000	0.71		21.2	SURCHARGED*	
6.008	SMH 19	0.000	0.60		36.3	SURCHARGED	
1.009	SMH 11	0.000	0.72		92.4	SURCHARGED	
12.000	DIST TANK	0.000	0.56		2.7	SURCHARGED	
12.001	SIC 222-1	0.000	0.16		2.8	SURCHARGED	
12.002	SMH 18	0.000	0.41		7.5	SURCHARGED	
13.000	DIS TANK	0.000	0.73		2.9	SURCHARGED	
13.001	SIC 220-1	0.000	0.15		2.8	SURCHARGED	
12.003	JUNCTION	0.000	0.79		15.6	SURCHARGED*	
14.000	DIST TANK	0.000	0.99		3.9	FLOOD RISK	
14.001	SIC 219-1	0.000	0.16		3.9	FLOOD RISK	
12.004	JUNCTION	0.000	1.06		21.2	SURCHARGED*	
12.005	SMH 17	0.000	0.57		31.5	SURCHARGED	
15.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	
15.001	SIC 136-1	0.000	0.03		0.8	FLOOD RISK	
12.006	JUNCTION	0.000	0.54		35.2	SURCHARGED*	
16.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
16.001	SIC 138-1	0.000	0.03		0.8	SURCHARGED	
12.007	JUNCTION	0.000	0.82		53.7	SURCHARGED*	
17.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	
17.001	SIC 140-1	0.000	0.03		0.8	SURCHARGED	
12.008	JUNCTION	0.000	0.71		46.8	SURCHARGED*	
18.000	DIST TANK	0.000	0.17		0.6	SURCHARGED	
18.001	SIC 141-1	0.000	0.02		0.6	SURCHARGED	
1.010	SMH 10	0.000	0.95		161.4	SURCHARGED	
1.011	SMH 9	0.000	0.77		199.6	SURCHARGED	
19.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
19.001	SIC 173-1	0.000	0.05		0.8	FLOOD RISK	
19.002	SMH 32	0.000	0.66		10.3	FLOOD RISK	
20.000	DIST TANK	0.000	0.20		0.8	SURCHARGED	
20.001	SIC 172-1	0.000	0.04		0.8	FLOOD RISK	
19.003	JUNCTION	0.000	0.82		14.6	SURCHARGED*	
21.000	DIST TANK	0.000	0.24		0.9	FLOOD RISK	
21.001	SIC 171-1	0.000	0.04		0.9	FLOOD RISK	
19.004	SMH 31	0.000	1.08		17.0	SURCHARGED	
22.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	
22.001	SIC 170-1	0.000	0.03		0.8	FLOOD RISK	
19.005	JUNCTION	0.000	1.08		19.4	SURCHARGED*	
23.000	DIST TANK	0.000	0.16		0.6	SURCHARGED	
23.001	SIC 167-1	0.000	0.02		0.6	SURCHARGED	
19.006	JUNCTION	0.000	1.12		20.2	SURCHARGED*	
19.007	SMH 30	0.000	2.00		32.2	SURCHARGED	
24.000	DIST TANK	0.000	0.16		0.9	SURCHARGED	
24.001	SIC 174-1	0.000	0.13		0.9	SURCHARGED	
24.002	SMH 34	0.000	0.59		9.1	SURCHARGED	
25.000	DIST TANK	0.000	0.16		0.9	SURCHARGED	
25.001	SIC 175-1	0.000	0.06		0.9	SURCHARGED	
24.003	JUNCTION	0.000	1.12		20.0	SURCHARGED*	
24.004	SMH 33	0.000	0.74		20.0	OK	
19.008	SMH 29	0.000	0.97		44.7	SURCHARGED	
26.000	DIST TANK	0.000	0.23		0.9	FLOOD RISK	
26.001	SIC 176-1	0.000	0.02		0.9	FLOOD RISK	
19.009	JUNCTION	0.000	1.16		34.6	SURCHARGED*	
27.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
27.001	SIC 169-1	0.000	0.03		0.8	FLOOD RISK	
19.010	SMH 28	0.000	1.43		53.5	SURCHARGED	
28.000	DIST TANK	0.000	0.24		0.9	FLOOD RISK	
28.001	SIC 178-1	0.000	0.03		0.9	FLOOD RISK	
19.011	JUNCTION	0.000	0.98		50.8	SURCHARGED*	
29.000	DIST TANK	0.000	0.18		0.7	SURCHARGED	
29.001	SIC 166-1	0.000	0.03		0.7	SURCHARGED	

©1982-2019 Innovyze

Jubb Consulting Engineers Limited		Page 42
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...	Designed by EPH Checked by	
Innovyze	Network 2019.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Flooded Volume (m ³)	Flow / Overflow Cap. (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
30.000	DIST TANK	0.000	0.23	0.9	SURCHARGED	

Jubb Consulting Engineers Limited									Page 43	
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR					VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC					
Date 15/07/2025 File SWD NETWORK - POND A - 100 YR...					Designed by EPH Checked by					
Innovyze					Network 2019.1					
<u>Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>										
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	Surcharged Depth (m)
30.001	SIC 184-1	60 Winter	100	+45%	100/15 Summer				142.296	0.401
30.002	SMH 27	15 Winter	100	+45%					141.674	-0.101
31.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				142.382	0.262
31.001	SIC 182-1	60 Winter	100	+45%	100/15 Summer				142.400	0.300
30.003	SMH 26	15 Winter	100	+45%					141.514	-0.076
30.004	SMH 25	15 Winter	100	+45%					141.407	-0.078
32.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				142.096	0.341
32.001	SIC 181-1	60 Winter	100	+45%	100/15 Summer				142.113	0.378
30.005	JUNCTION	15 Winter	100	+45%					141.348	-0.054
33.000	HD CP1	15 Summer	100	+45%	100/15 Summer				141.100	0.140
30.006	SMH 24	15 Winter	100	+45%					140.820	-0.040
34.000	DIST TANK	30 Winter	100	+45%	100/15 Summer				141.437	0.252
34.001	SIC 190-1	30 Winter	100	+45%	100/15 Summer				141.455	0.290
30.007	JUNCTION	30 Winter	100	+45%					139.990	0.000
35.000	DIST TANK	30 Winter	100	+45%	100/15 Summer				141.522	0.252
35.001	SIC 180-1	30 Winter	100	+45%	100/15 Summer				141.540	0.290
30.008	JUNCTION	15 Winter	100	+45%					139.951	0.000
36.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.372	0.227
36.001	SIC 191-1	30 Winter	100	+45%	100/15 Summer				141.382	0.257
30.009	JUNCTION	15 Winter	100	+45%					139.521	0.000
37.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				141.451	0.231
37.001	SIC 179-1	30 Winter	100	+45%	100/15 Summer				141.469	0.269
30.010	JUNCTION	15 Winter	100	+45%					139.427	0.000
19.012	SMH 23	15 Winter	100	+45%	100/15 Summer				139.457	1.067
38.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				140.056	0.116
38.001	SIC 165-1	180 Winter	100	+45%	100/15 Summer				140.068	0.148
19.013	JUNCTION	60 Winter	100	+45%					138.236	0.000
1.012	SMH 8	15 Winter	100	+45%	100/15 Summer				138.382	2.091
1.013	SMH 7	15 Winter	100	+45%	100/15 Summer				138.261	2.022
1.014	SMH 6	15 Winter	100	+45%	100/15 Summer				138.115	1.945
39.000	DIST TANK	120 Winter	100	+45%	100/15 Summer				138.135	0.325
39.001	SIC 146-1	120 Winter	100	+45%	100/15 Summer				138.159	0.369
1.015	JUNCTION	30 Winter	100	+45%					136.155	0.000
40.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.744	0.274
40.001	SIC 152-1	180 Winter	100	+45%	100/15 Summer				139.741	0.291
41.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.639	0.359
41.001	SIC 153-1	60 Winter	100	+45%	100/15 Summer				139.656	0.396
40.002	SMH 36	60 Winter	100	+45%					138.498	-0.127
42.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				139.284	0.359
42.001	SIC 154-1	60 Winter	100	+45%	100/15 Summer				139.301	0.396
40.003	JUNCTION	60 Winter	100	+45%					138.155	-0.122
43.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				138.794	0.359
43.001	SIC 155-1	60 Winter	100	+45%	100/15 Summer				138.811	0.396
40.004	JUNCTION	15 Winter	100	+45%					137.809	0.000
40.005	SMH 35	15 Winter	100	+45%	100/15 Summer				137.949	0.376
1.016	SMH 5	15 Winter	100	+45%	100/15 Summer				137.795	1.662
44.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				137.780	0.290
44.001	SIC 148-1	180 Winter	100	+45%	100/15 Summer				137.785	0.315
1.017	JUNCTION	30 Winter	100	+45%					136.119	0.000
1.018	SMH 4	15 Winter	100	+45%	100/15 Summer				137.446	1.355
45.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				137.794	0.304
45.001	SIC 150-1	180 Winter	100	+45%	100/15 Summer				137.798	0.328
1.019	JUNCTION	360 Winter	100	+45%					136.082	0.000
1.020	SMH 3	15 Winter	100	+45%	100/15 Summer				137.086	1.030
46.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				137.614	0.304
46.001	SIC 111-1	180 Winter	100	+45%	100/15 Summer				137.618	0.328
1.021	JUNCTION	120 Winter	100	+45%					136.046	0.000
47.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				137.237	0.277
47.001	SIC 113-1	180 Winter	100	+45%	100/15 Summer				137.239	0.299
1.022	JUNCTION	120 Winter	100	+45%					136.009	0.000
48.000	SWMH 114-3	15 Winter	100	+45%	100/15 Summer				137.664	0.039
48.001	SWMH 114-2	15 Winter	100	+45%	100/15 Winter				136.670	0.005
49.000	DIST TANK	60 Winter	100	+45%	100/15 Summer				136.914	0.314
49.001	SIC 115-1	30 Winter	100	+45%	100/15 Summer				136.924	0.344
©1982-2019 Innovyze										

Jubb Consulting Engineers Limited		Page 44
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
30.001	SIC 184-1	0.000	0.12		0.9	SURCHARGED	
30.002	SMH 27	0.000	0.23		4.2	OK	
31.000	DIST TANK	0.000	0.20		0.8	SURCHARGED	
31.001	SIC 182-1	0.000	0.05		0.8	SURCHARGED	
30.003	SMH 26	0.000	0.48		8.4	OK	
30.004	SMH 25	0.000	0.46		8.3	OK	
32.000	DIST TANK	0.000	0.22		0.9	SURCHARGED	
32.001	SIC 181-1	0.000	0.07		0.9	SURCHARGED	
30.005	JUNCTION	0.000	0.73		23.3	OK*	
33.000	HD CP1	0.000	1.56		24.6	SURCHARGED	
30.006	SMH 24	0.000	0.68		63.0	OK	
34.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
34.001	SIC 190-1	0.000	0.03		0.8	FLOOD RISK	
30.007	JUNCTION	0.000	1.47		44.0	SURCHARGED*	
35.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
35.001	SIC 180-1	0.000	0.03		0.8	SURCHARGED	
30.008	JUNCTION	0.000	0.58		53.6	SURCHARGED*	
36.000	DIST TANK	0.000	0.19		0.8	SURCHARGED	
36.001	SIC 191-1	0.000	0.03		0.7	SURCHARGED	
30.009	JUNCTION	0.000	1.49		64.3	SURCHARGED*	
37.000	DIST TANK	0.000	0.19		0.8	SURCHARGED	
37.001	SIC 179-1	0.000	0.03		0.8	SURCHARGED	
30.010	JUNCTION	0.000	0.79		80.4	SURCHARGED*	
19.012	SMH 23	0.000	1.62		151.5	SURCHARGED	
38.000	DIST TANK	0.000	0.16		0.6	SURCHARGED	
38.001	SIC 165-1	0.000	0.02		0.6	SURCHARGED	
19.013	JUNCTION	0.000	1.09		121.2	SURCHARGED*	
1.012	SMH 8	0.000	1.53		384.4	SURCHARGED	
1.013	SMH 7	0.000	1.56		412.1	SURCHARGED	
1.014	SMH 6	0.000	2.11		405.4	SURCHARGED	
39.000	DIST TANK	0.000	0.23		0.9	FLOOD RISK	
39.001	SIC 146-1	0.000	0.03		0.9	FLOOD RISK	
1.015	JUNCTION	0.000	1.34		358.4	SURCHARGED*	
40.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
40.001	SIC 152-1	0.000	0.04		0.8	SURCHARGED	
41.000	DIST TANK	0.000	0.23		0.9	FLOOD RISK	
41.001	SIC 153-1	0.000	0.04		0.9	FLOOD RISK	
40.002	SMH 36	0.000	0.06		1.7	OK	
42.000	DIST TANK	0.000	0.23		0.9	FLOOD RISK	
42.001	SIC 154-1	0.000	0.04		0.9	FLOOD RISK	
40.003	JUNCTION	0.000	0.08		2.6	OK*	
43.000	DIST TANK	0.000	0.23		0.9	FLOOD RISK	
43.001	SIC 155-1	0.000	0.04		0.9	FLOOD RISK	
40.004	JUNCTION	0.000	0.22		6.6	SURCHARGED*	
40.005	SMH 35	0.000	0.70		31.0	SURCHARGED	
1.016	SMH 5	0.000	2.06		423.6	SURCHARGED	
44.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	
44.001	SIC 148-1	0.000	0.03		0.8	SURCHARGED	
1.017	JUNCTION	0.000	1.47		385.7	SURCHARGED*	
1.018	SMH 4	0.000	1.95		431.9	SURCHARGED	
45.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	
45.001	SIC 150-1	0.000	0.03		0.8	FLOOD RISK	
1.019	JUNCTION	0.000	0.45		116.0	SURCHARGED*	
1.020	SMH 3	0.000	2.01		435.1	SURCHARGED	
46.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	
46.001	SIC 111-1	0.000	0.03		0.8	FLOOD RISK	
1.021	JUNCTION	0.000	0.86		238.7	SURCHARGED*	
47.000	DIST TANK	0.000	0.20		0.8	FLOOD RISK	
47.001	SIC 113-1	0.000	0.04		0.8	FLOOD RISK	
1.022	JUNCTION	0.000	0.84		239.1	SURCHARGED*	
48.000	SWMH 114-3	0.000	1.01		27.4	SURCHARGED	
48.001	SWMH 114-2	0.000	0.76		54.5	SURCHARGED	
49.000	DIST TANK	0.000	0.21		0.8	FLOOD RISK	

Jubb Consulting Engineers Limited				Page 45																	
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR		VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC																			
Date 15/07/2025		Designed by EPH																			
File SWD NETWORK - POND A - 100 YR...		Checked by																			
Innovyze		Network 2019.1																			
<u>Summary of Critical Results by Maximum Level (Rank 1) for Storm</u> <table><thead><tr><th>PN</th><th>US/MH Name</th><th>Flooded Volume (m³)</th><th>Flow / Cap.</th><th>Overflow (l/s)</th><th>Pipe Flow (l/s)</th><th>Status</th><th>Level Exceeded</th></tr></thead><tbody><tr><td>49.001</td><td>SIC 115-1</td><td>0.000</td><td>0.05</td><td></td><td>0.8</td><td>FLOOD RISK</td><td></td></tr></tbody></table>						PN	US/MH Name	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded	49.001	SIC 115-1	0.000	0.05		0.8	FLOOD RISK	
PN	US/MH Name	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded														
49.001	SIC 115-1	0.000	0.05		0.8	FLOOD RISK															
©1982-2019 Innovyze																					

Jubb Consulting Engineers Limited		Page 46
Unit 1, Ensign House Parkway Court, Longbridge Road Plymouth, PL6 8LR	VICTORIA ROAD SWD NETWORK- POND A 100 YEAR PLUS 45 CC	
Date 15/07/2025	Designed by EPH	
File SWD NETWORK - POND A - 100 YR...	Checked by	
Innovyze	Network 2019.1	

Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
48.002	SWMH 114-1	15 Winter	100	+45%	100/15 Summer				136.577
1.023	SMH 2	15 Winter	100	+45%	100/15 Summer				136.522
50.000	DIST TANK	15 Summer	100	+45%	100/15 Summer				136.626
50.001	SIC 116-1	15 Summer	100	+45%					136.421
1.024	JUNCTION	480 Winter	100	+45%					135.951
1.025	SMH 1	2880 Winter	100	+45%	100/15 Summer				136.280
1.026	POND	2880 Winter	100	+45%	100/30 Winter				136.279
1.027	FC	2880 Winter	100	+45%					135.224

PN	US/MH Name	Surcharged		Flooded		Pipe		Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)			
48.002	SWMH 114-1	0.427	0.000	0.88		53.0		SURCHARGED	
1.023	SMH 2	0.553	0.000	2.69		466.4		SURCHARGED	
50.000	DIST TANK	0.156	0.000	3.00		11.8		SURCHARGED	
50.001	SIC 116-1	-0.029	0.000	0.85		11.8		OK	
1.024	JUNCTION	0.000	0.000	0.36		106.6		SURCHARGED*	
1.025	SMH 1	0.371	0.000	0.18		35.0		SURCHARGED	
1.026	POND	0.701	0.000	0.05		3.5		FLOOD RISK	
1.027	FC	-0.126	0.000	0.06		3.5		OK	