



Key

- Proposed new dwelling
- Proposed new dwelling grassed area
- Proposed new dwelling drive and path area
- Proposed new communal grassed area
- Proposed new bike store
- Proposed new boundary fencing
- Proposed new tree landscaping
- Proposed dwelling parking bays 2.5 x 5m
- Proposed new hedging
- Location of integrated into cavity swift brick house
- Location of integrated into cavity bat box
- 4.5m Root protection zone to trees
- Tree protection fence

Landscaping

Hedging
Native country hedge mix to rear of the plots and along east boundary of plot 4

60% Crataegus monogyna (Hawthorn)
10% Prunus spinosa (Blackthorn, sloe)
5% Acer campestre (Field maple)
5% Cornus sanguinea (Dogwood)
5% Corylus avellana (Hazel)
5% Euonymus europaeus (Spindle tree)
5% Malus sylvestris (Crab Apple)
5% Viburnum lantana (Wayfaring tree)

Double row planting with plants staggered to those in adjacent rows. The rows should be 20cm apart and the plants 40cm apart in each row making a total of 5 plants per metre.

Trees
To be a mix of native species to include some or all of the following:

Sorbus aucuparia (Rowan)
Sorbus aria (Whitebeam)
Acer campestre (Field Maple)
Betula pendula (Silver Birch)
Malus sylvestris (Crab Apple)
Prunus Cerasifera nigra (Cherry Plum)

Dwellings

Plot 1 - Type A
4 bedroom house - Estimated 255sqm (including external walls)

Plot 2 - Type B
4 bedroom house - Estimated 255sqm (including external walls)

Key - Drainage

- Existing surface water drainage
- Proposed surface water drainage
- Proposed downpipe
- Proposed surface water inspection chamber
- Rodding eye
- Aco Drain

Note:
All information shown on this drawing is to be used for planning or building regulation purposes only and not to be used in conjunction with any other information or workstage including contract, working drawings, construction and as built papers.

No responsibility is taken by Concept Drawing & Design Architects for any measurements taken of this drawing. All dimensions shown on this drawing must be checked on site by the project manager and/or contractor to ensure that they are accurate. Any dimensions that can not be achieved, the client, project manager and architect must be made aware immediately.

Concept Drawing and Design Architects have not surveyed the external landscape, or the boundary line, external ground levels, and position/s of existing buildings. This information, if shown on the drawings, are just a representation of what might be there. Concept Drawing and Design Architects take no responsibility for the accuracy of the information relating to these topics.

The Party Wall Act may apply if any of the following categories of building work apply:

- Work on an existing wall or structure shared with another property.
- Building a new standing wall or a wall of a building up to, near or outside the boundary with a neighbouring property.
- Excavating near a neighbouring building.

It is the responsibility of the client/owner to determine whether the act applies and if so notify all adjoining owners in accordance with the act. Further information can be found on the communities and local government website.

A - 14.11.2023
Alteration to boundary
B - 22.11.2023
Alterations as per clients email
C - 28.11.2023
Alteration to notes
D - 01.05.2025
Bike Store and surface water drainage added
E - 10.08.2025
Garage and single storey extension added
F - 19.12.2025
Root protection added and bike shed moved to plot 2
G - 22.12.2025
Tree protection fence added

PROJECT
2338 - Quemerford Dwellings
Mr Mayo

Quemerford
Wiltshire, SN11 8UB


Proposed Dwellings

DRAWING
Proposed Site Plan
1:200, 1:100@A1
Drg No:2338.03.02 Rev G
22/12/2025

CONCEPT DRAWING & DESIGN
SERVICES

Telephone: 07557505990
Email: concept@drawinganddesign.co.uk
Website: www.drawinganddesign.co.uk
You can also find us on Facebook and Twitter

Default specification for protective barrier



- Key**
- Standard scaffold poles
 - Heavy gauge 2m tall galvanized tube and welded mesh infill panels
 - Panels secured to uprights and cross-members with wire ties
 - Ground level
 - Uprights driven into the ground until secure (minimum depth 0.6m)
 - Standard scaffold clamps

Examples of above-ground stabilizing systems

