

Hedgerow Protection Plan
Condition 6 Discharge
Planning Ref: PL/2022/05120

- Key:**
- Existing retained hedgerow (TPO protected)
 - Temporary Heras protective fencing
 - 3m hedgerow protection buffer zone

Hedgerow Protection Method Statement

Protective Heras fencing will be erected along the western boundary to create a 3m buffer from the retained hedgerow prior to the commencement of development.

The fencing will remain in place for the duration of the construction period and until all machinery, equipment and materials have been removed from the site.

No storage of materials, site compounds, machinery, excavation or changes to the ground levels will take place within the protected buffer zone.

