

BUTRESS

TOP ROW OF BRICKS REMOVED
AND REPLACED WITH BRICK ON
EDGE COPING.

EXISTING WALL HEIGHT

CAST STONE PIER CAP
TO RESEMBLE EXISTING STONE
CAPPINGS TO WESTERN BOUNDARY
WALL. COLOUR TO MATCH
EXISTING STONE.

APPROX

86.31

460

76 mm.

BOE
COPING

BONDING PATTERN TO
MATCH EXISTING.
(3x stretchers, Header, 3x stretchers
repeated on each row. Headers
alternate location on each row,
centered on middle stretcher.)

1.76 m

440.

1.82 m.

BRICK BONDING
TO PILLAR
TO INCLUDE
CENTRAL
HEADER ON
ALTERNATE
ROWS.
(front face only)

EXISTING
WALL

440.

460

BOUNDARY

GL 84.55

FRONT ELEVATION

PILLAR TYPE 'A'

SIDE ELEVATION

ALL BRICKWORK TO UTILISE CLEANED,
SALVAGED BRICKS FROM COLLAPSED WALL,
WITH LIME MORTAR JOINING / POINTING

SCALE 1:20 @ A3

0 0.2 0.4 0.8 1m

rev	description	date	by	chk
-	PLANNING ISSUE	2026-03-06	SH	CB

project
MANOR FARM BROAD CHALKE

client
Mr. & Mrs JOWETT

drawing title
DETAIL ELEVATION I - INC. PILLAR TYPE 'A'

drawing number	revision	status	scale
1294-EL-02	-	PLANNING	1:20@A3

FOR PLAN REFER TO
DRAWING 1294-GA-01

GENERAL NOTES:

This drawing is to be read in conjunction with all other relevant disciplines drawings, schedules, specifications and supporting information. Any discrepancies are to be reported to Indigo Landscape Architects Limited and resolution sought prior to proceeding. This drawing is subject to copyright.