



DO NOT SCALE this drawing. Use figured dimensions only.
The Contractor must check & verify all dimensions on site.
Any discrepancies must be reported immediately to the Engineer for clarification before proceeding.
This drawing is copyright and owned by Morgan Civil + Structural.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION
Refer to the relevant Construction (Design and Management) documentation where applicable.
It is assumed that all works on this drawing will be carried out by a competent contractor, working where appropriate to an approved method statement.

- NOTES**
1. Do Not Scale from this drawing, use figured dimensions only. All dimensions are in meters.
 2. This drawing is to be read in conjunction with all other relevant drawings/specifications.
 3. This drawing is to be read in conjunction with and checked against all engineering details, landscape architects, specifications, geotechnical and other relevant documentation provided.
 4. This drawing is subject to approvals from relevant statutory bodies.
 5. All the above requirements shall apply unless otherwise stated in the general arrangement drawings/specification. In the event of a contradiction the contract specific documents shall be deemed to prevail.
 6. The contractor is to check and verify all site dimensions and levels, including existing sewer invert levels and utilities, prior to start on site.
 7. Positions of existing services/statutory undertakers apparatus adjacent to or crossing proposed excavations are to be confirmed prior to start on site.
 8. This drawing is schematic for clarity only, positions of pipe runs and manholes may vary on site due to site conditions.
 9. Where trees adjacent to highways or drainage are proposed, root barriers (type to be approved) are required to prevent structural damage.
 10. Any anomaly or contradictions between any of the above is to be reported immediately.
 11. The contractor is to comply in all aspects with the current british standards, building regulations and building legislation etc.
 12. It is the responsibility of the contractor to execute the works at all times in strict accordance with the requirements of the health and safety at work etc. ACT 1974 And the C.D.M. REGULATIONS 2015. The contractor will be deemed to have allowed for full compliance.
 13. For construction details, please refer to drawing no. 138021-MCS-XX-DR-C-6000, 6001 & 6300.

- KEY:**
- Site Boundary
 - Footway Construction
 - Carriageway Construction Tarmac (Type AR4)
 - Vehicle Crossover
 - Vehicle Crossover - 3 or more properties - to match adjacent carriageway construction
 - Driveway Construction
 - Grass Verge
 - Half Battered Kerb 125mm Upstand (HB2)
 - Hit and Miss Kerb 125mm Upstand (HB2)
 - Bull Nosed Kerb 0-6mm Upstand (BN0)
 - Bull Nosed Kerb 25mm Upstand (BN25)
 - Transition Kerb
 - EF Edging Kerb
 - Quadrant Kerb
 - Channel Kerb (CS2) Laid Flat
 - Permeable Paving (to landscape architect's specification)
 - Block Paving - Marshall's Keyblok Colour Brindle
 - High Friction Surface (Buff)

Rev	Date	Description	By
Client			
Redcliffe Homes			
Project			
Woodlands Road, Mere			
Title			
Surface Finishes and Kerbing			
Drawing Status			
APPROVAL			
Drawn	Checked	Approved	Date
AM	NT	NT	MAR 2026
Scale @ A0	1:250		
Project No.	Drawing No.	Revision	
138021	138021-MCS-XX-DR-C-3300	P01	

