

TREE PLANTING SCHEDULES

Abbeyfield School Extension



Client	Job No.	Document management	Status	Rev	Purpose	Date
Wiltshire County Council	26CD07	26CD07-NVB-40-2XX-L-L-40001	Planting schedule - Phase 1 P03		Tender	27.03.2026

TREE SPECIFICATION LIST

LEGEND

S-M

S

M-S

S

Semi Mature

Standard

Multi Stem

Standard

C/S

F

Clear Stem

Feathered

NOTE

Whether a tree is supplied root-balled or containerised within a pot or airpot, is dependent on the season of planting. Pricing should therefore to suit the project programme.

SPECIES	COMMON NAME	CODE	HEIGHT / GIRTH	FORM & BRANCHING		NOTES	No.
<i>Acer campestre</i>	Field Maple		14-16cm	S	C/S	CG. 2m min clear stem	4
<i>Alnus glutinosa</i>	Black Alder		10-12cm	S	C/S	CG. 1.5m min clear stem	3
<i>Betula pubescens</i>	Downy Birch		10-12cm	S	C/S	CG. 1.5m min clear stem	6
<i>Corylus avellana</i>	Hazel		200-250	S-M	F	Min 3no. Stems from base.	9
<i>Fagus sylvatica</i>	Common Beech		14-16cm	S	C/S	CG. 2m min clear stem	2
<i>Ilex aquifolium</i>	Holly		100-150	S-M	F	Bushy specimen, healthy crown	1
<i>Pinus sylvestris</i>	Scots Pine		18-20cm	S-M	C/S	5m Feathered	6
<i>Quercus robur</i>	English Oak		14-16cm	S	C/S	CG. 2m min clear stem	3
<i>Salix alba</i>	White Willow		14-16cm	S	C/S	CG. 2m min clear stem	3
<i>Ulmus 'New Horizon'</i>	Elm 'New Horizon'		14-16cm	S	C/S	CG. 2m min clear stem	3
<i>Sorbus aria</i>	Common Whitebeam		14-16cm	S	C/S	CG. 2m min clear stem	1
<i>Sorbus torminalis</i>	Wild Service Tree		14-16cm	S	C/S	CG. 2m min clear stem	2
<i>Taxodium distichum</i>	Swamp Cypress		14-16cm	S	C/S	CG. 2m min clear stem	2
						Total	45

Client	Job No.	Document management	Status	Rev	Purpose	Date
Wiltshire County Council	26CD07	26CD07-NVB-40-2XX-L-L-40001	Planting schedule - Phase 1	P03	Tender	27.03.2026

HEDGING AND TRANSPLANT SPECIFICATION LIST

Note								
Whether hedge plants are supplied bare-root or in pots, is dependent on the season of planting and project programme. Pricing should therefore suit the project programme.								
SPECIES	COMMON NAME	SIZE			PLANTING DENSITY/ linear m	NOTES	No.	%
		Code	plant size cm	breaks or branches				
Mixed hedge (200 linear m)								
Acer campestre	Field Maple	1+2	60-80cm	5	3.5	Feathered to base.	70	10%
Corylus avellana	Hazel	1+2	60-80cm	5	3.5	Feathered to base.	70	10%
Crataegus monogyna	Hawthorn	1+2	60-80cm	5	3.5	Feathered to base.	350	50%
Prunus spinosa	Blackthorn	1+2	60-80cm	5	3.5	Feathered to base.	70	10%
Rosa canina	Dogrose	1+2	60-80cm	5	3.5	Feathered to base.	70	10%
Viburnum opulus	Guelder Rose	1+2	60-80cm	5	3.5	Feathered to base.	70	10%
							Total	700
SPECIES	COMMON NAME	SIZE			PLANTING DENSITY/ linear m	NOTES	No.	%
		Code	plant size cm	breaks or branches				
Carpark Hedging								
Fagus sylvatica	Beech	1+2	80-100cm	5	3.5	Feathered to base.	72	100%

Client	Job No.	Document management	Status	Rev	Purpose	Date
Wiltshire County Council	26CD07	26CD07-NVB-40-2XX-L-L-40001	Planting schedule - Phase 1 P03	P03	Tender	27.03.2026

CONTAINER GROWN SHRUBS, GRASSES, HERBACEOUS PERENNIALS & BULBS SPECIFICATION LIST

58m2

SPECIES	COMMON NAME	pot size	Plant size	breaks or branches	PLANT	NOTES	No.	%
<i>Cornus alba 'Sibirica'</i>	Siberian dogwood	3	40-60	Min. 5	3	Full pot, fully rooted pot system, healthy clump. Bushy	22	12.5
<i>Cornus sericea 'Flaviramea'</i>	Golden-twig Dogwood	3	40-60	Min. 5	3	Full pot, fully rooted pot system, healthy clump. Bushy	22	12.5
<i>Hydrangea paniculata 'Little Lime'</i>	Hydrangea 'Little Lime'	3	40-60	Min. 3	3	Full pot, fully rooted pot system, healthy clump. Bushy	44	25
<i>Hebe rakiensis</i>	Shrubby Veronica	3	15-20	Min. 5	3	Full pot, fully rooted pot system, healthy crown.	44	25
<i>Polystichum aculeatum</i>	Hard shield fern	2l	30-40		5	Full pot, fully rooted pot system, healthy clump. Bushy	73	25
Cornus and Hydrangea underplanted with:								
<i>Luzula nivea</i>	Snow-white Wood-rush	2l			3	Full pot, fully rooted pot system, Health crown	87	

Client	Document management	Status	Rev	Purpose	Date
Wiltshire County Council	26CD07-NVB-40-2XX-L-L-40001	Planting schedule - Phase 1	P03	Tender	27.03.2026

MEADOW GRASS SPECIFICATION LIST

SEED MIXES

Seed mixes selected to suit conditions. Wet ground (except for proposed bunds). Calcerous, slightly alkaline and low fertility).

Area dependant on area impacted by construction and extent of final bunding

SPECIES	
A19 All Purpose Landscaping Grass Seed by Germinal Amenity	%
https://germinalamenity.com/a19-all-purpose-landscaping	
<i>Agrostis castellana</i>	5
<i>Festuca rubra litoralis</i>	25
<i>Festuca rubra rubra</i>	20
<i>Lolium perenne</i>	10
<i>Lolium perenne</i>	40
Area dependant on area impacted by construction	
Meadow mixture for Wetlands EM13 Avis Meadow mix by Emorsgate Seeds	%
https://wildseed.co.uk/product/mixtures/complete-mixtures/brush-harvested-meadow-mixtures/em13-avis-meadow-mixture/	
Wild Flowers 31.1%	
<i>Centaurea nigra</i> – Common Knapweed	5
<i>Conopodium majus</i> – Pignut	0.1
<i>Filipendula ulmaria</i> – Meadowsweet	0.2
<i>Heracleum sphondylium</i> – Hogweed	0.4
<i>Lathyrus pratensis</i> – Meadow Vetchling	1
<i>Lecantherum vulgare</i> – Oxeye Daisy (Moon Daisy)	12
<i>Lotus corniculatus</i> – Birdsfoot Trefoil	1
<i>Primula veris</i> – Cowslip	4
<i>Prunella vulgaris</i> – Selfheal	1
<i>Ranunculus acris</i> – Meadow Buttercup	2
<i>Ranunculus bulbosus</i> – Bulbous Buttercup	1
<i>Rhinanthus minor</i> – Yellow Rattle	2
<i>Silene silaus</i> – Pepper Saxifrage	0.2
<i>Succisa pratensis</i> – Devil's-bit Scabious	0.2
<i>Vicia cracca</i> – Tufted Vetch	1
Grasses 68.9%	
<i>Agrostis capillaris</i> – Common Bent (w)	48
<i>Alopecurus pratensis</i> – Meadow Foxtail (w)	0.5
<i>Anthoxanthum odoratum</i> – Sweet Vernal-grass (w)	4
<i>Cynosurus cristatus</i> – Crested Dogtail (w)	6
<i>Dactylis glomerata</i> – Cocksfoot (w)	1
<i>Festuca rubra</i> – Red Fescue (w)	8
<i>Holcus lanatus</i> – Yorkshire Fog	0.4
<i>Lolium perenne</i> – Perennial Ryegrass	1

Meadow mixture for Bunds EM18 St Catherine's Meadow Mixture	%
https://wildseed.co.uk/product/mixtures/complete-mixtures/brush-harvested-meadow-mixtures/st-catherine-mixture-limestone-grassland/	
Wild Flowers 42%	
<i>Anthyllis vulneraria</i> – Kidney Vetch	1
<i>Centaurea nigra</i> – Common Knapweed	2
<i>Cerastium fontanum</i> – Common Mouse Ear	0.5
<i>Crepis capillaris</i> – Smooth Hawksbeard	1
<i>Hypochaeris radicata</i> – Catsear	0.5
<i>Leontodon hispidus</i> – Rough Hawkbit	3
<i>Leucanthemum vulgare</i> – Oxeye Daisy	3
<i>Linum bienne</i> – Pale Flax	1
<i>Linum catharticum</i> – Fairy Flax	4
<i>Lotus corniculatus</i> – Birdsfoot Trefoil	1
<i>Medicago lupulina</i> – Black Medic	2
<i>Plantago lanceolata</i> – Ribwort Plantain	6
<i>Primula veris</i> – Cowslip	0.5

<i>Prunella vulgaris</i> – Selfheal	1
<i>Ranunculus acris</i> – Meadow Buttercup	3
<i>Ranunculus bulbosus</i> – Bulbous Buttercup	1
<i>Rhinanthus minor</i> – Yellow Rattle	7
<i>Tragopogon pratensis</i> – Goat's-beard	0.5
<i>Trifolium pratense</i> – Wild Red Clover	3
<i>Trifolium dubium</i> – Lesser Trefoil	1
Grasses 58%	
<i>Anthoxanthum odoratum</i> – Sweet Vernal-grass	5
<i>Briza media</i> – Quaking Grass	4
<i>Bromopsis erecta</i> – Upright Brome	14
<i>Carex flacca</i> – Glaucous Sedge	8
<i>Cynosurus cristatus</i> – Crested Dogtail	8
<i>Dactylis glomerata</i> – Cocksfoot	2
<i>Festuca rubra</i> – Red Fescue	12
<i>Holcus lanatus</i> – Yorkshire Fog	1
<i>Lolium perenne</i> – Perennial Ryegrass	4

Client	Job No.	Document management	Status	Rev	Purpose	Date
Wiltshire County Council	26CD07	26CD07-NVB-40-2XX-L-L-40001	Planting schedule - Phase 1	P03	Tender	27.03.2026

RAIN GARDEN SPECIFICATION LIST						
70m2						
SPECIES	COMMON NAME	POT	DENSITY per m2	NOTES	%	No
<i>Amsonia tabernaemontana</i>	Blue star	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Anemone 'Wild Swan'</i>	Anemone	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Blechnum spicant</i>	Hard Fern	2l	5	Full pot, fully rooted pot system, healthy clump/crown.	5	18
<i>Deschampsia cespitosa</i>	Tufted hairgrass	2l	5	Full pot, fully rooted pot system, healthy crown.	10	35
<i>Eupatorium maculatum Atropurpureum</i>	Joe Pyeweed	3l	3	Full pot, fully rooted pot system, healthy crown. Bushy	5	11
<i>Filipendula ulmaria</i>	Meadowsweet	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Geum rivale</i>	Water Avens	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Polystichum aculeatum</i>	Hard shield fern	3l	5	Scattered through beds	10	35
<i>Iris psuedacorus</i>	Flag Iris	3l	3	Full pot, fully rooted pot system, healthy crown.	10	21
<i>Juncus inflexus</i>	Hard rush	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Helleborus foetidus</i>	Stinking hellebore	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Luzula sylvatica</i>	Wood rush	2l	5	Full pot, fully rooted pot system, healthy crown.	10	35
<i>Lysimachia atropurpurea 'Beaujolais'</i>	Purple loosestrife	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
<i>Osmunda regalis</i>	Royal fern	3l	3	Full pot, fully rooted pot system, healthy crown. Healthy Clump	10	21
<i>Sesleria caerulea</i>	Blue moor-grass	2l	5	Full pot, fully rooted pot system, healthy crown.	5	18
				Total		320