



Foul Water MH Schedule				
Ref.	Approximate Cover Level.	Invert Level.	Depth to Invert Level	Description
F1	85.270	84.670	0.600	TYPE E 250 mm dia - Sited in soft landscaped area
F2	85.270	84.670	0.600	TYPE E 250 mm dia - Sited in soft landscaped area
F3	85.270	84.270	1.000	TYPE D 450 mm dia - Sited in soft landscaped areas
F4	85.000	84.400	0.600	TYPE E 250 mm dia - Sited in driveways or paved areas

Surface Water MH Schedule				
Ref.	Approximate Cover Level.	Invert Level.	Depth to Invert Level	Description
CP1	85.270	84.670	0.600	CATCHPIT 600 mm dia - Sited in driveways or paved areas
CP2	84.920	84.260	0.660	CATCHPIT 600 mm dia - Sited in driveways or paved areas
CP3	85.050	84.450	0.600	CATCHPIT 600 mm dia - Sited in driveways or paved areas
CP4	85.000	84.385	0.615	CATCHPIT 600 mm dia - Sited in driveways or paved areas
CP5	84.800	83.860	0.940	CATCHPIT 600 mm dia - Sited in driveways or paved areas

1. Drawing for information only

Rev	Date	Description	Initials	Check
-----	------	-------------	----------	-------



WILTSHIRE COUNCIL

**SPRINGFIELD SCHOOL
CALNE**

DRAINAGE DETAILS
Sheet 2 of 2

Drawing No. 7061-C-106

Status	Preliminary for Comment
--------	--------------------------------

Not for Construction

Job Number	7061	Date	Aug 2025
Scale	Varies @ A1		
Drawn By	MTD	Checked By	TL