Existing retained hedgerow planting

Malmesbury Primary School

Footpath extension to tie into existing footpath running up to Sillars Green

Levels to be as existing or lower to retain or increase flood water volume

Wildflower meadow. Allow for 100mm depth site-won subsoil for wildflower meadow. Ground to be cultivated to a depth of 200mm to relieve compaction and create a fine and firm level tilth before spreading subsoil. Sow with a species-rich calcareous meadow seed mix, with grasses and high-floral diversity.

Specimen tree planting, including 300mm depth of premium grade imported topsoil within a 1000mm diameter pit. Break up and cultivate existing subsoil to a depth of 200mm below pit base to ensure free drainage. Incorporate 10g/m² slow-release fertiliser and PAS100-certified compost into the top 200mm of soil within each pit.

Mixed species native hedgerow - allow for 300mm depth of site-won topsoil. Existing subsoil to be broken up and cultivated to a depth of 200mm to ensure free drainage. Allow for 50mm depth of organic green mulch / biodegradable green waste to surface.

Tetbury Avon Flood Plain

Standard impermeable macadam surface build up to tie into existing footpaths on each end

Footpath to connect to revised proposals to Malmesbury Primary School extension (planning ref: PL/2025/07919), linking to Poole Road

Malmesbury Victoria Football Club

Mixed species native hedgerow - allow for 300mm depth of site-won topsoil. Existing subsoil to be broken up and cultivated to a depth of 200mm to ensure free drainage. Allow for 50mm depth of organic green mulch / biodegradable green waste to surface.

Key

- **Application Boundary**
- **Existing trees** Dashed line indicates root protection area
- Proposed hedge planting
- Proposed wildflower meadow
- Proposed specimen trees

Rev	Date	Description	Drn	Chk	App
P04	27.03.26	Issued for Planning	JV	--	JV
P03	27.02.26	Third issue for coordination	JH	--	JV
P02	18.02.26	Second issue for coordination	JH	--	JV
P01	11.02.26	First issue for coordination	JH	--	JV

Scale 1:250

0 2 4 6 8 10 12m

Drawings to be scaled only for planning purposes.
All dimensions to be verified on site for construction.
© Drawing & design copyright LUC

LUC

www.landuse.co.uk

Project
MALMESBURY PRIMARY SCHOOL SOUTH FOOTPATH

Client
MALMESBURY PRIMARY SCHOOL

LUC Job Nr	Scale @A3	Status
13086	1:250	S2 - INFORMATION

Drawing Title
FOOTPATH - LANDSCAPE GENERAL ARRANGEMENT

Drawing Nr	Rev
13086-LUC-XX-XX-DR-L-0008	P04