ALL DIMENSIONS AND EQUIPMENT POSITIONS TO BE CHECKED ON SITE PRIOR TO ORDERING.
THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS.
THIS DRAWING AND DESIGN REMAINS COPYRIGHT OF MORECROFTS AND MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN CONSENT FROM MORECROFTS.

CONSTRUCTION
Not Authorised FOR

EXTERNAL ELECTRICAL SERVICES LAYOUT - 1:300

1 External Electrical Services Layout
1 : 300



2 Section 57
1 : 300

EXTERNAL SERVICES LEGEND

- C — HOLOPHANE - D-SERIES 2 - AREA LUMINAIRE DSX2.4.LA402.FW (TZ) - 33396.1LM | 268W
- EX1 — HOLOPHANE - D-SERIES 0 - AREA LUMINAIRE DSX0.4.LA152.AY (TZ) - 12340LM | 106W FIXED ATOP 6m COLUMN
- EX2 — HOLOPHANE - D-SERIES 0 - AREA LUMINAIRE DSX0.4.LA152.SY (TZ) - 12885LM | 106W FIXED ATOP 6m COLUMN
- EX3 — HOLOPHANE - D-SERIES 1 - AREA LUMINAIRE DSX1.4.LA362.FW - 29288LM | 256W FIXED ATOP 8m COLUMN
- EX5 — HOLOPHANE - D-SERIES 1 - AREA LUMINAIRE DSX1.4.LA302.AY - 24679LM | 231W WALL MOUNTED 8m
- EX5|AY — HOLOPHANE - DENVER ID WALL DWL.1.LA042.AY.W025 - 3281LM | 25W WALL MOUNTED 4m
- EX5|FW — HOLOPHANE - DENVER ID WALL DWL.1.LA032.FW.W018 - 2223LM | 18W WALL MOUNTED 4m
- EX5|NR — HOLOPHANE - DENVER ID WALL DWL.1.LA012.NR.W007 - 813LM | 6.5W WALL MOUNTED 4m
- EX7 — HOLOPHANE LIGHTING - CSVT LED BATTEN CSVT.1.LM0748.M1.SY - 7016LM | 53W SURFACE MOUNTED 4m
- EX8 — HOLOPHANE - D-SERIES 0 - AREA LUMINAIRE DSX0.4.LA102.BLC - 5984LM | 79W FIXED ATOP 6m COLUMN
- EX9 — HOLOPHANE - TETRA PARCO 1330mm 5035611 - 1620LM | 28W
- EX11 — HOLOPHANE - CITY MAX EXTERNAL LUMINAIRE SCL.2.LA092.ST3.CP.W075 - 7975LM | 75W FIXED ATOP 6m COLUMN
- EX12 — HOLOPHANE - TETRA PARCO 2.6M 5035614 - 2390LM | 41W
- EX13 — HOLOPHANE - MICRO 3 LED MEDIUM 8401913 - 435LM | 5.9W
- EX14 — HOLOPHANE - MINI ONE PALETTO 800mm 1080611 - 110LM | 9.5W
- EX15 — HOLOPHANE - ONE 2.0 APPLIQUE 1515215 - 25W
- LED LINEAR TAPE
- EVC1 — ELECTRIC VEHICLE CHARGING POINT 22kW
- EVC2 — ELECTRIC VEHICLE CHARGING POINT 7.4kW

REVISION	DESCRIPTION	DATE	DRAWN BY
C10	SIEMENS UPDATES	17.02.2026	C.CARDOSO
C09	SIEMENS UPDATES	14.01.2026	T. SQUIRES
C08	SIEMENS SI UPDATES	13.01.2026	T. SQUIRES
C07	CONSTRUCTION ISSUE	25.11.2025	T. SQUIRES
C06	ELEVATION ADDED	19.11.2025	T. SQUIRES
C05	CCTV SETTING OUT ADDED	30.10.2025	C.CARDOSO
C04	LIGHTING SETTING OUT ADDED	17.10.2025	T. SQUIRES
C03	EXTERNAL SECURITY, REB UPDATES, CCTV ADDED	24.09.2025	T. SQUIRES
C02	CONTRACTUAL ISSUE	31.07.2025	T. SQUIRES
C01	CONTRACTUAL ISSUE	28.03.2025	T. SQUIRES

PROJECT: SIEMENS MOBILITY CHIPPENHAM

SIEMENS

BOWMER + KIRKLAND

CLIENT: BOWMER + KIRKLAND, HIGH EDGE COURT, CHURCH STREET, BELPER, DERBYSHIRE DE56 2BW

STATUS: CONTSTRUCTION

TITLE: EXTERNAL ELECTRICAL SERVICES LAYOUT

REVISION: C10

PROJECT	SCALE	DRAWN BY	PAGE SIZE	ISSUE DATE
00739	1:300	T.SQUIRES	A0	28.03.2025

PROJECT	ORIGINATOR	VOLUME	LEVEL	TYPE	ROLE	NUMBER
SMC	MOR	EX	ZZ	D	E	7001

MORECROFTS
Morecroft Electrical Ltd
Milldale House
Prime Parkway
Derby
DE1 3QB
01332 349580
info@morecrofts.net
www.morecrofts.net