

Replace defective cladding with larch boarding approx. 170mm to match average existing & create uniformity

New (replaced) Sliding Doors
See 3209/B/9 A.

Poor quality concrete floor to main barn and rear entrance to be taken up and replaced with limecrete floor (150mm thick over blinding and suitable hardcore

Existing Stone floor retained and made good as necessary

New Doors
(See 3209/B/11 A)

1:50 Scale

1 2 3 4 5m

BOLINGBROKE DESIGN

6 The Slipway, Staverton, BA14 8UP

Mobile 07860 491800

bolingbroke.design@gmail.com

LEGEND:-

-  Exg Walls
-  New Stone
-  New Brick
-  New Block
-  New Stud

NOTES:

© All copyright 2026
Reserved

Client

Peter Hood

Job Title

Barn at Beanacre Manor
Beanacre, SN12 7PT

Scale

1:50

Drawn by

ca

Date

April 2026

Drawing Title **Main Barn
Proposed floor Plan**

Drg No.

3209/B/15

Rev

B