

STAFF ROOM:
Any spare 'okay' condition ceiling tiles to be used to replace damaged or poor condition Staff Room ceiling tiles. If none available, then leave as is.
Fix lockers to wall.
General decoration to all wall and skirting boards.
Staff room flooring to be replaced except for vinyl in kitchen area.

FF QUIET ROOMS:
General decoration to walls and skirting. Windows and sills clean and touch up only.
Replace carpet with new.
Replace all old manifestation with new Smart Red dot manifestation.
Install new brand bands to customer facing rooms.
Remove any signage from glazed partitions.
Remove old cabinets.

TOILET LOBBY:
Lighting level appears insufficient. Install 1no. additional LED ceiling light.

FEMALE TOILET:
Remove broken shelving.
Install new long mirror.
Re-mastic sink.
Adjust vanity cupboard doors to prevent doors swinging open.
Fix broken flush if still broken at time of works.

MALE TOILET:
Replace missing tiles.
Fill any holes at the perimeter of floor to prevent water ingress under flooring.
Remove redundant loo roll holder at urinal position.

FF BANKING HALL & STAIRS:
General decoration to walls and skirting. Windows and sills clean and touch up only.
Flooring in scope for replacement. Replace flooring as per the drawing plus the stairs and the first floor landing. Stair nosing also to be replaced.
Swap and damaged and stained tiles with usable ceiling tiles from back of house areas.
Repair slight damage to ceiling grid adjacent to central ceiling AC unit.
Replace all old manifestation to glazing over the stairs with new Smart Red dot manifestation.
Query: Change door handle leading to back of house?

PROPOSED FIRST FLOOR
1:50 @ A1, 1:100 @ A3



NO WORKS REQUIRED

Notes.
This Drawing is the copyright and property of Santander UK PLC. It must not be copied or published without written consent.

Do not scale from this drawing.

Rev	Description	Date	By

FLOOR FINISHES:

- F1 Entrance mat**
Gradus, Boulevard 1500 in Calculus
- F2 Grey floor tile - concrete effect**
Ceramic Dark - SS5S3566 - Amtico Spacia (457.2x457.2mm)
- F3 New England oak effect plank**
New England Oak - SS5W2527 - Amtico Spacia (101.6x914.4mm)
- F4 Dark walnut effect plank**
Black Walnut - SS5W2534 - Amtico Spacia (101.6x914.4mm)
- F5 Dark grey carpet tile**
Interface Employ Loop Shale 4197006
- F6 Stripe carpet tile**
Milliken Carpet, Line Up Fix 520 (500x500mm)
- F7 SELECT carpet tile**
Milliken Carpet, Consequence 2.0 UPS 108-133 Tortoise (457.2x457.2mm)
- F8 Back of house carpet**
Ref: Interface Works Effect Haze
- F9 Plastic sheet vinyl**
Current Back of House Standard vinyl Altro Ltd. Safety Flooring Designer 25. 2.5mm Midnight 25421.
- F10 Red floor vinyl tile**
Red - Amtico: rio code: AR0ACF56 - Amtico Signature (457.2x1219.2mm)
- F11 Ceramic tiles**
Domus, 797x797x10mm, Natural Finish Steel DFDL04. Grout BAL Jasmin Grey.

NEW	BULLET RESISTANT PARTITION (anti ballistic cladding)
DEMOUNTABLE GLAZED PARTITION	1/2 HOUR FIRE RATED PARTITION
SECURE WALL (ATM and Cash rooms) as per latest design manual	1 HOUR FIRE RATED PARTITION
100mm STUD PARTITION	

PLANNING - LBC

Client			
Project	Salisbury 53 Silver Street, Wiltshire, SP1 2NG		
Title	Proposed First Floor General Arrangement		
Scale	1:50 @ A1 & 1:100 @ A3		
Drm	BG	App	RSB
Date	22/04/2026	Date	07/05/2026
Client drawing number		rev.	-
SalisburySL-0088-FF-GA-PR-PL			