

PROPOSED GROUND FLOOR
1:50 @ A1, 1:100 @ A3



NO WORKS REQUIRED

COUNTER / ADMIN AREA:
Remove the two square Santander logos behind cashier positions.
Ensure that screen is centred behind cashier positions.
Scuffed and worn walls and skirting boards in Admin Areas 1 & 2. General decoration.
Flooring in scope for replacement. Replace flooring as per drawing.
No whiteboard in Admin Area 2 for staff use.
Supply whiteboard.
Refit (or replace if missing) corner nosing that has dropped.
Adjust fire door in Admin Area 2 so that it closes.
Remove 2no. old brand bands from existing till blocks. Install 1no. new brand band to LHS till block.
For both till blocks, decorate existing red walls in black.

DISABLED TOILET:
Large section of missing tiles. Reinstate tiling.
Patch hole in wall.
Install plastic skirting to perimeter of floor to prevent water ingress under flooring.
Infill the cracks in the floor tiles with latex (to prevent possibility of trips/or wheelchair wheels getting caught).

GF QUIET ROOMS:
Remove picture rails.
Replace all old manifestation with new Smart Red dot manifestation.
Replace old chairs with new red chairs.
Remove old cabinet.

GF BANKING HALL:
Scuffed and worn walls and skirting boards.
General decoration.
Install replacement tiles where damaged or of a variance of type/finish.
Redundant picture rails on walls. Remove picture rails.
Flooring in scope for replacement. Replace flooring as per drawing.
Fire Alarm panel missing Zone Plan. Install Zone Plan.
Paint post box white.
Decorate window bay.
Smart Red branding to be installed at the ATMs.
Remove Literature walls.
Decorate window bay.
Install Tech Bar.
Install floor box to service Tech Bar.
Arrows to be applied to the floor to direct customers to the cashier desk.

CHAIRS TO BE REMOVED FROM BRANCH

	Symmetry Chair With Arms	0		Soft Staff Room Chair	0
	Customer Chair With Arms	0		Forma 5	0
	Dash Chair Without Arms	0		Perch Stool	0
	Box Single Seater Chair	0		Zebra Chair	0

Notes.
This Drawing is the copyright and property of Santander UK PLC. It must not be copied or published without written consent.

Do not scale from this drawing.

Rev	Description	Date	By

FLOOR FINISHES:

- F1 Entrance mat**
Gradus, Boulevard 1500 in Calculus
- F2 Grey floor tile - concrete effect**
Ceramic Dark - SS5S3566 - Amtico Spacia (457.2x457.2mm)
- F3 New England oak effect plank**
New England Oak - SS5W2527 - Amtico Spacia (101.6x914.4mm)
- F4 Dark walnut effect plank**
Black Walnut - SS5W2534 - Amtico Spacia (101.6x914.4mm)
- F5 Dark grey carpet tile**
Interface Employ Loop Shale 4197006
- F6 Stripe carpet tile**
Milliken Carpet, Line Up Fix 520 (500x500mm)
- F7 SELECT carpet tile**
Milliken Carpet, Consequence 2.0 UPS 108-133 Tortoise (457.2x457.2mm)
- F8 Back of house carpet**
Ref: Interface Works Effect Haze
- F9 Plastic sheet vinyl**
Current Back of House Standard vinyl Altro Ltd. Safety Flooring Designer 25. 2.5mm Midnight 25421.
- F10 Red floor vinyl tile**
Red - Amtico: rio code: AR0ACF56 - Amtico Signature (457.2x1219.2mm)
- F11 Ceramic tiles**
Domus, 797x797x10mm, Natural Finish Steel DFDL04. Grout BAL Jasmin Grey.

NEW	BULLET RESISTANT PARTITION (anti ballistic cladding)
DEMOUNTABLE GLAZED PARTITION	1/2 HOUR FIRE RATED PARTITION
SECURE WALL (ATM and Cash rooms) as per latest design manual	1 HOUR FIRE RATED PARTITION
100mm STUD PARTITION	

PLANNING - LBC

Client

Project

Salisbury
53 Silver Street,
Wiltshire, SP1 2NG

Title

Proposed Ground Floor
General Arrangement

Scale

1:50 @ A1 & 1:100 @ A3

Drn

BG

App

RSB

Date

22/04/2026

Date

07/05/2026

Client drawing number

SalisburySL-0088-GF-GA-PR-PL

rev.

-