

Wessex Refurbs Ltd

Skerryvore, Underhill
East Knoyle,
Wiltshire. SP3 6BS

Rose and Desond
Kiln Cottage
Teffont Evias
SP3

15^h March 2026

Chimney stack Rebuild:

Dear Desmond and Rose,

To rebuild the chimney stack to the required height needed above the ridge will be 1.85m in doing so the original bricks that are there are in a poor state.

The bricks are imperial bricks and the once I have removed and cleaned the bricks they will re-laid to the same pattern in a lime mortar mix using NHL 3.5 this will be a mix of 3 sand to 1 lime. By doing so we can match all the mortar that is in the greenstone based below in the gable end.

The bricks themselves will be Hampton Rural bricks which are a dark red with black markings that match those that are already there photos below.



As for the pot we will be installing a cannon top terracotta Pot. This matches to the other chimney breast in the property.

I hope this is enough to pass onto the planning department and is sufficient for them.

Kind regards
Russell Sandford

Incorporating Wessex Refurbs Limited
Registered in England No. 10969046

