# The Former Co-Op Store Site and Car Park, Mill Street, Calne, Wiltshire

## Archaeological Desk-Based Assessment

Nick Corcos BA, MA, PhD, MCIfA

Bristol: March 2026



## Avon Archaeology Limited

AAL Report No. 2024-25.695

Avon Archaeology Limited, Unit 36, Avondale Business Centre, Woodland Way, Kingswood, Bristol BS15 1AW
Tel: 0117 960 8487 email: mail@avonarchaeology.co.uk Registered Company 8498726

This page is intentionally blank

| | |
|---|---|
| Document Title | The Former Co-Op Store and Car Park, Mill Street, Calne, Wiltshire |
| Document Subtitle | Archaeological Desk-Based Assessment |
| Client Name | Cedar Care Homes Limited |
| Site Location | The Former Co-Op Store and Car Park, Mill Street, Calne, Wiltshire SN11 0HT |
| National Grid Reference | ST 99911 71017 |
| Planning Authority | Wiltshire County Council |
| Planning Reference | Pre-App |
| Project Code | AAL 24-25.695 |
| Document Author | Nick Corcos |
| Date of Preparation | March 2026 |
| OASIS Record Number | avonarch2-506242 |
| HER Number | Allocated by local authority |

©Avon Archaeology Limited: March 2026

**CONTENTS**

**Abstract**

**Acknowledgements**

**Notes**

**Copyright**

**1 Introduction**

**2 Methodology**

**3 Topography and Geology**

**4 Historical Background**

**5 Archaeological Background**

**6 Historic Map Evidence**

**7 National and Local Planning Policies**

**8 Conclusions**

**9 Bibliography**

**Cover**
Modern satellite image of the site in its present state. There are now no features or buildings of any archaeological and/or historic interest whatsoever to be seen on the site at ground level. Immediately to the west of the store building (on the left in this image) is the Grade II listed Calne Free Church, of mid-19th century date. Source: Google Earth.

**Figures**

1 Location of the site
2 Site plan showing red line boundary
3 Extract from map of Calne, 1828, with site shown
4 Extract from map of Calne, 1828, showing Eastman Street
5 Circular lockup at Ruabon, north Wales

©Avon Archaeology Limited: March 2026

6 Extract from Calne tithe map, 1843, showing site
7 Extract from First Edition 25" OS map, 1885, showing site
8 Extract from Third Edition 25" OS map, 1922, showing site

## Appendix

Wiltshire County Council Historic Environment Record, map and text printout

## Abbreviations

| | |
|---|---|
| aOD | Above Ordnance Datum |
| KYP | KnowYourPlace (online historic mapping resource) |
| mya | Million years ago |
| OS | Ordnance Survey |
| WHER | Wiltshire Historic Environment Record |
| WRO | Wiltshire Record Office |

©Avon Archaeology Limited: March 2026

## ABSTRACT

*Avon Archaeology Limited was commissioned by Cedar Care Homes Limited to undertake an archaeological desk-based assessment of a site currently occupied by a Co-Op store and its car park, in the centre of Calne, Wiltshire. It is proposed that the existing entirely modern store building will be demolished, and the space thus released, together with the former car park, used to construct a new care home, with associated car parking and landscaping, split across two adjacent sites, north and south of the River Marden.*

*The site lies in the centre of Calne, on the northern side of Mill Street, and effectively straddles the River Marden at this point as it flows through the town. It falls within the boundary of the Calne town centre Conservation Area. Parts of the site, especially the Mill Street frontage, are likely to have been developed in the medieval period, although historic maps show that large areas of its central part, and to the north and east, remained undeveloped well into the 20th century. There are no Scheduled Monuments within the site boundary, and no listed buildings – although a Grade II Listed Victorian church abuts the site's western boundary. A trawl of the local authority Site and Monuments Record showed no previous archaeological investigation of the site. Work on sites not far away, most notably evaluations, excavations and watching briefs, suggest intermittent survival of medieval and later archaeology, but the overall picture in the town centre thus far is at best vague. On the site itself, the best potential for archaeological survival is likely to be represented by those areas of hard standing which now form the car parking areas for the former Co-Op store, at the northern and eastern parts of the site. Within the footprint of the store building itself, archaeological survival on any level is far less likely. It is possible that some of the structures appearing on an early 19th century map may have far earlier origins, although there may also be remnants of later structures, most notably an early 20th century cinema building at the western side of the site. The early 19th century map recorded an enigmatic circular structure in a part of the site that does not*

*appear to have been subsequently built on, and the same map, and a slightly later one, also recorded an elongated pond at the eastern side of the site.*

*The present Co-Op store building was constructed before the advent of PPG16, in 1990, and so the site was not investigated prior either to its construction, or indeed as part of the process of demolishing and removing all the earlier structures to make way for the store and its car parks. In terms of below ground heritage assets, it is probable that, as already noted, considerable damage has been done within the footprint of the store building itself, but the same may not apply to the car parks. For the site as a whole, therefore, we consider that overall, the potential for archaeological preservation is, on balance, likely to be low to moderate – and that any surviving stratigraphy is likely to be chiefly of post-medieval date.*

©Avon Archaeology Limited: March 2026

**ACKNOWLEDGEMENTS**

Avon Archaeology Limited wishes to acknowledge the assistance given by the following in the production of this report: Ian Burridge of BBA Architects and Planners Ltd., and the ever-helpful and patient staff of the Wiltshire Record Office in Chippenham. We are extremely grateful to Tom Rogers, of Worcestershire Archaeology, for giving us early sight of the broad results of the very important excavation work recently conducted by that unit at 8-13 High Street, Calne, and now fully reported on.

**NOTES**

Whereas Avon Archaeology Limited have taken all possible care to produce a comprehensive summary of the known and recorded archaeological evidence, no responsibility can be accepted for any omissions of fact or opinion, however caused.

**COPYRIGHT**

The copyright to the following text, drawings and photographs is, unless otherwise credited, the property of the author and Avon Archaeology Limited. Full joint copyright passes to the commissioners of the project upon the full settlement of the project account.

All enquiries should be addressed to:

Avon Archaeology Limited
Avondale Business Centre
Woodland Way, Kingswood
Bristol BS15 1AW
Telephone 0117 960 8487.

Email: mail@avonarchaeology.co.uk

Website: www.avonarchaeology.co.uk

Plans and maps based on the Ordnance Survey Sheets are reproduced by permission of the Controller of His Majesty's Stationery Office. ©Crown Copyright Reserved. Licence Number AC0000811125.

# 1 INTRODUCTION

**1.1** Avon Archaeology Limited was commissioned by Cedar Care Homes Limited to undertake an archaeological desk-based assessment of land currently occupied by the (now disused) Co-Op store and car park in Calne, Wiltshire. This project is intended to be a part of a formal planning application relating to the site, to involve the demolition of the existing entirely modern store building, and the space thus released, together with the former car park, used to construct a new care home, together with associated landscaping and car parking, on what would be effectively two separate but closely adjacent sites, north and south of the River Marden. The site encompasses a total of about 8,400m², and unusually, is split in two, north and south, by the course of a river, the Marden, which flows from east to west through Calne. The site is bounded on the south-west by the line of Mill Street, on the west by the Calne Free Church and the boundaries of private properties, on the south by existing houses, on the east by a combination of the River Marden and the private gardens of existing properties, and on the north by a road called The Pippin. The site sits in the centre of the historic town, immediately to the north of the medieval church of St Mary. Its postcode is SN11 0HT. It lies within the formally designated Calne Conservation Area, although the local authority does not currently have any formal Appraisal or Management Plan available relating to it. The centre of the site is given by OS NGR ST 99911 71017 (**Figures 1** and **2**).

**1.2** Internally, the site itself is of entirely modern form, with the store itself occupying a footprint of about 2,000m², and the rest being car park hardstanding. The date of construction of the present store building was the early 1970s, and it stands on the site of earlier buildings which were demolished to make way for it.

**1.3** There are no Scheduled Monuments either within the site boundary or indeed, anywhere nearby within the town itself. The nearest is probably the medieval moated site and fishpond at Pinhills, which is well outside the town and

©Avon Archaeology Limited: March 2026

just under 1.5km to the south-west of the site, in open countryside. As might be expected in the centre of a relatively small but very historic market town, however, there are numerous listed buildings in the immediate vicinity of the site. There are none to the north of the site, but to the west, and indeed hard against its western boundary, is the mid-19th century Calne Free Church; immediately to the south, on the southern side of Mill Street, are no fewer than three different groups of listed houses; and to the south-east, only just outside the site, is the surviving Calne Mill and associated mill house, the complex probably standing on or very clOse to the site of a much earlier, medieval mill. The proposed development site is therefore 'surrounded' on three sides, or parts thereof, by listed structures of one kind or another. These are enumerated in rather more detail in **Section 5** below (**Archaeological Background**). An OASIS record, which will eventually be linked to the Archaeology Data Service, has been opened for this project, under reference number avonarch2-506242. There is no HER number for this project, as the local authority archaeology service only assigns them *after* submission of the final report.

## 2 METHODOLOGY

**2.1** The methodology adopted here has been framed according to the main tenets outlined in the relevant guidance document issued by the CIfA for this kind of project – specifically in this case, *Standard and guidance for historic environment desk-based assessment* (2017). Searches were made of the indices of the collections of the Wiltshire Record Office (now known as the Wiltshire and Swindon History Centre); and a variety of online bibliographic resources, most notably JISC Library Hub Discover, the Archaeology Data Service, and Google Scholar, were used to identify potentially useful sources of information, whether

published or otherwise[1]. In addition, a full commercial trawl of the local authority's HER was carried out on behalf of AAL by the Historic Environment Record Data Section for Wilts. County Council, and the most salient results of that search have been incorporated in this report.

## 3 TOPOGRAPHY AND GEOLOGY

**3.1** At the time of writing, there was no formal topographical survey available for the site. However, the entire area of the site itself is to all intents and purposes level, at about 72m aOD. Bearing in mind its position right next to a river, even if only a relatively minor one, it is extremely unlikely that this was always the case, and the original, natural profile of the ground here has probably been somewhat modified over time, and increased in height. The site occupies a loop in the River Marden which probably found a use as low-lying, and potentially floodable meadow land well into the 19th century (see further below **Section 6, Historic Map Evidence**).

**3.2** As might be expected of a river valley location, the superficial (drift) geological basis of the site, according to the BGS, consists of riverine alluvial deposits. The age and physical characteristics of this material is described in general terms by BGS as

> Alluvium - Clay, Silt, Sand and Gravel. Superficial Deposits formed up to 2 million years ago in the Quaternary Period. Local environment previously dominated by rivers……These sedimentary deposits are fluvial in origin. They are detrital, ranging from coarse- to fine-grained and form beds and lenses of deposits

[1] https://discover.libraryhub.jisc.ac.uk/; http://archaeologydataservice.ac.uk/; www.scholar.google.com

> reflecting the channels, floodplains and levees of a river or estuary (if in a coastal setting) (BGS).

Underpinning this geologically recent drift material, however, the 'hard rock' geology consists of deposits of the Stanford Formation, a series of highly variable deposits but dominated by limestones, and in date, straddling the mid- to late-Jurassic period. BGS describes them as

> Shell detrital limestones, ooidal limestone, coralline limestone, fossiliferous marls, and interbedded limestone, marl and mudstone (BGS).

**3.3** There is currently no borehole information from the site itself; however, an extensive series of bores has been taken, at different times, not very far away, in an arc running to the north-west of the site. One example, of 10m depth, will suffice to give an idea of what might perhaps be expected from the study site under review here. This is BGS borehole log 397612, which was taken at a point about 100m to the north-west of the western corner of the study site, at OS NGR ST 99770 71060. This point is in the car park behind (ie immediately to the north-east of) Calne Public Library. Ground level at the top of the bore was at 70.10m aOD. Made ground extended down to a depth of 1.40m. From that point down to 4m depth, the geology consisted of natural coral rag, clayey sands with abundant limestone gravel and occasional cobble; for the remaining depth of the bore, from 4m down to 10m (where it terminated) was Oxford Clay, becoming increasingly stiff, laminated and fissured as depth increased. The base of the bore was at 60.10m aOD. Like the study area, this site is also not far from the river, but does not seem to have revealed any undisturbed alluvial deposits at the top of the bore, although it is possible that the made ground down to 1.40m depth consisted largely of heavily disturbed and redeposited alluvium.

©Avon Archaeology Limited: March 2026

# 4 HISTORICAL BACKGROUND

## Calne – General

**4.1** Calne is fortunate in having two major sources of information relating to its history and development, which are both authoritative and relatively recent. These are a volume in the series of Victoria County Histories for Wiltshire (hereafter VCH 2002), and separately, an archaeological Extensive Urban Survey published in 2004 (hereafter EUS 2004). Together these two sources provide a comprehensive overview of the town's developmental history, and therefore there is no need here to dwell at length on this aspect of the background to the present study site. What follows therefore is merely a brief review of what we consider to be the most salient points from those two sources, which will not be separately referenced in this account. Sources other than these will be referenced as necessary.

**4.2** Before the Norman Conquest, Calne already stood at the head of its own hundred, which even on its own is an indication of its high status within the local administrative hierarchy. The place-name, Calne, probably represents an older, pre-English (ie British) name for what is now the River Marden (Gover, Mawer and Stenton 1939, 256). Its meaning is, however, entirely unknown. The ultimate origins of the estate are probably to be found in its position at a convenient crossing point of the river, perhaps first by a ford, and later a bridge, reinforced by the fact of its position straddling the main road from London leading to the west, and most notably to Bristol. Certainly before the Norman Conquest, an extremely large royal estate, probably of ancient foundation (ie by the 7th century at the latest), had become established here; its antiquity as part of the royal demesne attested by the fact that it was not rated for tax in Domesday Book (1086), and indeed it is the very first entry in the entire Wiltshire DB, which always records the estates of the King first (Thorn and Thorn 1979). Although unrated for tax, it is likely to have been in the order of 30 hides in extent, since DB records land for 29 ploughs there (Higham 1990). The estate is noted in several pre-

conquest documentary sources, and it is clear that it was the site of a large royal hall, most likely occupying the area that by the medieval period had become known as 'Kingsbury', immediately to the south of the church of St Mary.

**4.3** Domesday Book notes no fewer than a total of nine mills in operation on the estate in the late 11th century, and while there is no need to assume that all of these were water mills, it is likely that the majority were, and that, as later on, they lay along the banks of what is now the River Marden. Prior to the Norman Conquest there was a small estate of five hides attached to the church, and this is usually taken as an indication that it was an ancient, and probably royal foundation, with the status of a minster (Blair 2005).

**4.4** A crucial point about the entry for Calne in Domesday Book is its mention of no fewer than 45 burgesses there. This is important because it is likely that Calne possessed distinctively urban affinities and characteristics, and indeed was probably regarded as a fully-functioning town, prior to the Norman Conquest. After the Conquest, Calne was certainly a legal borough in its own right.

**4.5** Both markets and fairs were granted to the two manors which had emerged in the town in the post-Conquest period, the main one entirely under secular control, with a subsidiary manor in the hands of Salisbury Cathedral by the end of the 11th century. The name 'Portstrete', now lost but attested in the medieval period, is one of the strands of evidence for this. The markets of the secular manor were almost certainly held on what would originally have been a very large open area in the very centre of the town, immediately to the west of the modern library building. The block of buildings on the eastern side of what is now an extension of Castle Street (known formerly as Hog Street), is clearly later infill of an original and far larger space. The church manor held its markets on what later became known as Kingsbury Green, immediately to the south of the church. A small,

©Avon Archaeology Limited: March 2026

triangular area of this land, amounting to just over 3,000m², remains as open amenity space in its south-eastern corner.

**4.6** The name Castle Street was attested by the end of the 16th century, and both this and recurring local tradition suggests the existence of a castle on the right bank of the river, on a small piece of rising ground forming a highly localised topographical high, somewhere to the north of Castle Street. Castle Field, which lay here, is attested by the late 15th century (Gover, Mawer and Stenton 1939, 260), and Castlefield House, a listed building of early 19th century date in its present form, although probably with antecedents of at least 17th century date, lies on its southern boundary. Of the supposed castle itself, nothing was known until relatively recently. It is certainly true that the proposed site, commanding a river crossing and an ancient routeway, in the heart of a massive and ancient royal estate, would lead us entirely to expect the existence of an early post-Conquest castle somewhere there. In 2010, geophysical survey by Bath and Counties Archaeological Society, on a site immediately to the south of Castle House, revealed part of a very large, regular, curvilinear feature, possibly containing rectilinear stone buildings, and the affinities of which might well be most closely compared to a Norman motte (BACAS 2010). This site was later investigated archaeologically, resulting in the discovery of 'a substantial round tower of a medieval date'. The existence of the castle at Calne therefore appears to be proven with reasonable confidence (HER MWI76441).

**4.7** With perhaps only a single exception (**Para. 4.8** below), there are no obvious elements of planned layout, as the town emerged onto relatively well surveyed maps in the 18th century. The eastern and western sides of the Wood Street/High Street axis was probably fully developed and laid down to tenement plots by the end of the 13th century, together with Church Street and Back Street. The very earliest elements of the 'original' settlement, most likely by the 7th/8th century, are likely to have been in the immediate vicinity of the church and the

likely position of the royal hall immediately to its south; but there is as yet effectively no hard archaeological evidence for this supposition, and it is unlikely to have been as extensive as postulated by the Calne EUS (2002, Figure 8).

**4.8** Perhaps the most intriguing element of the town's medieval layout, however, was the planned extension, possibly as early as the 11th century, to the east of the main settlement, and founded by the church on land it had been granted before 1086. This probably took the form of a small, planned village, laid out along streets oriented north-south, with a mill, demesne farm, and the farmsteads of customary tenants. By the 14th century, this little subsidiary settlement was known as Eastman Street (VCH 2002, 51). Even on modern maps, the outline of the new settlement has a distinct form which was clearly planned, in the shape of an irregular oval encircled by the road now known as The Pippin on all sides except the north (Oxford Road). This striking little enclave, a completely coherent and self-contained entity, represents, in effect, an urban deserted medieval settlement, which makes it all the remarkable that it is recognised by neither the Calne EUS (Figure 9), nor indeed by the County HER. However, its survival within a modern urban setting, even if only in outline, is truly extraordinary, and it is directly relevant for present purposes because the northern extremity of the study site runs right up to its southern boundary. It appears to have been completely deserted by the time of the 1828 mapping of the town, apart from a single building on its eastern side, which was a barn.

**4.9** By the end of the 19th century, the largest single business in the town was the bacon factory and curing works founded by Thomas Harris. It eventually came to occupy a sprawling site split into several parts centred on Mill Street, High Street and Church Street. The business seems to have been founded by the late 18th century – Harris himself was certainly in business as a 'bacon factor' by 1839 (WRO 1171/154); his firm grew to become the town's single largest employer, until its buildings were eventually demolished in the mid-1980s.

©Avon Archaeology Limited: March 2026

## The Study Site

**4.10** The history of the study site itself is somewhat obscure until the time of the earliest available maps of the town in the second half of the 18th century (see further below, **Historic Map Evidence**). From the site's position, however, very close to and to the east of what would have been the centre of the medieval town, it is very likely that at least some tenement plots had been laid out within the site boundary, fronting on to Mill Street, by the 13th or 14th century at the latest. This is speculation, however, and in fact the historic maps highlight the quite striking contrast in plot layout between the study site and the main body of the medieval town to the west and north, along the north-south axis of High Street and Wood Street. Here one sees the 'classic' medieval urban arrangement of long, narrow plots extending behind the street frontages, with the possibility that at least some of these properties were laid out to a standard width. As originally set out, some of the plots may have been wider than they appear as first mapped in the 18th century, with subsequent subdivision along the longitudinal axis of the plot. We would expect this development to be most pronounced around the former main market place, where demand for street frontage properties, and therefore rents, would be highest.

**4.11** The layout of the plots within the study site, at least as they emerge on the earliest useful maps of the town, are quite different, and appear instead to be composed of a series of rectilinear 'blocks' of land, of varying size. Well into the late 19th century, most of the site lay open and undeveloped, spilt north and south, as indeed it always had been, by the River Marden. The earliest available map, of 1728, does not show the site in detail, but it is likely, as we have already noted, that at least the Mill Street frontage had become developed by the end of the medieval period. In the later 19th century, a terrace of modest houses was built at the northern side of the site, running east-west along the southern side of The Pippin; and a cinema opened between 1900 and 1915 in the northern part of Mill Street (VCH 2002). All of these earlier buildings, including houses at the southern

©Avon Archaeology Limited: March 2026

side of the site, and a mid-Victorian school on the western side, were swept away in the 1970s for the site of the new store and its car park. As already noted, therefore, while we would have expected at least some medieval settlement along the Mill Street frontage, it is simply the case that the state of the site *prior* to the early 18th century, and the level of development within it, is entirely unknown. It is perfectly possible, though, that traces of at least some of the structures mapped on the early edition OS maps within the site boundary, may survive archaeologically.

**4.12** The very detailed map of Calne dated 1828 (see further below, **Historic Map Evidence**) shows that at the extreme south-western corner of the study site, there lay a circular structure. This is the only occasion on which this structure appears to be depicted on a map, and its existence is not noted on the HER. In terms of possible function, there are a limited number of options for a relatively small building of this highly distinctive form, the most obvious being a dovecote (unlikely in a central urban setting), a small lock-up or jail, or a limekiln. We have unfortunately been unable to identify exactly what this structure is, and its site now seems to lie under the store building, although there is at least a theoretical possibility that it may survive archaeologically either partially or completely.

## 5 ARCHAEOLOGICAL BACKGROUND

**5.1** A trawl of the local authority Historic Environment Record was conducted on behalf of AAL by the HER Data Manager for Wiltshire County Council, Jacqueline Ramsay. The sweep took in an area encompassing a radius of 250m from the centre of the study site. Both the maps and the text arising from this exercise are presented here as part of the **Appendix**, so that the detail of each entry can be accessed if necessary. As is standard practice with HER reports, the results are split into three sections, one covering Monuments (ie actual *sites* of known

interest), another dealing with Events (ie archaeological work, of whatever kind, which has been recorded as having taken place on, or being related to, a specific site); and the third, Listed Buildings. We will first note that the HER trawl returned no Listed Buildings, Monuments, Scheduled Monuments or Events, within the boundary of the study site itself (**Figure 2**), although we would reiterate that it lies firmly within the Calne town centre Conservation Area. As we have already noted (above, **Para. 1.3**), the closest SM to the study site appears to be the moated site at Pinhills, outside the town to the south-west. There is a listed building immediately to the west of the study site, effectively along its western boundary, and there are numerous listed buildings to its south, in the vicinity of the church. We will look briefly in turn at those items from the trawl which are considered most salient for present purposes, and will concentrate on those which are physically closest to the site. The full return from the trawl is, however, provided within the **Appendix**.

### 5.2 Monuments

Of this element of the HER trawl, there are really only six items which might be considered as immediately relevant for present purposes. **MWI5197**, to the north-west of the site across the River Marden, records a small group of medieval pottery sherds found during an evaluation in 1997, and which were, anyway, considered to be residual. Archaeologically therefore they are of extremely limited value. **MWI5176** related to a site on the northern side of The Strand, not far to the west of the study site. This is potentially of more interest, as it records the discovery of ceramics of Romano-British date here; the exact nature of any activity with which this find may be associated is unclear, although it is most likely to represent an individual farmstead or small agricultural settlement somewhere nearby. The same site, which was in fact the former Harris Bacon Factory, also yielded material of medieval date (**MWI5191**), which in the wider context would be entirely expected. Both of these records relate to material which was very poorly-recorded at the time of expansion work at the bacon factory after World

©Avon Archaeology Limited: March 2026

War 2. **MWI5215** (also recorded as an Event under **EWI3567**) is an extremely important record as it relates to the discovery of at least one, and probably more in situ burials, of likely medieval date, just outside the churchyard boundary. This is significant because, as an early-founded minster church, it is likely that the burial ground of St Mary's was originally, in effect, unbounded, and burials could extend out for a considerable distance around it. The formal bounding of Christian graveyards in western Europe was a surprisingly late development, often not occurring until the 10th and 11th centuries or even later (Zadora-Rio 2003). There is, then, at least the theoretical possibility that, originally, burials may have extended northwards from the area immediately around St Mary, into the southern part of the study site. **MWI5214** relates to a rather similar discovery, involving human bones, in 1989, but in this case they were revealed in the course of a controlled excavation, albeit under rescue conditions; and although the *exact* find spot cannot be calculated from the published grid reference of the work, it seems at least likely to have been within the boundary of the present church graveyard.

**5.3** **MWI5216** (also recorded under Event **EWI9423**) is on a site just to the east of the study area, a few metres to the west of The Vicarage. This again involved the discovery, in 2002, of a small group of in situ human burials, probably (although not certainly) of medieval date, in part of what appears to have been a formal graveyard. It is just under 100m to the north-east of the church and therefore unlikely to be related to it. The HER attributes the burials to the site of a medieval 'monastic lodge or retreat', although there is no firm evidence for this suggestion. A hospital might well, however, give rise to the need for a burial ground, and the VCH describes how

> A hospital, in which St. John the Baptist and St. Anthony were invoked, stood in the town from 1248 or earlier……In 1442 part of its endowment was transferred to a chantry in Heytesbury church…..1535 its net income, £2 2s. 8d., was low…..and in 1546 it was providing no accommodation for poor people. (fn. 96) The Crown sold the hospital and its remaining endowments in 1548…..in the earlier 14th century the hospital was approached by a road leading from Church Street and stood near a watercourse: its site, which was not otherwise described, could have been in Mill

Street, north-east of Butcher Row, or between Church Street and Patford Street (VCH 2002, 41).

At present therefore the exact historical context for this small but important group of burials must be regarded as unsolved. It is very unlikely, though, that burials related to the same site extended across the course of the River Marden, immediately to the west, and into our study area. **MWI9216**, very close by, is the site of the present vicarage, but was formerly the rectory, and possibly established on this site by the 13th century. If this is the case though, as essentially a dwelling house, it is unlikely to represent the correct context for the burials found immediately to its west (see above, **MWI5216**).

### 5.4 Events

As before, the full list of this element of the HER trawl, within the search area, is found within the **Appendix**, and therefore only the most salient, in relation to the study site, will be included in the following brief review. The first record, **EWI8852**, relates to an evaluation on a site off the western side of The Pippin. However, this record has now been superseded by a subsequent, full excavation of the same site, carried out in the autumn of 2021 (**EWI10243**). The site would have represented the back plots extending behind (ie to the east of) medieval tenements fronting on to the High Street and now occupied by numbers 8-13. The work found extensive remains and material of medieval date, including pits and ditches, although at least one of the latter was out of alignment with the medieval plot boundaries, and probably predated them. Radiocarbon dating has confirmed a late Anglo-Saxon or early post-Conquest date for at least some of these antecedent features, although the roughly east-west plot alignment as it emerged, fossilised, into the era of modern maps, is probably of the late 11th or 12th century (WA 2023). The plot boundaries eventually came to be constructed of substantial masonry walls, although it is unlikely that this was their original form. A lime kiln

and cisterns were among later features recorded[2]. This site is only 120m or so to the north-west of the present study site, and may therefore have implications for the latter; although that said, the level of survival on the High Street site probably owes much to the fact that the greater part of it apparently remained open and undeveloped up to modern times. Contrast these findings to **EWI3565** (below).

**5.5** Immediately to the south of this site, on a piece of ground immediately to the east of the public library, a desk-based assessment in 1997 was followed by an evaluation (**EWI3565**). In terms of significant archaeology, the evaluated areas were entirely negative, finding only modern (19th-20th cent.) made-up ground, building foundations and alluvium. This area is only 60m or so to the north-west of the study area, and may well have implications for the nature of whatever might be expected to survive archaeologically on the latter site. A series of Event records cluster around the church, and are of limited relevance for present purposes. **EWI6976** and **6977** refer to watching briefs on a series of pits dug in the churchyard for unspecified purposes in 2009, and which were entirely negative.

**5.6** Finally in this review of the immediate archaeological context of the study area, **EWI9382** was an important and major recording exercise in 2019, undertaken in response to the proposed installation of a new swimming pool in the garden immediately to the north-east of the old vicarage house, on the northern side of Mill Street. This site is only about 75m to the east of the study site's eastern boundary, although separated from it by the course of the River Marden. As we have already noted, it is likely that the wider area of the present vicarage saw fairly extensive activity in the medieval period, and there is every possibility that the vicarage building, now of chiefly 19th century date, stands on

[2]We are extremely grateful to Tom Rogers, of Worcestershire Archaeology, for giving us sight of a summary of the main findings of this work prior to the production of the full client report.

or close to a much earlier site. Two ditches oriented north-south and described as substantial were recorded, and were dated to the medieval period as originally cut, although appeared still to be being backfilled in the post-medieval period. A few pieces of disarticulated human bone were also recovered, but there were no building remains. The report suggests that the ditches may represent the eastern extent of the supposed medieval 'monastic lodge' that tradition places on this site; although there is no firm evidence whatsoever for such an attribution, documentary or otherwise (VCH 2002).

### 5.7 Listed Buildings

As might be expected of a historic town such as Calne, and especially within its designated central Conservation Area, this is the single most numerous category of the three types of HER entry which are presented here. The overwhelming majority of the listed structures in Calne are concentrated, not unexpectedly, in a circle around, and close to the church, and therefore it is the most northerly of this group which are physically closest to the study area. By their very nature, listed buildings will not suffer any direct, *physical* impact from surrounding development because they are protected. Overwhelmingly, the chief concern for development proposals in terms of these structures, therefore, involves an assessment of impact on their *setting,* as reflected in the formal Historic England guidance relating to such matters (Historic England 2017). For the present proposal this is being dealt with in a separate, dedicated report, and we will briefly review here only those listed buildings which could be said to be in the immediate orbit of the site.

**5.8** The building which is by far the most directly related to the site, by simple fact of its being closest to it, is the Calne Free Church, which directly abuts the site's western boundary (**DWI5983**). The space between the eastern wall of the church and the western wall of the still extant Co-Op store building is a matter of metres, although it is proposed to open up a new, wider pedestrian access

pathway in this position as part of the development. The church itself is a mid-19th century building and is Grade II listed.

**5.9 DWI5914, 5917** and **5919** are the three most northerly listed structures in the group, only 15-25m away, on the southern side of Mill Street, around the church, and therefore closest to the site. They are all town houses and most contain fabrics of varying dates from the 17th to the 19th centuries. All are listed at Grade II level, and the only implications they have in the present context are in relation to matters of setting, as we have already noted. **DWI5980** and **5979** are closely related, as they are attached, respectively, to Calne Mill and the building known as Pond Cottage which is physically attached to its western gable end. The latter appears to have been a house for the miller. Both are Grade II listed. The house is dated to the early and/or mid-19th century, the mill to the mid-19th century. What is important in this context however, as well as the standing buildings themselves, is the possible date of the *site*, and as we have already seen it is possible that there was a mill here by the 13th century or even perhaps earlier. On the opposite (ie southern) side of Mill Street, slightly to the west of Calne Mill and Pond Cottage, is a supposedly related terrace of small houses, 14-20 Mill Street, listed as a group at Grade II, although of slightly varying dates, between the mid-18th and 19th centuries (**DWI5981**). No. 20 lies behind no. 19 and is accessed from a narrow passageway running down the western gable end of no. 19. Another house at the western end of this little terrace, **DWI5982**, is no. 21 Mill Street, is also Grade II listed, and is of late 17th century date. There are differences in the rooflines even within this group, however, with the eastern half of the row having a slightly hipped roofline. It seems likely from historic map evidence (see further below) that no. 19 is in fact infilling a gap which is shown on an early 19th century map between modern nos. 21 and 18; if this is indeed the case, then no. 19 must be later than 1828, the date of the map. The current orthodoxy regarding these houses is that at least some of them were constructed for millworkers, although the hard evidence for this suggestion is not entirely

©Avon Archaeology Limited: March 2026

clear, other than interlinked attics used supposedly for the drying of wool. It is notable, however, that the HER, following the formal Historic England listing description, says only that these houses are *said* to have been constructed for millworkers. Although the southern boundary of the study site lies only 30m to the north of this group of buildings, they are effectively 'shielded' from it by the houses on the northern side of Mill Street, which almost completely block intervisibility between the two. Only no. 21, at the westernmost end of the row, has a clear line of view northwards, towards the proposed development site.

### 5.10 Recommendations to HER:

- That the planned medieval settlement of Eastman Street should be added to the Wiltshire County HER.
- That the site of the former Harris Bacon Factory should have an entry in its own right, with details on its origins in the late 18th century, later development, and demolition in the late 20th century.
- That the site of the circular structure of unknown function shown on the 1828 map of Calne should be added to the HER
- That the site of the former pound of Calne Hundred should be added to the HER
- That the school building associated with the Calne Free Church should be added to the HER
- That the site of the former Regent Cinema should be added to the HER
- That the geophysical survey undertaken by BACAS in 2010, relating to the possible site of Calne 'castle', should be added to the Events section of the HER.

## 6 HISTORIC MAP EVIDENCE

**6.1** As a historic town it is no surprise to find that Calne was mapped from a

relatively early date, but the earliest surviving large-scale town plan, dated 1728 (WRO 1171/140(H)), unfortunately does not depict the site itself, and so we do not present it here as a figure. Interestingly, however, at the bottom of this map, a small table of landowners and acreages relating to a single furlong (Black Furlong), has been added, clearly later on, with the intention of correcting various errors in the figures. This table refers to those errors as having been made 'on the plan in 1774', so it is possible that a plan of that date has now been lost. The earliest *usable* map which was available for present purposes, and which shows the area of the site itself, is here reproduced as **Figure 3.** It is dated exactly a century later, 1828, and is the work of Thomas Cruse (WRO 3302/42L). This map shows that by the early 19th century, the western and southern peripheries of the site, serving the Mill Street frontages, were pretty well built up. The greater part of the 'interior' of the site, however, even at this relatively late date, remained open and undeveloped. A schedule of plots accompanies this map, linking each number to details of ownership, land use and size (WRO 1409/7/2). This shows that, compared against the site in its present state, a great number of earlier buildings and features now lie underneath it, or have been destroyed. On the west side of the site, plots 187-195, and 198-201, are all modest houses, and all now gone. 181 is the Bear Inn, later the site of the still extant Calne Free Church; 182 is a house, workshops and yard (purpose unspecified in the schedule); 183 is a brewhouse, sheds and yard, possibly related to the Bear Inn; 184 is a coalhouse and yard; 202 are stables and a yard; 205 are a house, offices and court; and 206 are described as 'warerooms' (?warehouse) and yard.

**6.2** At the southern side of the site, 207 and 209 are houses, offices and yards. Plot 208, however, 'sandwiched' between these two, is recorded as a 'candle factory', and we think it is possible that this small business arose because its raw material is very likely to have been tallow, arising as a by-product from the meat-processing concerns very close by. From the map it looks as though this may be the building now designated as 6 Mill Street, and possibly 5 Mill Street

(immediately to its west) as well. On plot 204, at the eastern side of the site, a long narrow pond with rounded ends is recorded, with a small building at its northern end. This feature is now underneath the car park on the eastern side of the modern Co-Op site. Its function is unclear, and while it may of course have had some decorative element, it might also have provided fish for the table of the owner. We estimate that it was in the order of 26m in length and 7-8m wide depending on the accuracy of the survey. This is the only map on which it is explicitly depicted and it must have been backfilled after 1843 (see further below). It is possible, however, that it survives archaeologically.

**6.3** Although lying strictly outside the boundary of the present study site, the most intriguing feature which appears on this map is also, unfortunately, the most enigmatic. This is a circular structure of entirely unknown function. Neither it, nor the plot on which it stands, is identified by a number that would refer it to the schedule already noted. It is our view that this is most likely to be a small bridewell or overnight lockup, of 18th or early 19th century date, such as, for example, the late 18th century example at Ruabon, near Wrexham, Wales (**Figure 5**). These are relatively common structures within small to medium size historic market towns, and while by no means all were circular, it was the most prevalent form for this kind of small building.

**6.4** This map also gives the first really detailed depiction of the former planned village extension called Eastman Street, which we have already noted as being of possibly 11th century foundation (**Figure 4**). By this date, the enclosure was given over almost entirely to arable within three large fields, with a scatter of smaller, pasture enclosures on its eastern side. However, the entire internal space of this tightly delineated area was by this date known as Cop Croft, which survives as the name of a small, modern alleyway. The former Eastman Street settlement was uninhabite, apart from a few small cottages on its northern side, fronting onto the southern side of what is now the Oxford Road. The walled plot numbered 87 was

©Avon Archaeology Limited: March 2026

a remarkable survival, and was the pound for the entire hundred of Calne. Its site now lies under houses. A remarkable feature is the north-south wall which runs the entire length of the Eastman Street 'enclosure', dividing it in half, east-west. This would have been about 210m in length. Its course is preserved in the alignment of the modern Cop Croft, at the northern side of the site, is interrupted by the Sainsbury's supermarket building, and then picked up again to the south by the small access road into the Sainsbury's car park.

**6.5** The tithe map for Calne is dated 1843, but as the cartouche on it makes clear, it was actually based on Thomas Cruse's earlier survey of 1828 (see above). We present a relevant extract from it here as **Figure 6** (WRO Calne T/A). Unfortunately, the Calne map is less useful than many because it gives very little useful detail in the centre of the town, where the study site actually lies. This may be because, as the preamble to the tithe award states,

> All cottage gardens throughout the said parish are by prescription absolutely exempt from any render of tithes…….[and] the vicarial glebe land of the said parish is by prescription absolutely exempt from any render of tithes…….

**Table 1** shows the owners, occupiers, plot names, sizes and uses of a small selection of plots on and around the study area. From the tithe map, it is clear that the entire northern two-thirds of the study site was exempt from tithes. Within the site boundary, all it is possible to say with any certainty, if this survey is to be taken at face value, is that the long narrow pond at the eastern side of the site, identified from the earlier map of 1828, remained extant some fifteen years later. No other details can be discerned, and the fate of the enigmatic circular building at the southern side of the site, also identified in 1828, is unknown by this date. Regrettably there are no tithe field/plot names from either the study site or its immediate vicinity which can be regarded as in any sense

©Avon Archaeology Limited: March 2026

archaeologically indicative[3].

| Owner | Occupier | Plot no. | Plot name | Land use | A | R | P |
|---|---|---|---|---|---|---|---|
| Henry Petty FITZMAURICE, Marquis of Lansdowne, prebendal estate | Charles CARTER | 450 | Gardens/ garden | | 0 | 0 | 25 |
| Lord Hungerford CREWE | Lord Hungerford CREWE | 451 | Field gardens | Arable | 0 | 2 | 36 |
| Lord Hungerford CREWE | Lord Hungerford CREWE | 452 | Field gardens | Arable | 1 | 1 | 21 |
| Henry Petty FITZMAURICE, Marquis of Lansdowne, prebendal estate | Henry Petty FITZMAURICE, Marquis of Lansdowne | 453 | Field gardens | Arable | 2 | 2 | 10 |
| Henry Petty FITZMAURICE, Marquis of Lansdowne | William PARRY | 454 | Yard and buildings | | 0 | 0 | 12 |
| Revd John GUTHRIE, glebe | Revd John GUTHRIE | 462 | Paddock | Pasture | 0 | 2 | 31 |
| Revd John GUTHRIE, glebe | Revd John GUTHRIE | 463 | Vicarage house and premises | | 1 | 0 | 16 |
| Henry Petty FITZMAURICE, Marquess of Lansdowne, prebendal estate | Revd John GUTHRIE | 464 | Buildings and yard | | 0 | 1 | 19 |
| Henry Petty FITZMAURICE, Marquis of Lansdowne, prebendal estate | George BLEADON | 465 | Mill, outbuildings and yard | | 0 | 0 | 19 |
| Henry Petty FITZMAURICE, Marquis of Lansdowne, prebendal estate | Robert BOWMAN | 466 | Garden and pond | | 0 | 2 | 7 |
| Thomas Ebenezer CLARKSON | Henry KING | 481 | Garden | | 0 | 1 | 2 |

**Table 1: Data from tithe award for Calne** (Wiltshire Record Office)

[3]See for example http://www.wikiarc.org/fieldnames

**A – Acres; R – Roods; P – Perches**[4]

**6.6** The First Edition OS 25" map of the study site (Wiltshire Sheet 27.5, surveyed 1885, published 1886) is best directly compared not with the tithe map, but with the far more detailed survey of 1828. The relevant extract from the OS sheet is presented here as **Figure 7**. By far the greatest changes have been at the western and northern peripheries of the site. Between 1828 and 1885, a row of houses had been constructed occupying virtually the entire length of the site's northern boundary, along the southern side of what is now The Pippin. On the western side, the main change has been twofold: the appearance of a new school on a plot fronting onto the eastern side of Mill Street, formerly occupied by a warehouse (plot 206 in 1828); and further to the north, just outside the site boundary, the appearance of the Calne Free Church, built in the late 1860s, and immediately to *its* north, another new school building. These new features together necessitated the removal of all the former structures lying just outside the study site's western boundary, and for the first time, established the line of that boundary as it remains to this day. However, the various houses and non-domestic structures just *within* the site boundary, numbered 182-195 on the 1828 map, survived onto the First Edition OS map. The school building next to the church does not appear on the HER, but it seems very likely that it was constructed from the outset in association with, and run by, the Free Church.

**6.7** At the eastern side of the site, the long narrow pond shown on both the 1828 map, and the tithe map, had gone by the time of the First Edition OS map, presumably backfilled. However, the outline of the enclosure in which it lay is still clear on the OS map, from which we can see that, since 1828, a small group of non-domestic buildings had appeared in its south-eastern corner. The circular building at south-west corner of the site, suggested here as an 18$^{th}$ or 19$^{th}$ century

[4]There were traditionally 4 roods to the acre, and 40 perches to the rood. An acre is the equivalent of 0.405ha (or just over 4,000m$^2$), and this therefore makes a rood about 1012m$^2$, and a perch just over 25m$^2$.

lockup, had also gone, although its site appears to have remained undeveloped, and looks as though it had become attached to the new school, possibly as part of its playing area. However, by far the greater part of the area actually within the site boundary at this time, on its eastern side and bounded by the River Marden, remained open and undeveloped.

**6.8** The Second Edition OS 25" map (same sheet number) was revised in 1899, and shows very little discernible change from fourteen years earlier; we therefore do not present it here as a formal figure. The only new piece of information for present purposes is that the school at the south-western corner of the site is by this date explicitly identified as being for infants.

**6.9** The Third Edition OS map (same sheet number) was revised in 1922 (**Figure 8**). The major change so far as the site itself is concerned is the appearance of a cinema at its western side, fronting onto the eastern side of Mill Street and replacing the large building numbered 205 on the map of 1828, which had survived intact up to this point. The cinema had in fact been constructed by 1915, originally as Taylor's Electric Cinema Theatre, latterly as The Regent, and was removed only in the 1970s (VCH 2002). Its site lies directly below the current Co-Op store building. It is mentioned in neither the Calne EUS nor the county HER, but the very first appearance of a cinema in any location is regarded as a highly significant development by social historians.

**6.10** The OS 25" map revision of 1936 shows no discernible change on the site for present purposes, and indeed, this is the last easily accessible OS map prior to what amounted to, effectively, the complete clearance from the study site, in the 1970s, of all the earlier structures on it, and the construction of the store and its associated car parking areas. We therefore do not present it here as a figure.

©Avon Archaeology Limited: March 2026

**6.11** Taking the archaeological and historic cartographic evidence together, it is our view that, within the site boundary itself, there is at least potential for survival of remains of the following features:

- All the structures depicted as extant at the time of the First Edition OS map (**Figure 7**), most notably the school at the south-western side of the site, houses and commercial buildings to its north-west, and the row of modest cottages (presumably originally a terrace) and the northern extremity of the site, on the southern side of The Pippin.

- The remains of the later cinema at the western side of the site (**Figure 8)**

- The remains of the long, cigar-shaped pond at the eastern side of the site, depicted on the map of 1828, and the tithe map (**Figures 3** and **6**).

- The circular structure depicted only on the map of 1828 (**Figure 3**) outside but close to the lower south-western boundary of the site, immediately to the south-east of what later became the site of the school.

It is perfectly possible that at least some of those structures depicted on the map of 1828, along the western side of the site, may already have been old at that date, and indeed the same goes for the pond on the eastern side, which might find some logic in the context of a medieval monastic fish pond; alternatively, it may be related to water management for the mill which lies just to its south. In addition, there may be any number of earlier structures or features surviving archaeologically which never found their way onto any map. This might be especially true of those parts of the site which remained open and undeveloped well into the 20th century, and which even with the construction of the present store building, remained only as car parking areas on its eastern and northern sides.

©Avon Archaeology Limited: March 2026

# 7 NATIONAL AND LOCAL PLANNING POLICIES

**7.1 National Planning Policy.** The current national legislative and planning policy system identifies, through the National Planning Policy Framework (NPPF), last substantively updated in Dec. 2024. It states that applicants should consider the potential impact of development upon 'heritage assets'. This term includes: designated heritage assets which possess a statutory designation (for example listed buildings and conservation areas); and non-designated heritage assets, typically compiled by Local Planning Authorities (LPAs) and incorporated into a Local List or recorded on the Historic Environment Record.

**7.2** Where any development may affect certain designated heritage assets, there is a legislative framework to ensure proposed works are developed and considered with due regard to their impact on the historic environment. This extends from primary legislation under the Planning (Listed Buildings and Conservation Areas) Act 1990. The relevant legislation in this case extends from section 66 of the 1990 Act which states that special regard must be given by the decision maker, in the exercise of planning functions, to the desirability of preserving or enhancing listed buildings and their setting. The meaning and effect of these duties have been considered by the courts in recent cases.

**7.3** The detail of such cases need not concern us here but the essential outcome of various litigations was that a succession of courts agreed that Parliament's intention in enacting section 66(1) was that decision makers should give '*considerable importance and weight*' to the desirability of preserving (i.e. keeping from harm) the setting of listed buildings. Section 69(1) of the Act requires LPAs to 'determine areas of special architectural or historic interest the character or appearance of which it is desirable to preserve or enhance' and to designate them as conservation areas. Section 69(2) requires LPAs to review and, where

necessary, amend those areas 'from time to time'. For development within a conservation area section 72 of the Act requires the decision maker to pay

> '*special attention* […] *to the desirability of preserving or enhancing the character or appearance of that area*'.

The duty to give special attention is considered commensurate with that under section 66(1) to give special regard, meaning that the decision maker must give considerable importance and weight to any such harm in the planning balance. However, as the site is not located within a Conservation Area, section 72 is not relevant for present purposes.

**7.4** The *National Planning Policy Framework* (NPPF), was last substantively revised in Dec. 2024, and is the principal document that sets out the Government's planning policies for England and how these are expected to be applied. It defines a heritage asset as a: 'building, monument, site, place, area or landscape identified as having a degree of significance meriting consideration in planning decisions, because of its heritage interest'. This includes both designated and non-designated heritage assets. Section 16: *Conserving and Enhancing the Historic Environment* relates to the conservation of heritage assets in the production of local plans and decision taking. It emphasises that heritage assets are

> '*an irreplaceable resource, and should be conserved in a manner appropriate to their significance*'.

**7.5** For proposals that have the potential to affect the significance of a heritage asset, paragraph 189 requires applicants to identify and describe the significance of any heritage assets that may be affected, including any contribution made by their setting. The level of detail provided should be

proportionate to the significance of the heritage assets affected. This is supported by paragraph 190, which requires LPAs to take this assessment into account when considering applications.

**7.6** Under '*Considering potential impacts*' the NPPF emphasises that '*great weight*' should be given to the conservation of designated heritage assets, irrespective of whether any potential impact equates to total loss, substantial harm or less than substantial harm to the significance of the heritage assets. Paragraph 195 states that where a development will result in substantial harm to, or total loss of, the significance of a designated heritage asset, permission should be refused, unless this harm is necessary to achieve substantial public benefits, or a number of criteria are met. Where less than substantial harm is identified paragraph 196 requires this harm to be weighed against the public benefits of the proposed development. Paragraph 197 states that where an application will affect the significance of a non-designated heritage asset, a balanced judgement is required, having regard to the scale of harm or loss and the significance of the heritage asset.

**7.7** Paragraph 200 of the NPPF notes that local planning authorities should look for opportunities for new development within Conservation Areas and World Heritage Sites and within the setting of heritage assets to enhance or better reveal their significance. It also states that proposals that preserve those elements of the setting that make a positive contribution to, or better reveal the significance of, the asset should be treated favourably.

**7.8** The *Planning Practice Guidance* (PPG) has been adopted in order to aid the application of the NPPF. It reiterates that conservation of heritage assets in a manner appropriate to their significance is a core planning principle. Key elements of the guidance relate to assessing harm. It states that substantial harm is a high bar that may not arise in many cases and that while the level of harm

©Avon Archaeology Limited: March 2026

will be at the discretion of the decision maker, generally substantial harm is a high test that will only arise where a development seriously affects a key element of an asset's special interest. It is the degree of harm, rather than the scale of development, that is to be assessed.

**7.9** Conservation Principles outlines Historic England's approach to the sustainable management of the historic environment. While primarily intended to ensure consistency in Historic England's own advice and guidance, the document is recommended to LPAs to ensure that all decisions about change affecting the historic environment are informed and sustainable. The guidance describes a range of heritage values which enables the significance of assets to be established systematically, with the four main heritage values being: evidential value; historical value; aesthetic value; and communal value.

**7.10** The PPS5 Practice Guide was withdrawn in March 2015 and replaced with three Good Practice Advice in Planning Notes (GPAs) published by Historic England. *GPA1: The Historic Environment in Local Plans* provides guidance to local planning authorities to help them make well informed and effective local plans. *GPA2: Managing Significance in Decision-Making* includes technical advice on the repair and restoration of historic buildings and alterations to heritage assets to guide local planning authorities, owners, practitioners and other interested parties. *GPA 3: The Setting of Heritage Assets* replaces guidance published in 2011. These are complemented by the Historic England Advice Notes in Planning which include *HEA1: Understanding Place: Conservation Area Designation, Appraisal and Management* (February 2016), *HEA2: Making Changes to Heritage Assets* (February 2016), *HEA3: The Historic Environment and Site Allocations in Local Plans* (October 2015), and *HEA4: Tall Buildings* (December 2015).

©Avon Archaeology Limited: March 2026

**7.11 Local Planning Policies.** Specifically for Wiltshire, planning policy is provided by the adopted 2015 Core Strategy and saved policies from the North Wiltshire Local Plan 2011. The 2015 Core Strategy has the following policy relevant for present purposes:

**Core Policy 58 - Ensuring the conservation of the historic environment**

*Development should protect, conserve and where possible enhance the historic environment. Designated heritage assets and their settings will be conserved, and where appropriate enhanced in a manner appropriate to their significance, including:*

*i Nationally significant archaeological remains*
*ii World Heritage Sites within and adjacent to Wiltshire*
*iii Buildings and structures of special architectural or historic interest*
*iv the special character or appearance of conservation areas*
*v historic parks and gardens*
*vi important landscapes, including registered battlefields and townscapes*

*Distinctive elements of Wiltshire's historic environment, including non-designated heritage assets, which contribute to a sense of local character and identity will be conserved, and where possible enhanced. The potential contribution of these heritage assets towards wider social, cultural, economic and environmental benefits will also be utilised where this can be delivered in a sensitive and appropriate manner in accordance with Core Policy 57 (Ensuring High Quality Design and Place Shaping).*

©Avon Archaeology Limited: March 2026

*Heritage assets at risk will be monitored and development proposals that improve their condition will be encouraged. The advice of statutory and local consultees will be sought in consideration of such applications.*

**7.12** The North Wiltshire Local Plan 2011 has the following saved policies which are relevant to this assessment:

**Policy HE6 – Locally Important Archaeological Sites**

*Development in defined areas of special archaeological significance, or in other locally important archaeological sites, will only be permitted where:*

*i Any archaeological remains would be unaffected by the proposals, or;*

*ii Satisfactory measures are taken to ensure the physical preservation of any archaeological remains in situ, or;*

*iii In cases where the significance of any archaeological remains is outweighed by the need for and benefits of the development, satisfactory measures are taken to excavate and record the site and its remains.*

**Policy HE8 – Archaeological Evaluation**

*Where any nationally or locally important archaeological site or historic building is likely to be affected, applicants will be requested to submit an archaeological evaluation before planning permission is granted.*

*Where necessary, adequate archaeological investigation and recording will be required before, and/or during, building or other operations, in order to*

*safeguard important evidence which might otherwise be destroyed without record.*

The above policies remain material considerations in accordance with Section 16 of the NPPF, and are given weight according to their consistency with the NPPF. As we have already noted, there are no buildings of any historic interest whatsoever within the bounds of the study site itself, and there is a single listed building (Calne Free Church) which is extremely close to the site on its western side.

**7.13** Matters of setting in relation to this site will be dealt with in a separate Heritage Impact Assessment report, to be produced as part of the same project by Nash Partnership.

## 8 CONCLUSIONS

**8.1** This desk-based assessment has been undertaken in relation to proposals to develop a site on the northern side of Mill Street, Calne, Wiltshire, which is presently occupied by a large former Co-Op store building and its associated car parking. The store building is to be entirely removed, and the site redeveloped for mixed retail, residential and amenity use.

**8.2** The wider history of Calne is that it is likely to have emerged in the middle Anglo-Saxon period as a very large royal estate with a minster church. The presence of a large royal hall somewhere in the vicinity of the church, in the area later known as Kingsbury, is suspected. At some point, perhaps in the 11$^{th}$ century, an entirely new, planned settlement, known later as Eastman Street, was founded on the eastern side of the original town. In the medieval and post-medieval

©Avon Archaeology Limited: March 2026

periods, Calne developed as a regional market and manufacturing centre of some significance.

**8.3** The local authority HER does not show any known heritage assets within the site boundary itself, although we have suggested a number that might beneficially be added to it. A listed building, Calne Free Church (Grade II), abuts hard against the site's western boundary. Buildings shown on historic maps might have left archaeological traces, and there may be features surviving archaeologically from periods prior to mapping; this possibility has been demonstrated by the as yet unreported excavation project not far to the north at 8-13 High Street. It seems unlikely, however, that much, if anything, would survive directly underneath the footprint of the present Co-Op store building. The areas of open car parking to its east and north seem to us to offer the greatest chance of survival of in situ archaeology, including the 'detached' part of the site to the north of the River Marden.

**8.4** On balance therefore, we consider that the purely *archaeological* potential of the site is likely to be low to moderate.

©Avon Archaeology Limited: March 2026

# 9 BIBLIOGRAPHY AND PRIMARY HISTORICAL SOURCES

## Published Works and Websites

**ADS** (Archaeology Data Service)
http://archaeologydataservice.ac.uk

**BACAS, 2010**
*Was There a Castle at Calne?* Bath and Counties Archaeological Society.
https://www.bacas.org.uk/wp-content/uploads/2017/08/2011-24-27.pdf

**BGS**
*Geology of Britain Online Viewer*. British Geological Survey
http://mapapps.bgs.ac.uk/geologyofbritain/home.html

**Blair, J., 2005**
*The Church in Anglo-Saxon Society.* Oxford.

**COPAC** (Joint Universities and British Library online bibliography)
www.copac.ac.uk

**EUS, 2004**
*Extensive Urban Survey: Calne.* Phil McMahon, Wiltshire County Archaeological Service.
https://archaeologydataservice.ac.uk/archives/view/wiltshire_eus_2009/downloads.cfm?REDSQUIDARCHIVES_bef68457-4a44-4a1b-96bc-0131469fc210_0&area=Calne

**Higham, N., 1990**
"Settlement, Land Use, and Domesday Ploughlands", *Landscape History* 12, 33-44.

**Historic England, 2008**
*Conservation Principles, Policies and Guidance.*

**Historic England, 2017**
*Good Practice Advice Note 3 - The Setting of Heritage Assets* – Second Edition. December 2017.

**Historic England, 2021**
*National Heritage List for England*

**JISC Library Hub Discover (formerly COPAC)**
https://discover.libraryhub.jisc.ac.uk/

**KnowYourPlace**
https://maps.bristol.gov.uk/kyp/?edition=wilts

**Ministry of Housing, Communities & Local Government, 2019**
*National Planning Practice Guidance (NPPG)*

**Ministry of Housing, Communities & Local Government, Dec. 2024**
*National Planning Policy Framework* (NPPF).

**National Library of Scotland: Online Maps**
https://maps.nls.uk/os/ (for historic OS maps)

**Sawyer, P., 1968**
*Anglo-Saxon Charters: An Annotated List and Bibliography*. Royal Historical Society.

**Thorn, F. and C. (eds), 1979**
*Domesday Book: Wiltshire.* Phillimore.

**VCH, 2002**
*A History of the County of Wiltshire: Volume 17, Calne.* D. A. Crowley (ed), Victoria County History.

**WA, 2023**
*Archaeological excavation on Land at The Pippin, Calne, Wiltshire*. Unpublished client report, Worcester Archaeology for Orion Heritage Limited, Report Ref. 3092.

**Zadora-Rio, E., 2003**
"The Making of Churchyards and Parish Territories in the Early-Medieval Landscape of France and England in the 7th-12th Centuries: A Reconsideration". *Medieval Archaeology* 47, 1-19.

©Avon Archaeology Limited: March 2026

**Wiltshire Record Office**

**1728**

Map of Calne (examined but not reproduced here as a figure). 1171/140(H).

**1828**

Map of Calne, 3302/42L; with schedule of properties shown on the map, 1409/7/2.

**1839**

Conveyances and deed: building lately used as a brewhouse, at the back of the house in Church Street, lately purchased by Henry Harris, grocer and bacon factor, and formerly occupied by James Perkins, deceased; and piece of land at the back of Henry Harris' premises. Deed of covenant to George Button, confectioner, of Fleet Street, London, and Thomas Rutherford, mason of Calne. 1171/154.

**1843**

Tithe map and award for Calne (no specific WRO reference).

Sources for later OS maps from the late 19th century onwards: National Library of Scotland and KnowYourPlace Wiltshire.


©Avon Archaeology Limited: March 2026

# Figure 1

## Location of the Site

The Site

Plans and maps based on the Ordnance Survey Sheets are represented by the permission of Her Majesty's Stationery Office.





Grid lines at 1km intervals

© Crown Copyright Reserved. Licence Number: AL 100005802
Based on OS Explorer 1:25,000 scale, Sheets 156—Chippenham and Bradford-on-Avon, Trowbridge and Melksham; and 157—Marlborough and Savernake Forest, Avebury and Devizes

# FIGURE 2

## Site Boundary Plan




Site boundary

0 50m

©Avon Archaeology Limited: March 2026

# FIGURE 3

Extract from map of Calne, 1828. Not to scale. Study site outlined in red, best fit to this survey. Source: WRO 3302/42L.




©Avon Archaeology Limited: March 2026

# FIGURE 4

Extract from map of Calne, 1828, showing the planned medieval settlement extension known as Eastman Street, which extends northwards immediately to the north of the study site. Not to scale. Source: WRO 3302/42L.




©Avon Archaeology Limited: March 2026

# FIGURE 5


The circular lockup at Ruabon, Wrexham, north Wales. It is possible that the circular building which was depicted on a map of Calne of 1828, is of this type.



©Avon Archaeology Limited: March 2026

# FIGURE 6


Extract from Calne tithe map, 1843. Not to scale. Study site outlined in red, best fit to this survey. Source: WRO.




©Avon Archaeology Limited: March 2026

# FIGURE 7


Extract from First Edition 25" OS map of Calne, Wiltshire Sheet 27.5, surveyed 1885, published 1886. Not to scale, study site outlined in red, best fit to this survey. Source: KnowYourPlace Wiltshire.




©Avon Archaeology Limited: March 2026

# FIGURE 8

Extract from Third Edition 25” OS map of Calne, Wiltshire Sheet 27.5, revised 1922. Not to scale, study site outlined in red, best fit to this survey. Source: KnowYourPlace Wiltshire.




©Avon Archaeology Limited: March 2026

# APPENDIX


## Wiltshire Council

## Historic Environment Record Trawl

©Avon Archaeology Limited: March 2026

Wiltshire Council

# Archaeological Events for Former Co-op, Calne Wiltshire.
# Data from the Wiltshire and Swindon Historic Environment Record



# Wiltshire and Swindon HER
# Event / Activity Full Report

**Former Co-op, Calne - Events Report**

Number of records: 21

For more details, please see the HER online at
https://www.wiltshire.gov.uk/museums-history-heritage-archaeology-historic-environment-record

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI10243 | Excavation at Land at The Pippin | Intervention |

**External Reference:**

**Dates:** 01/10/2021 - 31/12/2021, occasionally (2021)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

EVALUATION

**Event/Activity References**

| | |
|---|---|
| MAN - Museum Accession Number | DZSWS:48-2021 |
| OASIS - OASIS | fieldsec1-512779 |
| PC - Project Code/ Site Code | P6088 |

**Organisation:** Worcestershire Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Worcestershire Archaeology | Excavator |

**Location**

**Grid Reference**

Centred ST 9979 7112 (59m by 48m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

Stratigraphically the earliest features comprised a ditch and two parallel gullies which were orientated at a different angle to the later burgage plots. Radiocarbon dating has confirmed that these features were likely to be either late Saxon, or very early medieval, in origin. Following the imposition of long (medieval) burgage plots, these plots eventually became subdivided to front and rear. To the rear (ie east), there were the well-preserved remains of a lime kiln, including substantial walls and a stoke-hole. Large irregular cuts in its vicinity are interpreted as quarry pits, excavated to recover the lime-rich bed rock to burn in the kiln. The product of such a kiln would have been in demand, especially at a time when new building was happening on the High Street. After a period of possible later medieval

decline, several new stone walls divided the plots from north to south in the post-medieval period, which defined their northern and southern edges. Bonded with the walls was a substantial two-room stone-built, probably domestic/workshop, building with a fireplace at one end. The latter was associated with two stone-lined cisterns, one of which was fed from a stone lined gully running from higher ground. Thereafter, Victorian and 20th-century garden features were established, before this area finally became waste ground.

## Sources

(1) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology. (2023.033)

## Associated Monuments

MWI75861 Medieval Ditches, The Pippins (Monument MWI75861)
MWI75863 Medieval Pits, 83 The Pippin (Monument MWI75863)
MWI75864 Medieval Gullies, The Pippins (Monument MWI75864)
MWI75866 Post Medieval Walls, The Pippins (Monument MWI75866)
MWI78424 Medieval Postholes, The Pippins (Monument MWI78424)
MWI78425 Medieval Lime Kiln, The Pippins (Monument MWI78425)
MWI78426 Early Medieval Ditches, The Pippins (Monument MWI78426)
MWI78427 Early Medieval Gullies, The Pippins (Monument MWI78427)

**Event ID:** EWI10309 **Name:** Desk-Based Assessment of The Former Co-Op Store Site and Car

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI10309 | Desk-Based Assessment of The Former Co-Op Store Site and Car Park, Mill Street | Interpretation |

**External Reference:**

**Dates:** 25/04/2022 - 03/06/2022, occasionally (2022)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

DESK BASED ASSESSMENT

**Event/Activity References**

| | |
|---|---|
| OASIS - OASIS | avonarch2-506242 |
| PC - Project Code/ Site Code | 21-22.458 |

**Organisation:** Avon Archaeological Unit Ltd

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Avon Archaeological Unit Ltd | Archaeological Field Investigator |

**Location**

**Grid Reference**

Centred ST 9989 7099 (104m by 81m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The site lies in the centre of Calne, on the northern side of Mill Street, and effectively straddles the River Marden at this point as it flows through the town. Parts of the site, especially the Mill Street frontage, are likely to have been developed in the medieval period, although historic maps show that large areas of its central part, and to the north and east, remained undeveloped well into the 20th century. It is possible that some of the structures appearing on an early 19th century map may have far earlier origins. The early 19th century map recorded an enigmatic circular structure in a part of the site that does not appear to have been subsequently built on, and the same map, and a slightly later one, also recorded an elongated pond at the eastern side of the site.

**Sources**

(1) Report: Corcos, N.. 2022. The Former Co-Op Store Site and Car Park, Mill Street, Calne, Wiltshire. Avon Archaeological Unit. (2022.184)

**Associated Monuments - None recorded**

**Event ID:** EWI11191 **Name:** Excavation of Undated Bones, North East of St. Mary's Church

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI11191 | Excavation of Undated Bones, North East of St. Mary's Church | Intervention |

**External Reference:**

**Dates:** 01/01/1989 - 01/12/1989, at some time (1989)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

EXCAVATION

**Event/Activity References**

| | |
|---|---|
| NRHE - National Record of the Historic Environment to Historic Environment Records | 655129 |

**Organisation:** Wiltshire Rescue Archaeology Project

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Wiltshire Rescue Archaeology Project | Excavator |

**Location**

**Grid Reference**

| | | |
|---|---|---|
| ST 9991 7091 (point) | ST97SE | Point |

**Administrative Areas**

| | |
|---|---|
| Civil Parish | Calne, North Wiltshire, Wiltshire |

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

Excavation in 1989 by Wiltshire Rescue Archaeology Programme Unit, prior to demolition and rebuilding of a wall adjacent to a footpath, revealed redeposited ground containing an assortment of human bones.

**Sources**

(1) Serial: 1991. The Wiltshire Archaeological and Natural History Magazine - Volume 84 (master). The Wiltshire Archaeological and Natural History Magazine. Volume 84. p.143

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 655129

**Associated Monuments**

ST97SE552 Undated Bones, North East of St. Mary's Church (Find Spot ST97SE552)

**Event ID:** EWI11204 **Name:** Desk Based Assessment for Land to The Rear of 9-11 High

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI11204 | Desk Based Assessment for Land to The Rear of 9-11 High Street, Calne | Interpretation |

**External Reference:**

**Dates:** 01/01/2000 - 31/12/2000, at some time (2000)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

DESK BASED ASSESSMENT

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | B.46.6500 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1368227 |

**Organisation:** Cotswold Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Cotswold Archaeology | Carried out by |

**Location**

**Grid Reference**

| | | |
|---|---|---|
| ST 9979 7109 (point) | ST97SE | Point |

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

During the course of the assessment no sites or artefacts of archaeological significance were recorded from within the study area. However, consultation of documentary and cartographic archives identified that the study area lay in close proximity to a Bronze Age burial and just to the north of the Anglo-Saxon town of Calne. The recovery of Romano-British potsherds from a site 80 metres to the south also suggested that the study area may lie within an area of activity dating to that period.

**Sources**

(1) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1368227

**Associated Monuments - None recorded**

**Event ID:** EWI3225 **Name:** Evaluation on Land at the Rear of Church Street, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI3225 | Evaluation on Land at the Rear of Church Street, Calne | Interpretation |

**External Reference:**

**Dates:** 01/09/1996 - 30/09/1996, between (1996)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

EVALUATION

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | C.46.0703 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1128630 |
| PC - Project Code/ Site Code | 0603 |
| WSMR - Wiltshire SMR Event Number | 5311 |
| WSMR - Wiltshire SMR Event Number | 5314 |
| WSMR - Wiltshire SMR Event Number | 3322 |

**Organisation:** Cotswold Archaeological Trust

**Associated Individuals**

Beamish, Hugh Director of fieldwork

**Associated Organisations**

**Location**

**Grid Reference**

Centred ST 9982 7087 (20m by 18m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The evaluation recorded the presence of deposits of 5th to 7th century date, two medieval pits, undated cut features and 12th to 14th century deposits and cut features. Metal-working waste was recovered from the pits, which probably lay in an open area behind a building. Site described as having high archaeological potential.

**Sources**

(1) Report: Beamish, H.F.. 1996. Land at the Rear of Church Street, Calne. Cotswold Archaeological Trust. (1996.047)

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1128630

**Associated Monuments**

ST97SE400 Calne (Monument ST97SE400)

ST97SE468 Medieval Metal Working Site, Church Street (Monument ST97SE468)

**Event ID:** EWI3565 **Name:** Evaluation on Land off The Pippin, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI3565 | Evaluation on Land off The Pippin, Calne | Intervention |

**External Reference:**

**Dates:** 24/06/1997 - 25/06/1997, between (1997)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

EVALUATION
TRIAL TRENCH

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | C.46.2001 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1221826 |
| WSMR - Wiltshire SMR Event Number | 737 |
| WSMR - Wiltshire SMR Event Number | 5312 |
| WSMR - Wiltshire SMR Event Number | 3664 |

**Organisation:** Wessex Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Wessex Archaeology | Excavator |

**Location**

**Grid Reference**

| | | |
|---|---|---|
| Centred ST 9980 7106 (84m by 73m) | ST97SE | Area |

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The evaluation revealed that the site is largely composed of late 19th and 20th century deposits of made-ground and building foundations. Undated alluvium associated with the River Marden and three undated post holes were also recorded.

**Sources**

(1) Report: Boismier, W.. 1997. Land off The Pippin, Calne. Wessex Archaeology. (1997.075)
(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1221826

**Associated Monuments**

ST97SE458 Medieval Pottery, Land off the Pippen (Find Spot ST97SE458)

**Event ID:** EWI3567 **Name:** Watching Brief at Church Street, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI3567 | Watching Brief at Church Street, Calne | Intervention |

**External Reference:**

**Dates:** 10/07/1997 - 11/07/1997, throughout (1997)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

WATCHING BRIEF

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | E.46.2034 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1203071 |
| WSMR - Wiltshire SMR Event Number | 3665 |
| WSMR - Wiltshire SMR Event Number | 5315 |
| WSMR - Wiltshire SMR Event Number | 3666 |

**Organisation:** AC Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| AC Archaeology | Excavator |

**Location**

**Grid Reference**

Centred ST 9986 7092 (1m by 24m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The partial remains of a single burial were exposed and recorded, and an earlier graveyard boundary noted to the north of the burial.

**Sources**

(1) Report: AC Archaeology. 1997. An Archaeological Watching Brief at Church Street, Calne. AC Archaeology. (1997.036)

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1203071

**Associated Monuments**

ST97SE551 Wall Footings, Castle House (Building ST97SE551)

ST97SE553 Undated Burial, Church Street (Monument ST97SE553)

**Event ID:** EWI4825 **Name:** Watching Brief at 29 Church Street, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI4825 | Watching Brief at 29 Church Street, Calne | Intervention |

**External Reference:**

**Dates:** 09/09/1999 - 09/09/1999, throughout (1999)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

WATCHING BRIEF

**Event/Activity References**

WSMR - Wiltshire SMR Event Number 4925

**Organisation:** Foundations Archaeology

**Associated Individuals - None recorded**

**Associated Organisations - None recorded**

**Location**

**Grid Reference**

Centred ST 9982 7086 (11m by 8m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

An intact post medieval limestone wall was identified and remnants of a second section of walling running on an east/west alignment were also identified.

**Sources**

Report: Foundations Archaeology. 2000. 29 Church Street, Calne. Foundations Archaeology. (2000.003)

**Associated Monuments - None recorded**

**Event ID:** EWI5151 **Name:** Avebury World Heritage Site Mapping Project (Aerial Survey)

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI5151 | Avebury World Heritage Site Mapping Project (Aerial Survey) | Extensive Survey |

**External Reference:**

**Dates:** 31/12/1999, pre (1999)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

AERIAL PHOTOGRAPH INTERPRETATION

**Event/Activity References**

WSMR - Wiltshire SMR Event Number 5251

**Organisation:** English Heritage

**Associated Individuals**

**Associated Organisations**

Royal Commission on the Historical Monuments of England — Surveyor

**Location**

**Grid Reference**

Centred SU 0752 6747 (15048m by 14915m) SU06NE Line

**Administrative Areas**

Civil Parish Avebury, Kennet, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The Avebury World Heritage Site Mapping Project was part of the National Mapping Programme. Resulting from the Avebury survey there were a total of 1492 sites recorded for the survey area with 380 new sites discovered from aerial photographs. The majority of the new sites were represented by five main types of site, mostly Medieval in date. These included Ridge and Furrow, Lynchets, Enclosures, Water Meadows and Field Systems.

**Sources**

(1) Report: Small, F.. 1999. Avebury World Heritage Site Mapping Project, Wiltshire. English Heritage. (1999.117)

**Associated Monuments**

SU07SW527 RAF Compton Bassett (Monument SU07SW527)
SU16NW104 Avebury Stone Circle and Henge (Monument SU16NW104)
SU16NW331 Romano-British Finds, Snail Creep Field (Find Spot SU16NW331)
SU16NW675 Enclosure, North-West of North Farm (Monument SU16NW675)
SU16NW687 Field System, Overton Down (Monument SU16NW687)
SU16SW618 Possible Round Barrow, North West of New Town (Monument SU16SW618)

SU17SW451 Medieval and Post Medieval Enclosures, South of Wroughton Copse (Monument SU17SW451)

**Event ID:** EWI5155 **Name:** Desk Top Study of Land off The Pippin, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI5155 | Desk Top Study of Land off The Pippin, Calne | Extensive Survey |

**External Reference:**

**Dates:** 12/06/1997, pre (1997)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

DESK BASED ASSESSMENT

**Event/Activity References**

WSMR - Wiltshire SMR Event Number 5255

**Organisation:** Alison Borthwick & Associates

**Associated Individuals**

Borthwick, Alison - Unassigned Carried out by

**Associated Organisations**

**Location**

**Grid Reference**

Centred ST 9980 7106 (84m by 73m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

There is the potential for medieval remains, particularly in the form of property boundaries, pits and minor structures, to survive within land to the rear of the High Street. It is also possible that a marked rise in ground levels along the northern edge of the car park area may represent the remnants of an earlier, perhaps medieval, property boundary. Much of the remainder of the area will have undergone considerable development or re-development from the mid-19th century onwards as Harris's Bacon Industry began to flourish.

**Sources**

Report: Borthwick, A.. 1997. Proposed Car Park Development by J. Sainsbury plc, on Land off The Pippin, Calne, Wiltshire. Alison Borthwick & Associates. (1997.093)

**Associated Monuments - None recorded**

**Event ID:** EWI6733 **Name:** Watching Brief at 9A Wood Street, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6733 | Watching Brief at 9A Wood Street, Calne | Intervention |

**External Reference:**

**Dates:** 01/03/2006 - 30/11/2006, between (2006)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

WATCHING BRIEF

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | E.46.3401 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1463750 |
| OASIS - OASIS | oxfordar1-36400 |
| PC - Project Code/ Site Code | CALWS 06 |
| PC - Project Code/ Site Code | 3179 |
| WSMR - Wiltshire SMR Event Number | 6540 |
| WSMR - Wiltshire SMR Event Number | 6854 |

**Organisation:** Oxford Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Oxford Archaeology | Carried out by |

**Location**

**Grid Reference**

Centred ST 9976 7122 (35m by 12m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The watching brief revealed a number of graves and charnel pits of the Quakers burial ground dating to the 17th - 19th centuries.

**Sources**

(1) Report: Mumford, J.. 2006. 9A Wood Street, Calne, Wiltshire. Oxford Archaeology. (2006.073)

(2) Serial: 2008. The Wiltshire Archaeological and Natural History Magazine - Volume 101 (master). The Wiltshire Archaeological and Natural History Magazine. Volume 101. pp.275-276

(3) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1463750

**Associated Monuments**

ST97SE527 Probable 17th Century Meeting House, Wood Street (Monument ST97SE527)

**Event ID:** EWI6972 **Name:** Watching Brief at Phelps Parade, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6972 | Watching Brief at Phelps Parade, Calne | Intervention |

**External Reference:**

**Dates:** 28/08/2008 - 08/10/2008, occasionally (2008)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

WATCHING BRIEF

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | E.46.3527/2008 |
| MAN - Museum Accession Number | DZSWS: 2008.44 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1490335 |
| OASIS - OASIS | cotswold2-52320 |
| PC - Project Code/ Site Code | PPC 08 |
| PC - Project Code/ Site Code | 2689 |

**Organisation:** Cotswold Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Cotswold Archaeological Trust | Carried out by |

**Location**

**Grid Reference**

Centred ST 9981 7120 (31m by 60m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

A well was encountered during the monitoring of the groundworks.

**Sources**

(1) Report: Reynish, S.. 2008. Phelps Parade, Calne, Wiltshire. Cotswold Archaeology. (2008.091)

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1490335

**Associated Monuments**

MWI31409 Probable Post Medieval Well, The Pippin, Calne (Monument MWI31409)

**Event ID:** EWI6973 **Name:** Evaluation at Zion Chapel Burial Ground, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6973 | Evaluation at Zion Chapel Burial Ground, Calne | Intervention |

**External Reference:**

**Dates:** 01/11/2008 - 30/11/2008, between (2008)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

TEST PIT

**Event/Activity References**

| | |
|---|---|
| PC - Project Code/ Site Code | CAZION08 |
| PC - Project Code/ Site Code | 4266 |

**Organisation:** Oxford Archaeology

**Associated Individuals - None recorded**

**Associated Organisations - None recorded**

**Location**

**Grid Reference**

Centred ST 9979 7116 (26m by 15m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The evaluation revealed a number of post medieval features, including six earth cut graves, two brick shaft graves and two stone lined shaft graves. A dry stone culvert, part of the original north churchyard boundary wall and three possible refuse pits were also revealed.

**Sources**

Report: Webb, H.. 2008. Zion Baptist Chapel, Calne, Wiltshire. Oxford Archaeology. (2008.112)

**Associated Monuments**

MWI74622 Graves, Zion Baptist Chapel (Monument MWI74622)

MWI74623 Linear Features, Zion Baptist Chapel (Monument MWI74623)

**Event ID:** EWI6974 **Name:** Geophysical Survey at Zion Chapel Graveyard, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6974 | Geophysical Survey at Zion Chapel Graveyard, Calne | Survey |

**External Reference:**

**Dates:** 29/12/2008 - 29/12/2008, throughout (2008)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

GROUND PENETRATING RADAR SURVEY

**Event/Activity References - None recorded**

**Organisation:** Archaeological Surveys Ltd

**Associated Individuals - None recorded**

**Associated Organisations - None recorded**

**Location**

**Grid Reference**

Centred ST 9979 7116 (20m by 13m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The results of a ground penetrating radar survey indicated the presence of nine graves that may be constructed as shafts.

**Sources**

Report: Sabin, D. + Donaldson, K.. 2009. Zion Baptist Chapel, Calne. Archaeological Surveys Ltd. (2009.004)

**Associated Monuments**

MWI74622 Graves, Zion Baptist Chapel (Monument MWI74622)

MWI74623 Linear Features, Zion Baptist Chapel (Monument MWI74623)

**Event ID:** EWI6975 **Name:** Watching Brief at Zion Baptist Chapel, Phelps Parade, Calne,

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6975 | Watching Brief at Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire. | Intervention |

**External Reference:**

**Dates:** 13/07/2009 - 10/09/2009, between (2009)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

WATCHING BRIEF

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | E.46.3884 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1578612 |
| OASIS - OASIS | cotswold2-101370 |
| PC - Project Code/ Site Code | ZBP 09 |
| PC - Project Code/ Site Code | 2888 |

**Organisation:** Cotswold Archaeology

**Associated Individuals**

**Associated Organisations**

Cotswold Archaeology Carried out by

**Location**

**Grid Reference**

Centred ST 9979 7116 (26m by 15m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

During the watching brief the locations of 21 earth cut graves and 6 burial shafts were identified. All of the burials were laid out on an east/west alignment and no in situ headstones were present. In addition to the burials, walls and a pathway associated with the chapel were identified. Although no artefactual material was recovered, the bricks and coffins exposed within the shaft graves are consistent with the 19th century date of the graveyard.

**Sources**

(1) Report: Hart, J.. 2009. Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire. Cotswold Archaeology. (2009.078)

(2) Serial: 2011. The Wiltshire Archaeological and Natural History Magazine - Volume 104 (master). The Wiltshire Archaeological and Natural History Magazine. Volume 104.

(3) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1578612

**Event ID:** EWI6975 **Name:** Watching Brief at Zion Baptist Chapel, Phelps Parade, Calne,

**Associated Monuments**

MWI74622 Graves, Zion Baptist Chapel (Monument MWI74622)
MWI74623 Linear Features, Zion Baptist Chapel (Monument MWI74623)

**Event ID:** EWI6976 **Name:** Watching Brief on Test Pits at St Mary Parish Church, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6976 | Watching Brief on Test Pits at St Mary Parish Church, Calne | Intervention |

**External Reference:**

**Dates:** 01/09/2009 - 30/11/2009, at some time (2009)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

GEOTECHNICAL TEST PIT
WATCHING BRIEF

**Event/Activity References - None recorded**

**Organisation:** Wiltshire Archaeological and Natural History Society, Archaeology Field Group

**Associated Individuals - None recorded**

**Associated Organisations - None recorded**

**Location**

**Grid Reference**

Centred ST 9991 7091 (13m by 12m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

One test pit in the graveyard cut mostly through soil that had previously been disturbed, and which consequently contained many fragments of human bone. Auguring of a test pit

**Sources**

Report: Holley, R.J.. 2009. St. Mary Parish Church, Calne, Wiltshire. Archaeological Watching Brief - Test Pits. Wiltshire Archaeological and Natural History Society. (2009.112)

**Associated Monuments - None recorded**

**Event ID:** EWI6977 **Name:** Watching Brief at St Mary Parish Church, Calne

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI6977 | Watching Brief at St Mary Parish Church, Calne | Intervention |

**External Reference:**

**Dates:** 13/10/2009 - 21/10/2009, between (2009)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

WATCHING BRIEF

**Event/Activity References - None recorded**

**Organisation:** Wiltshire Archaeological and Natural History Society, Archaeology Field Group

**Associated Individuals - None recorded**

**Associated Organisations - None recorded**

**Location**

**Grid Reference**

Centred ST 9991 7089 (19m by 37m) ST97SE Dispersed

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

Very little early pottery was recovered, but as the pits were only excavated to a maximum depth of 0.5 metres, the possibility of finding any structures or artefacts from the Saxon period was unlikely.

**Sources**

Report: Holley, R., Smith, W. + Baumber, J.. 2009. St. Mary Parish Church, Calne, Wiltshire. Archaeological Watching Brief. Wiltshire Archaeological and Natural History Society. (2009.113)

**Associated Monuments - None recorded**

**Event ID:** EWI8741 **Name:** Research Report for The Church and Chapel Interiors of John

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI8741 | Research Report for The Church and Chapel Interiors of John Loughborough Pearson, St Mary's Church, Calne | Interpretation |

**External Reference:**

**Dates:** 01/10/2014 - 28/02/2015, between (2014-2015)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

ARCHITECTURAL SURVEY

**Event/Activity References - None recorded**

**Organisation:** Historic England

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Historic England | Carried out by |

**Location**

**Grid Reference**

Centred ST 9990 7090 (41m by 29m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

A priority research topic under the National Heritage Protection Plan in response to the rate of change to historic church interiors. The NHPP identified a particular need for more information on the rarity and quality of schemes or part-schemes designed by major architects. The research on Pearson serves to demonstrate some of the major trends identified through an examination of selected examples. The report contains an assessment of the significance of Pearson's church interiors and also a series of appendices containing case studies, a list of all Pearson's work in England, a gazetteer and a summary of a church questionnaire.

**Sources**

(1) Report: Howard, C. + Taylor, S.. 2016. The Church and Chapel Interiors of John Loughborough Pearson: A Selective Assessment of Significance. Historic England. (2016.155)

**Associated Monuments - None recorded**

**Event ID:** EWI8852 **Name:** Evaluation at 83, The Pippin

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI8852 | Evaluation at 83, The Pippin | Intervention |

**External Reference:**

**Dates:** 15/03/2016 - 18/03/2016, between (2016)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

TRIAL TRENCH

**Event/Activity References**

| | |
|---|---|
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1614585 |
| OASIS - OASIS | fieldsec1-246201 |

**Organisation:** Worcestershire Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Worcestershire Archaeology | Excavator |

**Location**

**Grid Reference**

Centred ST 9979 7111 (73m by 63m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

The evaluation revealed a large ditch of unknown date, but sealed by 13th century garden soils. The presence of free-threshing wheat from within the ditch suggested a possible Saxon date. A possible metalled surface of medieval date was identified on the eastern edge of the site, whilst two small ditches were excavated in the southern half. These too were beneath medieval garden soils. Within the burgage plot on the western side of the site was a sequence of complex stratified medieval and post-medieval deposits associated with backyard activity. This included a number of medieval pits cutting into the natural strata, and robbed out walls with associated demolition deposits. A post-medieval stone boundary wall defined the plot, and was later faced with brick. A number of brick structures were built during the 18th-19th centuries, including one with evidence for a hearth. These had gone out of use by the early 20th century, with the site becoming the mix of hard standing and grass that exists today.

**Sources**

(1) Report: Lovett, P.. 2016. 83, The Pippin, Calne. Worcestershire Archaeology. (2016.166)

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1614585

**Associated Monuments**

MWI75861 Medieval Ditches, The Pippins (Monument MWI75861)

MWI75863 Medieval Pits, 83 The Pippin (Monument MWI75863)
MWI75864 Medieval Gullies, The Pippins (Monument MWI75864)
MWI75865 Medieval Pits, The Pippins (Monument MWI75865)

**Event ID:** EWI9382 **Name:** Strip, Map and Sample Excavation at The Old Vicarage, Anchor

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI9382 | Strip, Map and Sample Excavation at The Old Vicarage, Anchor Road | Intervention |

**External Reference:**

**Dates:** 01/04/2019 - 05/04/2019, throughout (2019)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

EXCAVATION

**Event/Activity References**

| | |
|---|---|
| OASIS - OASIS | wessexar1-349785 |
| PC - Project Code/ Site Code | 218320 |

**Organisation:** Wessex Archaeology

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Wessex Archaeology | Excavator |

**Location**

**Grid Reference**

Centred SU 0002 7100 (13m by 6m) SU07SW Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

An archaeological investigation was undertaken to monitor groundworks for the construction of a proposed new swimming pool located within the north-east corner of the garden of The Old Vicarage. The monitored area measured c.75 meters square. The investigation confirmed the presence of two substantial north to south orientated ditches, which based on artefactual evidence could have dated to the medieval period, although were still extant and being infilled in the post medieval period during landscaping within the grounds of the vicarage. The ditches may have been part of a boundary demarcating the site of a medieval monastic lodge, which was thought to have been located within the grounds of the current vicarage. Although no further evidence of in situ human burials indicating the extension of a medieval cemetery were identified during the investigation, as had been recorded in 2002 during construction of a garage within the vicarage grounds to the west, a small amount of disturbed human bone along with animal bone was recovered from the fill of one of the recorded ditches. These remains were likely to have been displaced from the possible cemetery in the west possibly during later landscaping works within the grounds of the vicarage. Although the ditches are possibly boundaries demarcating the eastern extent of the medieval monastic lodge, no evidence of medieval buildings or building remains predating the current 18th and 19th century vicarage were encountered. Although the overriding evidence would point to the ditches being medieval in date, the presence of a single sherd of post medieval pottery within the fill of one of the ditches could have indicated that these ditches could be later events associated with landscaping of the vicarage gardens,

and may also explain the presence of disturbed human remains where material from the western part of the site have been displaced to the eastern side of the garden.

Sources

(1) Report: Froud, S.. 2019. The Old Vicarage, Anchor Road, Calne. Wessex Archaeology. (2019.038)

**Associated Monuments - None recorded**

**Event ID:** EWI9423 **Name:** Excavations at The Old Vicarage, Mill Street/Anchor Road

| Event ID | Event Name | Event Type |
|---|---|---|
| EWI9423 | Excavations at The Old Vicarage, Mill Street/Anchor Road | Intervention |

**External Reference:**

**Dates:** 12/02/2002 - 12/02/2002, throughout (2002)

**Project Details:**

**Work Status - Not recorded**

**Event Types**

RESCUE EXCAVATION

**Event/Activity References**

| | |
|---|---|
| AIP - Archaeological Investigations Project | E.46.F016 |
| NRHE - National Record of the Historic Environment to Historic Environment Records | 1443719 |

**Organisation:** Wiltshire County Council

**Associated Individuals**

**Associated Organisations**

| | |
|---|---|
| Wiltshire Council Archaeology Service | Recorder |

**Location**

**Grid Reference**

Centred ST 9998 7098 (18m by 17m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address - None recorded**

**Activity Objective, Description and Sources**

**Activity Objective - None recorded**

**Description**

Groundworks to construct a new double garage on site encountered a previously unsuspected burial ground. Six graves were noted within a small area, and it was felt highly likely that further inhumations lay beyond the excavated area. Circumstantial evidence suggested that these burials were of medieval date.

**Sources**

(1) Unassigned: McMahon, Phillip. 2002. Note on Human Burials at the Old Vicarage, Mill Street/Anchor Road, Calne. (2002.016)


(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1443719

**Associated Monuments**

ST97SE554 Probable Medieval Burial Ground, The Old Vicarage, Mill St/Anchor Rd (Monument ST97SE554)

Wiltshire Council

# Listed Buildings for Former Co-op, Calne Wiltshire.
# Data from the Wiltshire and Swindon Historic Environment Record



# Wiltshire and Swindon HER Designation Full Report

**Former Co-op, Calne - Listed Buildings Report**

Number of records: 102

**DesigUID:** DWI5894 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271379 | 1271379 | 755-1, 5, 4 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE ST9970 CASTLE STREET
755-1/5/4 (South side)
08/07/76 No.3
GV II
House. Possibly a C17 basement, rebuilt early C19. Limestone ashlar plinth, painted squared limestone, brick left-hand gable stack and slate roof. Double-depth plan. Coped gables, a round-arched right-hand doorway and 6-panel door, with steps up; shallow canted bay and plinth, with a C20 window with glazing bars; first-floor 8/8-pane sashes. INTERIOR: details include a right-hand axial stair with stick balusters and ramped rail, a C17 axial ceiling beam in the basement with wide stopped chamfers, and re-used timber lintel with mortice holes.
Listing NGR: ST9968470964

**Curatorial Notes**

Type and date: C17 HOUSE. Date: from 1600 to 1699
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: STEPS.
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99680 70966 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

3 Castle Street, Calne, Wiltshire, SN11 0DX

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

**DesigUID:** DWI5894 **Name:**

MWI36354 Building: 3, CASTLE STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455085

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5895 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246405 | 1246405 | 755-1, 4, 5 |

**Name:**
**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE ST9971 CASTLE STREET
755-1/4/5 (West side)
19/05/50 No.4
GV II
House. Mid C18, C19 roof. Limestone rubble with ashlar dressings, brick gable stacks and slate roof. Single-depth central entry plan with rear wing. 2 storeys, cellar and attic; 5-window range. A symmetrical front has a plinth with moulded band, plain plat band, eaves cornice and quoins. Doorway with steep pediment linked to plat band, 3-pane overlight and panelled door; architraves to C19 6/6-pane sashes, and two C19 gabled dormers with 2/2-pane sashes. Right-hand stack set forward of the ridge. Former stable range to rear has 3-light casement window with leaded lights.INTERIOR: details include a central through-passage, to a rear, right-hand C19 dogleg stair with stick balusters ramped rail; 4-bay C19 collar truss roof with tenon purlins half-glazed doors with stained glass, and front room with bolection-moulded fire surround.
Listing NGR: ST9966571049

**Curatorial Notes**

Type and date: Mid C18 HOUSE. Date: from 1733 to 1766
Type and date: C19 HOUSE. Date: from 1800 to 1899
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99669 71042 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

**DesigUID:** DWI5895 **Name:**

4 Castle Street, Calne, Wiltshire, SN11 0DU

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36355 Building: 4, CASTLE STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455086

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5896 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246406 | 1246406 | 755-1, 5, 6 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE ST9970 CASTLE STREET
755-1/5/6 (South side)
08/07/76 No.5
GV II
House. Early or mid C18, re-roofed mid C19. Rendered limestone rubble, ashlar right-hand gable stack and a slate roof. Single-depth plan. 2 storeys; 2-window range. Stone-coped right-hand gable; left-hand doorway and C20 door; timber lintel to a 3-light C20 casement and smaller one to the right; 2- and 3-light first-floor stone-mullioned windows; 2 late C19 gabled dormers with decorative barge-boards and 2x4-pane casements. INTERIOR not inspected.
Listing NGR: ST9967670964

**Curatorial Notes**

Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Early or mid C18 HOUSE. Date: from 1700 to 1766
Main material: render
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**DesigUID:** DWI5896 **Name:**

**Grid Reference:** ST 99673 70964 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**
Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**
5 Castle Street, Calne, Wiltshire, SN11 0DX

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**
MWI36356 Building: 5, CASTLE STREET

**Associated Consultations - None**

**Additional Information**
**LBSUID:** 455087

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5897 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246407 | 1246407 | 755-1, 4, 7 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**
CALNE ST9971 CASTLE STREET
755-1/4/7 (West side)
08/07/76 Nos.6 AND 8
GV II
Pair of attached houses. Early C19, No.8 rebuilt internally and to rear. Painted squared, coursed limestone rubble, with pantile roof and brick stacks. Each of 2 storeys and attic; 2-window range. Plinth, round-arched doorways with fanlights, No.6 set centrally beneath a round-arched recess; 6/6-pane sashes. No.6 has 2 gabled dormers with C20 casements. No.8 rebuilt at rear. INTERIOR not inspected.
Listing NGR: ST9966871033

**Curatorial Notes**
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: limestone
Main material: rubble
Covering material: pantile

**DesigUID:** DWI5897 **Name:**

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99665 71031 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

6 Castle Street, Calne, Wiltshire, SN11 0DU

6 Castle Street, Calne, Wiltshire, SN11 0DU

8 Castle Street, Calne, Wiltshire, SN11 0DU

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI32981 Building: 6 AND 8, CASTLE STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455088

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5900 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246410 | 1246410 | 755-1, 4, 10 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE ST9971 CASTLE STREET
755-1/4/10 (West side)
08/07/76 No.12
GV II

Pair of attached houses, now one. Early C18, altered early C19. Rendered limestone rubble, gable stack and pantile roof in 2 sections, higher to the right. Single-depth plan with C19 rear wing making L-plan. Formerly 2 houses entered from the through-passage. 2 storeys, attic and cellar; 3-window range. A left-of-centre doorway, with early C19 8/8-pane ground-floor sashes, first-floor left-hand casement, 2 late C19 right-hand 2/2-pane horned sashes, and a left-hand gabled dormer; two C18 stone-mullioned cellar openings. Rear elevation with a late C19 projecting brick S wing, 8/8-pane

**DesigUID:** DWI5900 **Name:**

weightless sash, and a cellar ovolo-moulded stone-mullioned window. INTERIOR: details include a through-passage, flagged cellar with stone steps down; C19 left-hand rear stair.
Listing NGR: ST9966471018

**Curatorial Notes**

Type and date: Early C18 CROSS PASSAGE HOUSE. Date: from 1700 to 1732
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C19 HOUSE. Date: from 1867 to 1899
Main material: render
Main material: limestone
Main material: rubble
Covering material: pantile
Main material: brick

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99662 71019 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

12 Castle Street, Calne, Wiltshire, SN11 0DU

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36359 Building: 12, CASTLE STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455091

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5901 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246411 | 1246411 | 755-1, 4, 12 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

**DesigUID:** DWI5901 **Name:**

CALNE ST9971 CASTLE STREET
755-1/4/12 (West side)
08/07/76 No.14
GV II
House. c1705, largely rebuilt in early C19. Rendered rubble, limestone dressings, brick left-hand gable stack and pantile roof. Double-depth plan. 3 storeys and cellar; 2-window range.A symmetrical front has a round-arched, recessed doorway and 6-panel door, pilaster strips and a plinth, low cellar openings, and 8/8-pane ground and first-floor sashes, 4/8-panes on the second floor. INTERIOR not inspected. Dated in deeds.
Listing NGR: ST9966671010

**Curatorial Notes**

Type and date: c1705 HOUSE. Date: from 1685 to 1725
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: render
Main material: rubble
Main material: limestone
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99663 71012 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

14 Castle Street, Calne, Wiltshire, SN11 0DU

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36360 Building: 14, CASTLE STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455092

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5902 **Type:** Listed Building **Status:** Active
**NHLE number** **NHLE number** **Volume/Map/Item**

**DesigUID:** DWI5902 **Name:**

1246412 1246412 755-1, 4, 13

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE ST9971 CASTLE STREET
755-1/4/13 (West side)
08/07/76 No.16
GV II
House. Early C19 with earlier origins. Rendered limestone rubble, ashlar plinth and dressings, brick right-hand gable stack and double Roman tile roof. Single-depth plan. 2 storeys, cellar and attic; 3-window range to street. Blocked left-hand doorway, formerly with round-arched head, stone mullion cellar window, 3 first-floor windows, the middle one blocked, and 2 ground-floor windows; all with 8/8-pane sashes. 1-window gable has an attic casement, similar sash and 3-light canted bay. C18 and early C19 former outbuilding to rear, of similar materials and now incorporated into house. INTERIOR not inspected. Possibly rebuilt over an early C18 cellar; see No.12 (qv).
Listing NGR: ST9966171003

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: C18 and early C19 OUTBUILDING. Date: from 1700 to 1832
Main material: render
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: roman tile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99663 71003 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

16 Castle Street, Calne, Wiltshire, SN11 0DU

**Designation History**

Assignment
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36361 Building: 16, CASTLE STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455093

**DesigUID:** DWI5902 **Name:**

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5909 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246415 | 1246415 | 755-1, 5, 22 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE ST9970 CHURCH STREET
755-1/5/22 (West side)
08/07/76 No.13
GV II
Oddfellows Hall, now shop. c1840, altered late C20. Limestone ashlar with moulded stacks and hipped slate roof. Single-depth plan. 2 storeys; 4-window range. 1-window right-hand bay at slight angle with 6-panel door with overlight set in moulded architrave with bracketed cornice; wide late C20 shop front; first-floor cill band, and 6/6-pane sashes set in moulded architraves. INTERIOR completely altered late C20. Included for group value.
Listing NGR: ST9985270954

**Curatorial Notes**

Type and date: c1840 ODDFELLOWS HALL. Date: from 1820 to 1860
Type and date: Now SHOP.
Type and date: Late C20 SHOP. Date: from 1967 to 1999
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99849 70953 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36402 Building: 13, CHURCH STREET

**DesigUID:** DWI5909 **Name:**

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455100

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5911 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271362 | 1271362 | 755-1, 5, 24 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/24 (West side)
08/07/76 No.19 (Formerly Listed as: CHURCH STREET (West side) Nos.19-29 (Odd) incl 27A & 27B)
GV II
Formerly known as: Butcher's Arms Public House CHURCH STREET. House, public house, now shop. C17, altered early C19. Dressed squared, coursed limestone, rendered ground floor, brick gable stacks and slate roof. Single-depth plan with a rear left-hand wing: originally a C17 range with early C19 range built across the front. 2 storeys and attic; 2-window range. Double fronted with a plain right-hand doorway, central wide door with bracketed timber pediment above a half-glazed early C19 door. Flanking mid C20 shallow bowed oriel shop windows with glazing bars, first-floor 2/2-pane late C19 horned sashes, and 2 gabled dormers with 6/6-pane casements. INTERIOR altered; details include recessed wall cupboards in the C17 rear wing, C19 stair and roof.
Listing NGR: ST9983970924

**Curatorial Notes**

Type and date: C17 HOUSE. Date: from 1600 to 1699
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: PUBLIC HOUSE.
Type and date: Now SHOP.
Type and date: Mid C20 SHOP. Date: from 1933 to 1966
Main material: limestone
Main material: render
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** Centred ST 99849 70927 (1m by 0m)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

**DesigUID:** DWI5911 **Name:**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

19 Church Street, Calne, Wiltshire, SN11 0HY

**Listed Building Addresses**

Alternative

BUTCHER'S ARMS

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36404 Building: 19, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455149

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5912 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246433 | 1246433 | 755-1, 5, 25 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/25 (West side)
08/07/76 Nos.21 AND 23
(Formerly Listed as: CHURCH STREET (West side) Nos.19-29 (Odd) incl 27A & 27B)
GV II

House, now shop and flats. c1500, altered mid C19, restored late C20. Squared, dressed limestone, brick gable and rear lateral stacks and a pantile roof. Single-depth plan. 2 storeys and attic; 3-window range. Double-fronted with pilaster strips, plat band and a frieze; C20 door, restored early C19 shop windows each side with panelled jambs, fascia and cornice, each with 3 plate-glass panes, 6/6-pane first-floor sashes, and a central gabled casement dormer. INTERIOR: details include a 4-bay roof with threaded ridge, wind braces between 2 sets of chamfered, stopped purlins, and joists laid flush with the tops or the ties. Ground floor has moulded C16 axial and lateral beams with removed corner bosses. (Wiltshire Buildings Record: Trowbridge: 1990-).
Listing NGR: ST9985070915

**DesigUID:** DWI5912 **Name:**

**Curatorial Notes**

Type and date: c1500 HOUSE. Date: from 1480 to 1520
Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Type and date: Early C19 SHOP. Date: from 1800 to 1832
Type and date: Now FLATS.
Main material: limestone
Main material: brick
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99850 70917 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

21-23 Church Street, Calne, Wiltshire, SN11 0HY
21-23 Church Street, Calne, Wiltshire, SN11 0HY
21-23 Church Street, Calne, Wiltshire, SN11 0HY

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36405 Building: 21 AND 23, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455150

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5913 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271363 | 1271363 | 755-1, 5, 26 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

**DesigUID:** DWI5913 **Name:**

CALNE
ST9970 CHURCH STREET
755-1/5/26 (West side)
08/07/76 No.25
(Formerly Listed as: CHURCH STREET (West side) Nos.19-29 (Odd) incl 27A & 27B)
GV II
House, now shop and flat. Early C19, restored late C20. Rendered limestone ashlar with brick gable stack and slate roof. Single-depth plan. Single storey; 1-window range. A right-hand through carriage arch, 3-pane late C20 plate-glass shop front, and first-floor 8/8-pane sash in exposed box; shop doorway in the archway. Coped left-hand party wall. INTERIOR not inspected.
Listing NGR: ST9983770906

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C20 HOUSE. Date: from 1867 to 1899
Type and date: Late C20 SHOP. Date: from 1967 to 1999
Type and date: Now FLATS.
Main material: render
Main material: limestone
Main material: ashlar
Main material: brick
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99847 70905 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

25 Church Street, Calne, Wiltshire, SN11 0HY

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36406 Building: 25, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455151

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5913 **Name:**

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5914 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246434 | 1246434 | 755-1, 5, 27 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/27 (East side)
08/07/76 No.26
GV II
House, now shop. Mid/late C17, refronted and altered mid C19. Rendered limestone rubble with a slate hipped roof and brick stack. L-plan on a corner site with a left-hand rear wing. 2 storeys; 2-window range. Mid/late C19 wide double-fronted shop front with a fascia and cornice, thin mullions and plate glass; 2 first-floor 2/2-pane sashes. Left-hand return has a central recessed door, with 3-light casement to the left, mid C19 casement above, and late C19 right-hand casement with glazing bars. INTERIOR: details include chamfered lateral beams; rear room has widely-chamfered axial beam with roll stops; right-hand dogleg winder stair by the side door, to an axial first-floor passage. Roof not seen.
Listing NGR: ST9986970968

**Curatorial Notes**

Type and date: Mid/late C17 HOUSE. Date: from 1633 to 1699
Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Mid/late C19 SHOP. Date: from 1833 to 1899
Main material: render
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99863 70966 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

26 Church Street, Calne, Wiltshire, SN11 0HU

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**DesigUID:** DWI5914 **Name:**

**Associated Monuments**

MWI36407 Building: 26, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455152

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5915 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246435 | 1246435 | 755-1, 5, 28 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/28 (West side)
08/07/76 No.27
(Formerly Listed as: CHURCH STREET (West side) Nos.19-29 (Odd) incl 27A & 27B)
GV II
House. Early C19. Limestone ashlar, brick gable stacks and a slate roof. Double-depth plan including rear wing. 2 storeys; 2-window range. A raised surround to a right-hand segmental-arched carriage way and boarded door, with a right-hand pilaster strip; 6/6-pane sashes. INTERIOR not inspected.
Listing NGR: ST9984870899

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99848 70896 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Flat 1 27 Church Street, Calne, Wiltshire, SN11 0HY

**Designation History**

**Assignment**

08/07/1976

**DesigUID:** DWI5915 **Name:**

**Sources - None recorded**

**Associated Monuments**

MWI36408 Building: 27, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455153

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5916 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271364 | 1271364 | 755-1, 5, 29 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/29 (West side)
08/07/76 Nos.27A AND 27B
(Formerly Listed as: CHURCH STREET (West side) Nos.19-29 (Odd) incl 27A & 27B)
GV II
House and shops. Dated 1842. Limestone ashlar, with coursed rubble gables, brick gable stacks and slate roof. Double-depth plan. 3 storeys; 3-window range. Near symmetrical front divided by first- and second-floor cill bands, and eaves cornice, with coped gables. Central round-arched doorway to fanlight and 6-panel door, flanked by symmetrical shop fronts with recessed doorways, ashlar plinths, plate-glass windows and bracketed cornice and blind box. Central round-arched windows, all with horned plate-glass sashes with margin lights. Rear datestone. INTERIOR not inspected.
Listing NGR: ST9985270887

**Curatorial Notes**

Type and date: 1842 HOUSE. Date: 1842
Type and date: 1842 SHOP. Date: 1842
Type and date: 1842 DATE STONE. Date: 1842
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99852 70887 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**DesigUID:** DWI5916 **Name:**

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

27b Church Street, Calne, Wiltshire, SN11 0HY

27a Church Street, Calne, Wiltshire, SN11 0HY

27a Church Street, Calne, Wiltshire, SN11 0HY

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36409 Building: 27A AND 27B, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455154

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5917 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246436 | 1246436 | 755-1, 5, 30 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/30 (East side)
08/07/76 No.28
(Formerly Listed as: CHURCH STREET (East side) Nos.28 AND 30)
GV II
House, now office. Late C18/early C19. Limestone ashlar, ashlar gable stacks and slate roof. Double-depth plan. 2 storeys; 3-window range. Double-fronted with cornice and parapet, coped gables; 6-panel door and overlight, blocked first-floor window, and 6/6-pane sashes. Rear has 2 parallel gabled ranges, with a blocked first-floor window. INTERIOR altered.
Listing NGR: ST9987670962

**Curatorial Notes**

Type and date: Late C18/early C19 HOUSE. Date: from 1767 to 1832
Main material: limestone

**DesigUID:** DWI5917 **Name:**

Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99868 70960 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

28 Church Street, Calne, Wiltshire, SN11 0HX

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36410 Building: 28, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455155

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5918 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246437 | 1246437 | 755-1, 5, 31 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/31 (West side)
08/07/76 No.29
(Formerly Listed as: CHURCH STREET (West side) Nos.19-29 (Odd) incl 27A & 27B)
GV II
House and shop. Early C19, altered late C20. Coursed, squared limestone rubble, brick ridge and party wall stacks and pantile roof. Double-depth plan. 2 storeys; 4-window range. Right-hand 2-window house has an ashlar surround to a right-hand panelled door; long left-hand range has a left-hand carriage entrance with a timber cornice, and a double shop front with wide central half-glazed door

**DesigUID:** DWI5918 **Name:**

and plate-glass windows, beneath a fascia and cornice, rebuilt mid C20. Horned plate-glass late C19 sashes in ashlar surrounds. INTERIOR not inspected.
Listing NGR: ST9985370876

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Type and date: Late C20 SHOP. Date: from 1967 to 1999
Type and date: Early C19 SHOP. Date: from 1800 to 1832
Type and date: Mid C20 SHOP. Date: from 1933 to 1966
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Main material: limestone
Main material: rubble
Main material: brick
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99853 70876 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

29 Church Street, Calne, Wiltshire, SN11 0HY

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36411 Building: 29, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455156

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5920 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246439 | 1246439 | 755-1, 5, 34 |

**Name:**

**DesigUID:** DWI5920 **Name:**

**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/34 (East side)
19/05/50 No.32
GV II
House. Mid-late C17, refronted mid C18, with an early C19 porch. Limestone ashlar with a large central brick ridge stack and stone slate roof. Double-depth plan. 2 storeys and attic; 3-window range. Rusticated quoins to a deep coved cornice returned at the ends, and blocking course; plinth. Architraved doorway with a pediment and 6-panel door; a good Greek Revival-style prostyle porch has steps up, paired Doric columns on plinths, to an entablature with triglyphs, cornice and blocking course. Shallow surrounds to 3-light flat-faced stone-mullioned windows and 6-pane casements, with a central first-floor window in similar flat-faced surround. 2 gabled dormers, restored C20. INTERIOR: details include chamfered beams, a left-hand early C19 central dogleg stair with stick balusters and column newels; collar truss roof.
Listing NGR: ST9987870839

**Curatorial Notes**

Type and date: Mid-late C17 HOUSE. Date: from 1633 to 1699
Type and date: Mid C18 HOUSE. Date: from 1733 to 1766
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: STEPS.
Main material: limestone
Main material: ashlar
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99872 70837 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

32 Church Street, Calne, Wiltshire, SN11 0HZ

**Designation History**

**Assignment**

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36413 Building: 32, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455158

**DesigUID:** DWI5920 **Name:**

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5921 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246440 | 1246440 | 755-1, 5, 35 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/35 (East side)
08/07/76 Nos.34 AND 36
GV II
Pair of houses with shops. Early-mid C19. Limestone rubble, rendered to No.34, with red brick stacks to pantile roofs. Double-depth plan. 2 storeys. Each of 2-window range with late C19 2/2-pane and plate-glass sashes to first floor. Both have mid/late C19 shop fronts with pilasters to projecting cornices, altered fenestration; No.34 has late C20 glazed door to left, and No.36 has gabled roof dormers. INTERIORS not inspected.
Listing NGR: ST9987970831

**Curatorial Notes**

Type and date: Early-mid C19 HOUSE. Date: from 1800 to 1866
Type and date: Mid/late C19 SHOP. Date: from 1866 to 1899
Main material: limestone
Main material: rubble
Main material: render
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99873 70826 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

34 Church Street, Calne, Wiltshire, SN11 0HZ

34 Church Street, Calne, Wiltshire, SN11 0HZ

36 Church Street, Calne, Wiltshire, SN11 0HZ

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**DesigUID:** DWI5921 **Name:**

**Associated Monuments**

MWI36414 Building: 34 AND 36, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455159

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5922 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246441 | 1246441 | 755-1, 5, 36 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/36 (West side)
08/07/76 No.35
GV II
House. Late C18 or early C19, altered mid C20. Limestone rubble, ridge stack and slate roof. Single-depth plan, attached to the rear of No.37 (qv). Single storey and attic; 4-window range. A mid C20 left-hand doorway and door, with altered C20 sashes, and 2 hipped dormers. INTERIOR: reported to have chamfered ceiling beams and a hob grate to the ground floor.
Listing NGR: ST9984570843

**Curatorial Notes**

Type and date: Late C18 or early C19 HOUSE. Date: from 1767 to 1832
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

---

**Location**

**Grid Reference:** ST 99845 70843 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

---

**Designation History**

**Assignment**

**DesigUID:** DWI5922 **Name:**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36415 Building: 35, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455160

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5923 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246442 | 1246442 | 755-1, 5, 37 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/37 (West side)
08/07/76 Nos.37, 39 AND 40
GV II
Terrace of 3 houses, now with one shop. Early C19. Rendered limestone rubble, brick ridge stacks and pantile roof. Double-depth plan. 2 storeys and attic; 2:1:2-window range. No.37 has a late C19 double-fronted shop front with timber pilasters and cornice, 6-panel door, a small right-hand window and 2 late C19 three-light first-floor casements. No.39 has a right-hand mid C20 door, and similar 3-light casements windows. No.40 double-fronted, with a boarded door, similar 3-light casement to ground-floor right and mid C20 windows. 3 gabled dormers with mid C20 windows. INTERIOR not inspected.
Listing NGR: ST9985670835

**Curatorial Notes**

Type and date: Early C19 TERRACE. Date: from 1800 to 1832
Type and date: Early C19 TERRACED HOUSE. Date: from 1800 to 1832
Type and date: Late C19 SHOP. Date: from 1867 to 1899
Main material: render
Main material: limestone
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99855 70840 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**DesigUID:** DWI5923 **Name:**

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

39 Church Street, Calne, Wiltshire, SN11 0HZ

40 Church Street, Calne, Wiltshire, SN11 0HZ

40 Church Street, Calne, Wiltshire, SN11 0HZ

37 Church Street, Calne, Wiltshire, SN11 0HZ

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36416 Building: 37,39 AND 40, CHURCH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455161

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5925 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246443 | 1246443 | 755-1, 5, 39 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/39 (West side)
08/07/76 Nos.42 AND 43
GV II

Pair of attached houses, now house and shop. Late C18. Limestone rubble with brick quoins to openings, and a pantile roof. Double-depth plan. 2 storeys; 2-window range. Timber lintels to a central wide doorway with 6-panel door, and over horned 2/2-pane sashes; an altered left-hand late C19 shop front with right-hand door; 2 raking dormers with C20 casements. INTERIOR not inspected. Listing NGR: ST9986170819

**Curatorial Notes**

Type and date: Late C18 HOUSE. Date: from 1767 to 1799
Type and date: Late C19 SHOP. Date: from 1867 to 1899

**DesigUID:** DWI5925 **Name:**

Main material: limestone
Main material: rubble
Main material: brick
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99861 70819 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

42 Church Street, Calne, Wiltshire, SN11 0HZ

43 Church Street, Calne, Wiltshire, SN11 0HZ

42 Church Street, Calne, Wiltshire, SN11 0HZ

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36418 Building: 42 and 43, Church Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455163

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5926 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271047 | 1271047 | 755-1, 5, 40 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/40 (West side)
08/07/76 Nos.44 AND 45
GV II

**DesigUID:** DWI5926 **Name:**

Pair of attached houses. Early C19, altered and No.45 built in mid C19. Squared, coursed limestone rubble with ashlar quoins to left end of No.44; slate roof. Double-depth plan. 2 storeys and attic; 1:2-window range. Right-hand double-fronted house has a recessed doorway, left-hand house has a left-hand door. Ground-floor windows boarded at time of review; paired mid-late C19 horned 2/2-pane sashes to first floor. INTERIOR not inspected.
Listing NGR: ST9985370809

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Mid C16 HOUSE. Date: from 1833 to 1866
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99863 70807 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

44 Church Street, Calne, Wiltshire, SN11 0HZ

44 Church Street, Calne, Wiltshire, SN11 0HZ

45 Church Street, Calne, Wiltshire, SN11 0HZ

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36419 Building: 44 and 45, Church Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455164

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5951 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247208 | 1247208 | 755-1, 4, 67 |

**DesigUID:** DWI5951 **Name:**

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/67 (West side)
08/07/76 No.6
GV II
House, now shop. Early C19, altered late C19. Rendered limestone rubble with brick gable stacks and hipped pantile roof. Single-depth plan. 2 storeys; corner site with half-glazed door in splayed right-hand corner to 1+2-window range. Corner site with a splayed right-hand corner, half-glazed door; late C19 plate-glass shop fronts with entablatures each side, and 6/6-pane sashes including 2 to the right-hand return and one to the ground floor beneath. Right-hand door on return has a fanlight and 6-panel door. INTERIOR: altered late C20. Connected internally to No.1 Market Hill (qv) to the right.
Listing NGR: ST9970471044

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C19 HOUSE. Date: from 1867 to 1899
Type and date: Late C19 SHOP. Date: from 1867 to 1899
Main material: render
Main material: limestone
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99712 71053 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

6 High Street, Calne, Wiltshire, SN11 0BJ

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36439 Building: 6, HIGH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456517

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5951 **Name:**

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5952 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247209 | 1247209 | 755-1, 4, 68 |

**Name:**

**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/68 (East side)
19/05/50 No.8
GV II

Formerly known as: Hawkins HIGH STREET. House and inn, now shop. Late C17, refronted and extended early C18; further rear extension in early C19; altered internally late C20. C19 rendered brick with stone dressings, otherwise rendered rubble with squared, coursed limestone rubble sides; brick stacks to right-hand and rear gables, stone slate roof, with pantiles to the rear. 2-room parallel plan with right-hand rear wing, extended twice. 2 storeys and attic; 3-window range. Early C19 shop front has an ashlar stall riser beneath C20 plate-glass windows which curve in to a left-hand doorway and panelled door, with heavy ovolo-moulded timber doorposts, and a full-width bracketed canopy; to the left a segmental-arched carriage opening inserted between No.9 (qv). Rusticated first-floor quoins, timber modillion cornice gutter. Early C18 bolection-moulded architraves to early C19 6/6-pane sashes, and 2 C19 gabled dormers with casements. Original lead downpipe and decorative hopper with wreath flanked by figures. Rear wing has brick gable and exposed C19 sawn purlin ends, the carriage passage has timber joists and a horizontal sliding sash in a blocked former side entrance; 2 further ranges of different heights with wide timber lintels. INTERIOR: includes a panelled ground-floor room in rear extension with boxed out cornice; front ground floor has late C20 inserted stair, partition walls removed. HISTORICAL NOTE: forms a U-shaped plan with No.9 (qv), suggesting a previous use as an inn.
Listing NGR: ST9974471073

**Curatorial Notes**

Type and date: Late C17 HOUSE. Date: from 1667 to 1699
Type and date: Late C17 INN. Date: from 1667 to 1699
Type and date: Early C18 INN. Date: from 1700 to 1732
Type and date: Early C18 HOUSE. Date: from 1700 to 1732
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Early C19 INN. Date: from 1800 to 1832
Type and date: Early C19 SHOP. Date: from 1800 to 1832
Main material: render
Main material: brick
Main material: stone
Main material: limestone
Covering material: stone
Covering material: pantile

**Designating Organisation:**

**Location**

**DesigUID:** DWI5952 **Name:**

**Grid Reference:** ST 99736 71073 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**
Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**
8 High Street, Calne, Wiltshire, SN11 0BS

**Listed Building Addresses**
Alternative
HAWKINS

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**
MWI36440 Building: 8, High Street

**Associated Consultations - None**

**Additional Information**
**LBSUID:** 456518

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5953 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270987 | 1270987 | 755-1, 4, 69 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**
CALNE
ST9971 HIGH STREET
755-1/4/69 (East side)
08/07/76 No.9
GV II
Attached house, inn, now shop and office. Mid/late C17, refronted early C19. Rendered front, coursed limestone rubble sides, brick rear ridge stack and a slate roof. 2-room parallel plan with left-hand rear wing. Forms a U-shaped plan with No.8 (qv) suggesting an original use as an inn. 2 storeys and attic; 2-window range. A left-hand late C19 shop front with left-hand door, plate-glass window, with an inserted right-hand carriage archway shared with No.8 (qv); cornice and blocking course. Tripartite 6/6-pane sashes. Archway has heavy timber joists, sandstone sets in the carriageway, a side entrance beyond, and the 2-window rear wing has C19 casements. INTERIOR: details include a C19 stair from

the side entrance, with an attic stair above parallel to the side; front 4-bay roof divided by a C17 stud partition with lath and plaster, later rear wing divided by a ridge stack, with late C19 roof and wide oak floor boards. In the rear is a well.
Listing NGR: ST9974071081

**Curatorial Notes**

Type and date: Mid/late C17 HOUSE. Date: from 1633 to 1699
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Mid/late C17 INN. Date: from 1633 to 1699
Type and date: Late C19 SHOP. Date: from 1867 to 1899
Type and date: Now OFFICE.
Type and date: Early C19 INN. Date: from 1800 to 1832
Type and date: WELL.
Main material: render
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99733 71082 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

9 High Street, Calne, Wiltshire, SN11 0BS

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36441 Building: 9 High Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456519

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5955 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270988 | 1270988 | 755-1, 4, 71 |

**DesigUID:** DWI5955 **Name:**

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/71 (East side)
08/07/76 No.12
GV II
House, police station, now shop. Mid C18, altered mid C19, mid C20 shop front. Coursed limestone rubble, limestone dressings, ashlar right-hand gable stack, and slate roof. Plate-glass shop front with a right-hand passage entrance; stone first floor with a large inserted C19 Venetian window with central 6/6-pane sash, cornice and low blocking course, and 2 dormers with casements and hipped roofs. Rear has blocked 2-light C18 window with chamfered mullions. INTERIOR: ground-floor shop, altered. Formerly the Police Station until c1886.
Listing NGR: ST9973071099

**Curatorial Notes**

Type and date: Mid C18 HOUSE. Date: from 1733 to 1766
Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Mid C20 SHOP. Date: from 1933 to 1966
Type and date: Until c1886 POLICE STATION.
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99729 71101 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

12 High Street, Calne, Wiltshire, SN11 0BS

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36443 Building: 12, High Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456521

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5955 **Name:**

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5956 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247211 | 1247211 | 755-1, 4, 72 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/72 (East side)
08/07/76 No.13
GV II
House, now shop. Early C19, altered mid C20. Rendered, brick right-hand gable stack, ashlar stack to rear, and slate roof. 2 storeys and attic; 4-window range. C20 shop front with plate-glass windows; pilaster strips above to a cornice and parapet, with plate-glass sashes, the left-of-centre one blocked. Wide mid C20 dormer. INTERIOR altered mid C20. Included for group value.
Listing NGR: ST9972971106

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Type and date: Now SHOP.
Main material: render
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99725 71106 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

T G Jeary Chemist 13 High Street, Calne, Wiltshire, SN11 0BW

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36444 Building: 13 High Street

**Associated Consultations - None**

**Additional Information**

**DesigUID:** DWI5956 **Name:**

**LBSUID:** 456522

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5957 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270989 | 1270989 | 755-1, 4, 73 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/73 (East side)
08/07/76 Nos.15, 16 AND 17
GV II
Terrace of 3 houses, now shops. Mid C19. Limestone rubble with rendered front, slate roof and brick stacks. 2 storeys; 2:1:1-window range. Cornice and blocking course; right-hand doorways and C20 shop fronts to Nos 15 & 16, with a right-hand passage entrance, left-hand door to No.17 with a late C20 brick shop front. Raised window surrounds with cill blocks and 2/2-pane sashes. INTERIOR not inspected. Included for group value.
Listing NGR: ST9972871111

**Curatorial Notes**

Type and date: Mid C19 TERRACE. Date: from 1833 to 1866
Type and date: Mid C19 TERRACED HOUSE. Date: from 1833 to 1866
Type and date: C20 SHOP. Date: from 1900 to 1999
Type and date: Late C20 SHOP. Date: from 1967 to 1999
Main material: limestone
Main material: rubble
Main material: render
Covering material: slate
Main material: brick

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99725 71117 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

15 High Street, Calne, Wiltshire, SN11 0BS

16 High Street, Calne, Wiltshire, SN11 0BS

17 High Street, Calne, Wiltshire, SN11 0BS

15 High Street, Calne, Wiltshire, SN11 0BS

**DesigUID:** DWI5957 **Name:**

**Designation History**

Assignment
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36445 Building: 15,16 and 17, High Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456523

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5960 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270990 | 1270990 | 755-1, 4, 75 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/75 (East side)
08/07/76 Nos.19 AND 21
GV II
Pair of attached houses, now shops. Mid C19, altered mid C20. Limestone ashlar, slate roof. 2 storeys; 5-window range. Late C20 shop fronts; pilaster strips flank facade with first-floor cill band, frieze, cornice and parapet; shallow canted 3-light left-hand oriel; late C19 horned plate-glass sashes. INTERIOR not inspected. Included for group value.
Listing NGR: ST9972871125

**Curatorial Notes**

Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Type and date: Late C20 SHOP. Date: from 1967 to 1999
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99723 71130 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**DesigUID:** DWI5960 **Name:**

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

19 High Street, Calne, Wiltshire, SN11 0BS

19 High Street, Calne, Wiltshire, SN11 0BS

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36447 Building: 19 AND 21, HIGH STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456526

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5962 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270991 | 1270991 | 755-1, 5, 79 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 KINGSBURY STREET
755-1/5/79 (South side)
08/07/76 No.1
GV II

Pair of attached houses, altered and made into one. Late C17 or early C18, later C18 wing to rear; altered late C20. Coursed limestone rubble with brick gable and ridge stacks, pantile roof. L-shaped plan with later C18 wing facing Church Street. 2-storey, 2-window range to Kingsbury Street, which includes right-hand gable end of earlier 2-storeys-and-attic range. Central recessed door with panelled door, and timber lintels to paired ground-floor 2/2-pane sashes, and 3-light casements above. Right-hand return to Church Street has a low central doorway with chamfered frame, timber lintels to varied late C19 and C20 fenestration, including wide first- and second-floor 4-light casement windows. Blocked left-hand first-floor window. A straight joint to a right-hand C19 2-storey lean-to. INTERIOR: details of Kingsbury Street range include 3 inch chamfer ground-floor beams, an original timber winder stair to the rear of the left-hand fireplace, with a first-floor 3-plank door with strap hinges, and 3-bay roof with some original tenoned purlins. From the roof is visible one tie beam end and rafters of the

**DesigUID:** DWI5962 **Name:**

later roof to the Church Street range, which has late C18 trusses, a chamfered axial first-floor beam and altered stairs.
Listing NGR: ST9987070859

**Curatorial Notes**

Type and date: Late C17 or early C18 HOUSE. Date: from 1667 to 1732
Type and date: Later C18 HOUSE. Date: from 1733 to 1799
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Main material: limestone
Main material: rubble
Main material: brick
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99868 70861 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1-2 Kingsbury Street, Calne, Wiltshire, SN11 8DF

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36449 Building: 1, KINGSBURY STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456528

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5963 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247306 | 1247306 | 755-1, 5, 80 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE

**DesigUID:** DWI5963 **Name:**

ST9970 KINGSBURY STREET
755-1/5/80 (South side)
08/07/76 No.3
GV II
House. Probably C18, refronted early C19. Rendered with brick gable stack and pantile roof. Single-depth plan. 2-storeys and attic; 3-window range. Left of centre recessed doorway has a 4-panel door, a blank window above, with 8/8-pane sashes each side, and 2 gable dormers with casements.
INTERIOR not inspected.
Listing NGR: ST9987970859

**Curatorial Notes**

Type and date: C18 HOUSE. Date: from 1700 to 1799
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: render
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99876 70862 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

3 Kingsbury Street, Calne, Wiltshire, SN11 8DF

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36450 Building: 3, KINGSBURY STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456529

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5964 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247215 | 1247215 | 755-1, 5, 81 |

**Name:**

**DesigUID:** DWI5964 **Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 KINGSBURY STREET
755-1/5/81 (South side)
08/07/76 Nos.4 AND 5
GV II

Attached pair of houses. Early C19, altered late C20. Rendered with brick gable stacks and slate roof. Single-depth plan. 2 storeys and attic; 3-window range. A symmetrical front has paired doorways with bracketed pediments and late C20 doors; 2-light flat-faced stone-mullioned windows with 6/6-pane sashes, blank to the centre of the first-floor; 3 hipped dormers with 6-pane 2-light casement windows. INTERIOR not inspected.
Listing NGR: ST9988670862

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Main material: render
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99884 70863 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

5 Kingsbury Street, Calne, Wiltshire, SN11 8DF

4 Kingsbury Street, Calne, Wiltshire, SN11 8DF

4 Kingsbury Street, Calne, Wiltshire, SN11 8DF

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36451 Building: 4 AND 5, KINGSBURY STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456530

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5964 **Name:**

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5965 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247307 | 1247307 | 755-1, 5, 82 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 KINGSBURY STREET
755-1/5/82 (South side)
08/07/76 Nos.6 AND 9
GV II

Pair of attached houses. Early/mid C19. Rendered, with brick gable stacks and slate roof. Each of 2 storeys; 1-window range. A symmetrical range with a central through-passage to Nos 7 & 8 at the back (not included), with doorways each side and 6-panel doors with overlights; a blind window above, and 8/8-pane sashes each side. INTERIOR not inspected.
Listing NGR: ST9989470864

**Curatorial Notes**

Type and date: Early/mid C19 CROSS PASSAGE HOUSE. Date: from 1800 to 1866
Main material: render
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99894 70866 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

6 Kingsbury Street, Calne, Wiltshire, SN11 8DF

6 Kingsbury Street, Calne, Wiltshire, SN11 8DF

9 Kingsbury Street, Calne, Wiltshire, SN11 8DF

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36452 Building: 6 AND 9, KINGSBURY STREET

**Associated Consultations - None**

**Additional Information**

**DesigUID:** DWI5965 **Name:**

**LBSUID:** 456531

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5974 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247317 | 1247317 | 755-1, 4, 91 |

**Name:**
**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 MARKET HILL
755-1/4/91 (South side)
02/04/70 No.1
GV II
House in row. Late C18, with mid C19 alterations. Rendered and colourwashed, Welsh slate roof between coped gables, brick chimney stacks, partly rendered. Symmetrical parallel range plan, but the front range has been modified, with no rear slope at its west end. EXTERIOR: 2 storeys with attics, 3 bays. Plinth, cornice with timber box gutter on a coved cornice. Sash windows to outer bays, plain below and 12-pane above, in centre a C20 panelled door with square transom-light in plain surround, and above is a blind panel with ovolo mould architrave, impost blocks and keystone. The ground-floor windows have `floating' keystones, and all cills are in stone. Three 2-light C20 casement windows in gabled dormers, with slating to gables and cheeks. INTERIOR: not inspected. The site has been occupied since at least since the C13, when the street was known as Byestewel. The present property was probably rebuilt at the same time as Nos 4 & 6 (qqv), with which it shares some detail; it is set back approx. 300m from these adjoining units.
Listing NGR: ST9970471044

**Curatorial Notes**

Type and date: Late C18 ROW. Date: from 1767 to 1799
Type and date: Late C18 ROW HOUSE. Date: from 1767 to 1799
Type and date: Mid C19 ROW HOUSE. Date: from 1833 to 1866
Type and date: Mid C19 ROW. Date: from 1833 to 1866
Main material: render
Covering material: welsh slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99701 71049 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Market Hill, Calne, Wiltshire, SN11 0BT

**DesigUID:** DWI5974 **Name:**

**Designation History**

**Assignment**
02/04/1970

**Sources - None recorded**

**Associated Monuments**
MWI36460 Building: 1, MARKET HILL

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456687

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5976 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247318 | 1247318 | 755-1, 4, 93 |

**Name:**
**Grade:** II* **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**
CALNE
ST9971 MARKET HILL
755-1/4/93 (North side)
19/05/50 No.3
GV II*
Formerly known as: St Brigett's, St Mary's School, MARKET HILL.
House, school, now offices. Dated 1683, restored c1980. Rendered limestone rubble, ashlar right-hand lateral stack and stone slate hipped roof with flat, leaded centre. Double-depth plan with right-hand stair. 3 storeys, attic and cellar; 3-window range. Road front has a first-floor drip course; right of centre entrance with an early C19 timber bracketed pediment, ashlar surround and 6-panel door, with wrought-iron rails to steps up. Early or mid C19 ground-floor 6/6-pane sashes, paired to the left; bolection-moulded architraves to late C18 6/6-pane first-floor sashes, and original stone-mullioned and transomed second-floor cavetto-moulded cross windows. W front has a continuous ground-floor label mould and first-floor string, with bolection-moulded paired ground-floor 6/6-pane sashes, and original 3- and central 2-light cross windows above; 2 late C20 hipped dormers, replacing a central one. Central sundial inscribed 1683. 2 similar cross windows light stairs to right-hand return. INTERIOR: details include a fine late C17 dogleg stair with turned balusters, square panelled newels, uncut string; fully panelled rear right-hand room and fire surround; vaulted cellar; C18 roof with plastered central room and 3-plank door, inscribed JG/1786; original 2-panel doors; first-floor C19 Egyptian Revival hob grates in bolection-moulded surrounds. The front room has a fine C17 stone fire surround and overmantel from Castle House (qv), with a carved central panel of a burning crocodile, and 2 figures supporting a painted cartouche. The flat, leaded roof may formerly have supported a lantern.
Listing NGR: ST9968671037

**DesigUID:** DWI5976 **Name:**

**Curatorial Notes**

Type and date: 1683 HOUSE. Date: 1683
Type and date: c1980 HOUSE. Date: from 1970 to 1990
Type and date: SCHOOL.
Type and date: Now OFFICE.
Type and date: RAILINGS.
Type and date: STEPS.
Type and date: 1683 SUNDIAL. Date: 1683
Main material: render
Main material: limestone
Main material: rubble
Covering material: stone
Covering material: lead
Main material: wrought iron

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99684 71041 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

3 Market Hill, Calne, Wiltshire, SN11 0EG

**Listed Building Addresses**

Alternative
ST BRIGETT'S
Alternative
ST MARY'S SCHOOL

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36364 Building: 3 Market Hill

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456689

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5976 **Name:**

**DesigUID:** DWI5978 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270944 | 1270944 | 755-1, 4, 95 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 MARKET HILL
755-1/4/95 (West side)
08/07/76 No.5
GV II

House, now shop. Early/mid C19, gable rebuilt c1963. Rendered with coursed rubble limestone gable, and a slate roof. Double-depth plan. 2 storeys and attic; 2-window range. Coped gable; shop front with a left-hand doorway with panelled door and bracketed canopy, and paired 2/2-pane horned sashes, with a matching first-floor window; gabled casement dormer. Rubble rear range with oak lintel over casement window. INTERIOR: noted as having a C19 left-hand stair with stick balusters.
Listing NGR: ST9967771067

**Curatorial Notes**

Type and date: Early/mid C19 HOUSE. Date: from 1800 to 1866
Type and date: Now SHOP.
Type and date: After c1963 SHOP. Date: from 1953
Main material: render
Main material: rubble
Main material: limestone
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99676 71068 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

5 Market Hill, Calne, Wiltshire, SN11 0BU

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36366 Building: 5, MARKET HILL

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456691

**DesigUID:** DWI5978 **Name:**

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5981 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270946 | 1270946 | 755-1, 5, 97 |

**Name:**
**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 MILL STREET
755-1/5/97 (West side) Nos.14-20 (Consecutive)
GV II

Row of 6 cottages with 7th cottage to rear. Mid/late C18, except Nos 14 and 15 probably of early C19; late C17 No.20 to rear of No.19, refronted in late C19. Coursed limestone rubble, pantile (of gambrel type to Nos 14 & 15) roofs with brick stacks to gable ends and some party walls; gabled concrete tile roof to No.20 with rear end stack. Double-depth plan to Nos 14 & 15; Nos 16-18 each of single-unit plan with later rear outshuts. No.20 is a late C17 2-room central-entry plan with large heated room and small service room; it is reached by a passage underneath and to the right of No.19. 2 storeys with attics; each cottage is one-window range, except 2-window range to Nos 19 & 20. Nos 14 & 15 to the left each have a small gabled dormer to the front and similar larger C20 dormers to the rear set in a continuous mansard roof. No.14 has C20 door to the right and C20 windows, No.15 has C19 four-panel door to the left, a C19 paired horned plate-glass sash window to the right and a C20 two-light window to the first floor. No.16 has C19 casement windows, 2-lights to the first floor, 3-lights to the ground floor and a C20 door to the right. No.17 has a C19 horned 2/2-pane sash window to the first floor and a C20 door to the left of a C20 window under C18 chamfered wood lintel. No.18 has a double-pitched pantile roof covering the front and the rear left wing, added later but of similar date; the front is rendered, incised to the ground floor, with a C20 two-light casement window to the first floor over a C19 tripartite sash window to the left of a late C18 frame and 6-panel door. No.19 has brick architraves to horned 2/2-pane sashes; stone lintel over C20 door and segmental brick arch over passage door. No.20 has timber lintels over C19 first-floor 3-light casements, and central C20 door and flanking casements. INTERIOR of No.18: the ground floor has an open fire to the front room with ashlar lintel and jambs within a later stone surround; the original, now exposed rubblestone rear wall separates the rear left wing, both rooms have chamfered crossbeams and the rear wing now has exposed rafters. The roof to the front has trenched purlins, the roof to the rear wing has threaded purlins and ridge with rafters resting on the ridge. No.20 not inspected but likely to be of interest. HISTORICAL NOTE: these are said to have been built as millworkers' cottages, the attics originally interlinked where wool was dried. These cottages occupy a prominent position close to the Church of St Mary (qv).
Listing NGR: ST9994270935

**Curatorial Notes**

Type and date: Mid/late C18 ROW HOUSE. Date: from 1733 to 1799
Type and date: Mid/late C18 ROW. Date: from 1733 to 1799
Type and date: Early C19 ROW. Date: from 1800 to 1832
Type and date: Early C19 ROW HOUSE. Date: from 1800 to 1832
Type and date: Late C17 ROW HOUSE. Date: from 1667 to 1699

**DesigUID:** DWI5981 **Name:**

Type and date: Late C17 ROW. Date: from 1667 to 1699
Type and date: Late C19 ROW. Date: from 1867 to 1899
Type and date: Late C19 ROW HOUSE. Date: from 1867 to 1899
Type and date: SERVICE WING.
Type and date: WORKERS COTTAGE.
Main material: limestone
Main material: rubble
Main material: render
Main material: stone
Covering material: pantile
Covering material: concrete
Covering material: tile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99938 70938 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

14 Mill Street, Calne, Wiltshire, SN11 8DP
17 Mill Street, Calne, Wiltshire, SN11 8DP
18 Mill Street, Calne, Wiltshire, SN11 8DP
15 Mill Street, Calne, Wiltshire, SN11 8DP
16 Mill Street, Calne, Wiltshire, SN11 8DP
16 Mill Street, Calne, Wiltshire, SN11 8DP
19 Mill Street, Calne, Wiltshire, SN11 8DP

**Designation History**

**Assignment**
22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI36369 Building: 14-20, MILL STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456694

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5982 **Name:**

**DesigUID:** DWI5982 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247322 | 1247322 | 755-1, 5, 98 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 MILL STREET
755-1/5/98 (South side)
08/07/76 No.21
GV II

House. Late C17. Coursed limestone rubble, formerly rendered, with a left-hand brick stack and pantile roof. 2-room parallel plan with rear additions. 2 storeys and attic; 2-window range. Central doorway has a heavy timber frame and 3-plank door; timber lintels over 3-light timber mullion windows and casements with a horizontal bar. Rear has a central door, 4-light attic window and C19 gable dormer. Right-hand gable has a 3-light timber mullion window, probably from a former stair. INTERIOR: details include a through-passage with chamfered axial beams with roll stops, large fireplaces, on the first floor with a bressumer and stone cheeks; inserted right-hand stair rises to attic with collar truss roof and tenoned purlins.
Listing NGR: ST9992370925

**Curatorial Notes**

Type and date: Late C17 CROSS PASSAGE HOUSE. Date: from 1667 to 1699
Main material: limestone
Main material: rubble
Main material: render
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99919 70927 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

21 Mill Street, Calne, Wiltshire, SN11 8DP

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36370 Building: 21, MILL STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456695

**DesigUID:** DWI5982 **Name:**

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5986 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247324 | 1247324 | 755-1, 5, 105 |

**Name:**
**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/105 (East side) No.8
GV II
House. Early-mid C19. Roughcast over limestone rubble, slate roof. Double-depth plan. 3 storeys; symmetrical 3-window range. C20 horned 6/6-pane sash windows, that to the 2nd-floor centre is blind. Early C19 six-panel door with iron knocker of a ring of twisted rope design and shallow overlight. INTERIOR: details include a through-passage with a closed string staircase with stick balusters to the rear right; landings to the first and second floors have a narrow rear closet extension jettied out over the ground floor and supported by pillars.
Listing NGR: ST9981170819

**Curatorial Notes**

Type and date: Early-mid C19 CROSS PASSAGE HOUSE. Date: from 1800 to 1866
Main material: roughcast
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99811 70819 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

8 New Road, Calne, Wiltshire, SN11 0JQ

**Designation History**

**Assignment**
22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI32985 Building: 8, NEW ROAD

**DesigUID:** DWI5986 **Name:**

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456699

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5987 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247325 | 1247325 | 755-1, 5, 106 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/106 (East side)
08/07/76 Nos.17, 18, 19 AND 19A Ivy House
(Formerly Listed as: NEW ROAD (East side) Nos.17-21 (Consecutive))
GV II
Terrace of 4 houses, altered. Early C19. Rendered limestone rubble, ridge stacks and hipped slate roof. 2 storeys and attic; 1:3:2-window range facing New Road. No.17 has principal front to the left return, double-fronted with quoins, a round-arched doorway and 6-panel door, with 8/8-pane sashes. No.18 formerly 2 houses, double-fronted with a round-arched doorway and C20 panelled door, late C19 2/2-pane left-hand sashes, and right-hand first-floor timber oriel. No.19 with C19 shop fronts, a central doorway and 8/8-pane first-floor sashes, and a wide C20 dormer. No.19A is in the parallel rear range behind No.19, with an entrance in the right-hand return, beneath a 10/10-pane sash. INTERIOR not inspected.
Listing NGR: ST9982970795

**Curatorial Notes**

Type and date: Early C19 TERRACE. Date: from 1800 to 1832
Type and date: Early C19 TERRACED HOUSE. Date: from 1800 to 1832
Type and date: C19 SHOP. Date: from 1800 to 1899
Main material: render
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99829 70795 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

**DesigUID:** DWI5987 **Name:**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

5 New Road, Calne, Wiltshire, SN11 0JJ

**Listed Building Addresses**

Statutory

IVY HOUSE

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36374 Building: IVY HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456700

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5988 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247326 | 1247326 | 755-1, 5, 107 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/107 (East side)
08/07/76 No.20
(Formerly Listed as: NEW ROAD (East side) Nos.17-21 (Consecutive))
GV II

House and shop. Early C19. Rendered limestone rubble, brick gable stacks and slate roof. Double-depth plan with front left wing at right angles. 2 storeys; 3-window range. Double-fronted, with round-arched doorway and fanlight, blocked central first-floor window, and 8/8-pane sashes. Front of wing projecting to right has a good mid C19 shop front with cornice, bracketed cill and 2-panel window, beneath a wide canted first-floor bay; flat-roofed porch with C20 door to left. INTERIOR: details include a flagged hall, left-hand lateral dogleg stair, right-hand fireplace, cupboards set into walls. Listing NGR: ST9984270784

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832

**DesigUID:** DWI5988 **Name:**

Type and date: Mid C19 SHOP. Date: from 1833 to 1866
Main material: render
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99842 70784 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

20 New Road, Calne, Wiltshire, SN11 0JQ

**Designation History**

Assignment
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36375 Building: 20, NEW ROAD

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456701

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5999 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247339 | 1247339 | 755-1, 5, 118 |

**Name:**
**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/118 (West side)
02/04/70 No.1
GV II
House, now offices. Early C19. Render with limestone ashlar dressings, coursed rubble sides, brick ridge and lateral stacks and a pantile roof. Single-depth plan with rear range making L-plan. 2 storeys

**DesigUID:** DWI5999 **Name:**

and attic; 2-window range. A symmetrical front has a round-arched doorway and panelled door with a radial fanlight, and 6/6-pane sashes, with a single gabled dormer. 2-window side range with uneven fenestration including C19 sashes with glazing bars and a lateral stack. INTERIOR: details include an altered ground floor and C19 right-hand dogleg stair with stick balusters.
Listing NGR: ST9970570972

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Now OFFICE.
Main material: render
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99705 70972 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Patford Street, Calne, Wiltshire, SN11 0EF

**Designation History**

**Assignment**
02/04/1970

**Sources - None recorded**

**Associated Monuments**

MWI36385 Building: 1, PATFORD STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456747

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6000 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247340 | 1247340 | 755-1, 5, 119 |

**Name:**
**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**DesigUID:** DWI6000 **Name:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/119 (West side)
19/05/50 Nos.2 AND 3
GV II

House, divided into 2, now offices. Early-mid C17, altered mid C20. Rendered with pantile roof. 2-room plan. 2 storeys and attic; 3-window range. Formerly a central doorway, now blocked with a late C20 casement, with flanking full-height C17 shallow canted bays; these have ground-floor C20 casements, and first-floor timber 5-light mullion and transom windows with an overhanging canopy and dentil cornice. 2 gabled dormers with C19 casements. INTERIOR: details include a 4-bay roof with butt purlins, ridge not visible; good scratch-moulded panelling to left-hand first-floor room, panelled window reveals, wall cupboard with double doors and wrought-iron cockshead hinges, carved cornice; blocked salt cupboard to fire surround; chamfered ground-floor beams. Forms part of No.1 (qv).
Listing NGR: ST9970670966

**Curatorial Notes**

Type and date: Early-mid C17 HOUSE. Date: from 1600 to 1666
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Main material: render
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99703 70965 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Patford Street, Calne, Wiltshire, SN11 0EF

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36386 Building: 2 - 3 Patford Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456749

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6000 **Name:**

**DesigUID:** DWI6001 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270924 | 1270924 | 755-1, 5, 120 |

**Name:**

**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/120 (West side)
02/04/70 No.4
(Formerly Listed as: PATFORD STREET (West side) Calne Municipal Offices)
GV II
House, now surgery. C18, altered early C19, altered late C20. Limestone rubble and squared rubble, ashlar dressings and a slate roof. Single-depth plan. 2 storeys; 2-window range. A low ashlar plinth; left-hand doorway with a 6-panel door; early C19 inserted ashlar lintels to paired horned 2/2-pane sashes. Squared coursed rubble upper courses suggest an earlier roofline and origins. INTERIOR: altered, with C20 roof, but C18 chamfered beams survive.
Listing NGR: ST9969870938

**Curatorial Notes**

Type and date: C18 HOUSE. Date: from 1700 to 1799
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Type and date: Now SURGERY.
Type and date: LOCAL GOVERNMENT OFFICE.
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99701 70957 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

4 Patford Street, Calne, Wiltshire, SN11 0EF

**Listed Building Addresses**

Former Statutory
CALNE MUNICIPAL OFFICES

**Designation History**

**Assignment**

02/04/1970

**Sources - None recorded**

**Associated Monuments**

**DesigUID:** DWI6001 **Name:**

MWI36387 Building: 4, PATFORD STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456750

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6002 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270925 | 1270925 | 755-1, 5, 121 |

**Name:**
**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/121 (West side)
02/04/70 No.5
(Formerly Listed as: PATFORD STREET (West side) Calne Municipal Offices)
GV II
House, now offices. Early-mid C18. Limestone rubble and dressings, formerly rendered, brick gable stack and pantile roof. Single-depth plan. 3 storeys and cellar; 3-window range. A ground-floor drip mould, with frieze, cornice and blocking course, and quoins. A left-hand doorway with late C20 door, keyed lintels to horned 2/2-pane sashes, smaller on the second floor. INTERIOR: details include central axial dogleg stair with turned balusters, square newels and moulded rail; boarded stud panelling, chamfered beams and 4-hinge door; oak winder stair to attic with C18 collar-truss roof.
Listing NGR: ST9970270948

**Curatorial Notes**

Type and date: Early-mid C18 HOUSE. Date: from 1700 to 1766
Type and date: Now OFFICE.
Type and date: LOCAL GOVERNMENT OFFICE.
Main material: limestone
Main material: rubble
Main material: render
Covering material: pantile

**Designating Organisation:**

---

**Location**

**Grid Reference:** ST 99698 70948 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

**DesigUID:** DWI6002 **Name:**

7 Patford Street, Calne, Wiltshire, SN11 0EF

**Listed Building Addresses**

Former Statutory
CALNE MUNICIPAL OFFICES

**Designation History**

**Assignment**
02/04/1970

**Sources - None recorded**

**Associated Monuments**

MWI36388 Building: 5 Patford Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456751

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6003 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247349 | 1247349 | 755-1, 5, 122 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/122 (East side)
08/07/76 No.7
GV II
Attached house. Mid C19. Painted brick with limestone dressings, and pantile roof. 2 storeys; 3-window front with quoins and a small eaves cornice, plain doorway and recessed 6-panel door and 3-pane overlight; tripartite ground-floor windows; 2/2-pane sashes. INTERIOR not inspected. Included for group value.
Listing NGR: ST9972170950

**Curatorial Notes**

Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Main material: brick
Main material: limestone
Covering material: pantile

**Designating Organisation:**

**DesigUID:** DWI6003 **Name:**

**Location**

**Grid Reference:** ST 99712 70949 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

7 Patford Street, Calne, Wiltshire, SN11 0EF

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI32986 Building: 7, PATFORD STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456753

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6020 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247358 | 1247358 | 755-1, 5, 143 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/143 (East side)
08/07/76 Nos.1 AND 2
GV II

Pair of attached houses. Early/mid C19. Rendered with limestone dressings, coursed rubble sides, with moulded ashlar gable stacks and a pantile roof. Double-depth plan with 2-storey lean-to to left. 3 storeys; 3:1-window range. Coped gables, quoins and plinth, No.1 double fronted with a fanlight to the doorway, No.2 has a right-hand doorway, with panelled doors. 2-light ground- and first-floor windows, single light second-floor and central window to No.1, with 6/6-pane sashes. Rear has a central 1-window range, and a left-hand narrow 2-storey lean-to. INTERIOR: details of No.2 include a right-hand stair with stick balusters and column newels.
Listing NGR: ST9993370874

**Curatorial Notes**

**DesigUID:** DWI6020 **Name:**

Type and date: Early/mid C19 HOUSE. Date: from 1800 to 1866
Main material: render
Main material: limestone
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99931 70866 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Flat 1 4 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36396 Building: 1 AND 2, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456785

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6021 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247406 | 1247406 | 755-1, 5, 144 |

**Name:**
**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/144 (East side)
19/05/50 No.3
(Formerly Listed as: THE GREEN (East side) Nos.3, 4 AND 5)
GV II
House. Late C18/early C19. Limestone ashlar, right-hand gable stack and a pantile roof. Late Georgian

**DesigUID:** DWI6021 **Name:**

style. 2 storeys; 1-window range. Cornice and parapet; right-hand doorway with 6-panel door and overlight, and late C19 horned 8/8-pane sashes. INTERIOR not inspected.
Listing NGR: ST9994170862

**Curatorial Notes**

Type and date: Late C18/early C19 HOUSE. Date: from 1767 to 1832
Main material: limestone
Main material: ashlar
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99937 70861 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

3 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36397 Building: 3, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456873

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6022 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270922 | 1270922 | 755-1, 5, 145 |

**Name:**
**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/145 (East side)

**DesigUID:** DWI6022 **Name:**

19/05/50 No.4
(Formerly Listed as: THE GREEN (East side) Nos.3, 4 AND 5)
GV II
House. Late C18/early C19. Limestone ashlar with ashlar gable stacks and a double-pile pantile roof. Late Georgian style. Double-depth plan. 3 storeys; 3-window range. A symmetrical front has pilaster strips to a modillion cornice and parapet, with a first-floor cill band, and coped end gables. Round-arched entrance has an architrave, key and impost blocks, plate-glass fanlight and 6-panel door. Ground-floor Venetian windows with 6/6-pane sashes; flat stone arches over 6/6-pane sashes to first floor, and 4/8-pane second-floor sashes. INTERIOR not inspected.
Listing NGR: ST9994670857

**Curatorial Notes**

Type and date: Late C18/early C19 HOUSE. Date: from 1767 to 1832
Main material: limestone
Main material: ashlar
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99942 70854 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Flat 1 4 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36398 Building: 4, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456874

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6023 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247407 | 1247407 | 755-1, 5, 146 |

**DesigUID:** DWI6023 **Name:**

**Name:**

**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/146 (East side)
19/05/50 No.5
(Formerly Listed as: THE GREEN (East side) Nos.3, 4 AND 5)
GV II
House. Late C18/early C19. Limestone ashlar with a pantile roof and right-hand gable stack. 3 storeys; 2-window range. Cornice and parapet, left-hand doorway with architrave and 6-panel door, 8/8-pane sashes, with 4/8-pane sashes on the second. INTERIOR not inspected.
Listing NGR: ST9995470849

**Curatorial Notes**

Type and date: Late C18/early C19 HOUSE. Date: from 1767 to 1832
Main material: limestone
Main material: ashlar
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99946 70847 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

5 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI34225 Building: 5, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456875

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6024 **Name:**

**DesigUID:** DWI6024 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247408 | 1247408 | 755-1, 5, 147 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/147 (East side)
08/07/76 No.6
(Formerly Listed as: THE GREEN (East side) Nos.6 AND 7)
GV II
House, now divided. Mid C15, altered mid C19. Limestone rubble, formerly rendered, with limestone dressings, ridge stack and stone slate roof. Single-room plan with rear extension. 2 storeys and attic; 1-window range. A right-hand doorway with 6-panel door, the bottom pair flush; C19 raised surrounds to paired plate-glass sashes. INTERIOR not inspected. Formerly part of No.7 (qv), which has a flying freehold above the rear parallel range, and a mid C15 arch-braced roof. Part of an open hall house, almost certainly originally timber-framed, and subsequently encased.
Listing NGR: ST9996870839

**Curatorial Notes**

Type and date: Mid C15 OPEN HALL HOUSE. Date: from 1433 to 1466
Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Mid C15 TIMBER FRAMED HOUSE. Date: from 1433 to 1466
Main material: limestone
Main material: rubble
Main material: render
Main material: timber
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99963 70834 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

6 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI34226 Building: 6, THE GREEN

**Associated Consultations - None**

**DesigUID:** DWI6024 **Name:**

**Additional Information**

**LBSUID:** 456877

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6025 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247409 | 1247409 | 755-1, 5, 148 |

**Name:**
**Grade:** II* **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/148 (East side)
08/07/76 No.7
GV II*
House, divided into 2. Mid C15, altered C19. Roughcast limestone rubble with brick gable stack and stone slate roof. Single-room plan with a through-passage; parallel rear range, connected by a C18 right-hand side range. 2 storeys and attic; 2-window range. A raised surround to the left-hand doorway and panelled door, ground-floor 2-light casement window, C19 two-light sashes on the first floor, with a late C16 blocked 2-light stone-mullioned window with reserved chamfers to the right. Side range has a gabled lateral stack. INTERIOR: details include a good mid C15 roof with 4 arched braced collar trusses with threaded ridge, not smoke-blackened, with wind braces to the middle register of tenoned purlins, and a framed truss with doorway and wattle and daub panels; rear range has later roof with chamfered beams, and connecting side range later still, with 2 collar trusses of c1700. The first-floor has chamfered stopped lateral beams with deep chamfers; C18 cupboard flanking ground-floor right-hand room fireplace, also panelled shutters and wainscot; early C19 stair has stick balusters and column newels with a moulded rail; a second stair between the 2 rear ranges on the right. Rear ground-floor room has a very deep axial lateral beam, and HL hinges to the door. Formerly part of No.7 (qv), as an open hall house, with through-passage. The gable has been rebuilt, and the chimney inserted. One of the earliest domestic buildings in the parish, and almost certainly originally a timber-framed building, subsequently encased.
Listing NGR: ST9997670833

**Curatorial Notes**

Type and date: Mid C15 CROSS PASSAGE HOUSE. Date: from 1433 to 1466
Type and date: C19 HOUSE. Date: from 1800 to 1899
Type and date: C18 HOUSE. Date: from 1700 to 1799
Type and date: Mid C15 OPEN HALL HOUSE. Date: from 1433 to 1466
Type and date: Mid C15 TIMBER FRAMED HOUSE. Date: from 1433 to 1466
Main material: roughcast
Main material: limestone
Main material: rubble
Covering material: stone
Main material: timber

**Designating Organisation:**

**DesigUID:** DWI6025 **Name:**

**Location**

**Grid Reference:** ST 99969 70827 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

7 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI34227 Building: 7, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456878

**List Locality:** THE GREEN

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6026 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270886 | 1270886 | 755-1, 5, 149 |

**Name:**

**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/149 (East side)
02/04/70 Nos.8 AND 9
GV II

Cloth mill, now flats. Late C18. Coursed limestone rubble with limestone dressings, ashlar gable stacks and stone slate roof. Single-depth plan. 4 storeys and attic; 5-window range. Coped gables, windows of 3 lights with raised surrounds to flat-faced stone mullions and casements with horizontal glazing bars, in groups of 2:1:2. Central and left-hand doors in raised stone surrounds. Attic visible at rear. INTERIOR not inspected. Formerly with railed front garden and wide gate, and a full-width canopy. An important example of pre-industrial cloth production in Wiltshire: 'Nowhere has the environment of the trade in pre-factory days survived better (than in the E side of the Green)' (Edington). (Wiltshire Buildings Record: Trowbridge: B316; Rogers K: Woollen Mills of Wiltshire and Somerset: Edington, Wilts: 1976-: 87).

**DesigUID:** DWI6026 **Name:**

Listing NGR: ST9999570834

**Curatorial Notes**

Type and date: Late C18 TEXTILE MILL. Date: from 1767 to 1799
Type and date: Now FLATS.
Type and date: RAILINGS.
Type and date: GATE.
Main material: limestone
Main material: rubble
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99989 70829 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Flat 1 4 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**
02/04/1970

**Sources - None recorded**

**Associated Monuments**

MWI34228 Building: 8 and 9 The Green, Calne

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456879

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6029 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270887 | 1270887 | 755-1, 6, 152 |

**Name:**
**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
SU0070 THE GREEN

**DesigUID:** DWI6029 **Name:**

755-1/6/152 (East side)
19/05/50 No.12
GV II
House. Mid C17, extended to rear and refronted in early C19. Limestone ashlar with rubble sides, slate roof, large rear external stack and rear gable stack. 2-room parallel plan, with hall/kitchen to left heated by large rear lateral stack, extended to L-plan with right-hand rear wing. 2 storeys and attic; 3-window range. Front has pilasters, cornice and parapet; right-hand doorway has a plain surround and bracketed pediment to a 6-panel door with glazed top panels. Windows have architraves to 6/6-pane sashes, with a round-arched first-floor window over the door with imposts and key to 4/4-pane sash; 2 hipped dormers with casements. Left-hand rear large external stack with gabled top. Rear range set at an angle to the front rebuilt with coursed, squared rubble to upper floors, with a first-floor 6/6-pane sash in an exposed frame. INTERIOR: remodelled in C19, details include an entrance stair hall with C20 stair, panelled doors and shutters; roof not seen.
Listing NGR: SU0001070798

**Curatorial Notes**

Type and date: Mid C17 HOUSE. Date: from 1633 to 1666
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** SU 00010 70798 (point)
**Map sheet:** SU07SW **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

12 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI34230 Building: 12, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456883

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE

**DesigUID:** DWI6029 **Name:**

**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6040 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247441 | 1247441 | 755-1, 5, 162 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/162 (West side)
08/07/76 No.23A
GV II

National school, now house. c1828, altered c1975. Stucco with limestone dressings and slate roof. T-shaped plan with central axial hall. Picturesque Tudor Gothic style. Single storey; 3-window range. Coped end and projecting central gables with moulded kneelers; left-hand segmental-arched doorway with label mould and ridge door. To the right a 2-light Tudor-arched window with label mould, and similar 3-light window to the right-hand section; central gable has a small niche containing a figure, over a tall 3-light, 2-centre-arched window with hood mould and intersecting tracery; on side returns are 2-centre arched niches with hood and head stops; 2 inserted late C20 gabled dormers. INTERIOR altered.
Listing NGR: ST9990870776

**Curatorial Notes**

Type and date: c1828 NATIONAL SCHOOL. Date: from 1808 to 1848
Type and date: c1975 HOUSE. Date: from 1965 to 1985
Main material: stucco
Main material: limestone
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99908 70776 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

A 23 The Green, Calne, Wiltshire, SN11 8DJ

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI34241 Building: 23A, THE GREEN

**DesigUID:** DWI6040 **Name:**

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456917

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6041 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247463 | 1247463 | 755-1, 5, 163 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/163 (West side)
08/07/76 Nos.24 AND 25
GV II
Pair of attached houses. Early C19. Painted squared, coursed limestone rubble with central brick ridge stack and slate roof. Double-depth plan. Each of 2 storeys; 2-window range. Outer flat-headed doorways contain 6-panel doors, No.24 with a 3-pane overlight. 8/8-pane sashes, with 2 on the ground floor, that beside the door of No.25 a 6/6-pane sash. INTERIOR: No.25 altered; No.24 not inspected.
Listing NGR: ST9990670783

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99905 70787 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Flat 1 4 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**
08/07/1976

**DesigUID:** DWI6041 **Name:**

**Sources - None recorded**

**Associated Monuments**

MWI32988 Building: 24 AND 25, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456948

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6042 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270880 | 1270880 | 755-1, 5, 164 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/164 (North side)
08/07/76 No.28
(Formerly Listed as: THE GREEN (North side) Nos.28 AND 29)
GV II
House. Late C18, altered late C20. Painted limestone rubble with brick gable stack and stone slate roof. Single-depth plan. 2 storeys; 2-window range. Coped left-hand gable, a central recessed late C20 door, right-hand boarded door, and late C20 casements with timber lintels. INTERIOR not inspected. Included for group value.
Listing NGR: ST9990970817

**Curatorial Notes**

Type and date: Late C18 HOUSE. Date: from 1767 to 1799
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Main material: limestone
Main material: rubble
Covering material: stone

**Designating Organisation:**

---

**Location**

**Grid Reference:** ST 99905 70815 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

28 The Green, Calne, Wiltshire, SN11 8DJ

**DesigUID:** DWI6042 **Name:**

**Designation History**

Assignment
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI34242 Building: 28, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456949

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6043 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247464 | 1247464 | 755-1, 5, 165 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/165 (North side)
08/07/76 No.29
(Formerly Listed as: THE GREEN (North side) Nos.28 AND 29)
GV II
House. Mid C18. Painted limestone ashlar, brick left-hand gable and central ridge stack and stone slate roof. Lobby-entry single-depth 2-room plan. 2 storeys and attic; 2-window range. Double-fronted with an ashlar surround to the panelled door with a bracketed timber canopy, timber lintels to mid C19 plate-glass sashes with margin panes; 2 gabled dormers. INTERIOR not inspected.
Listing NGR: ST9991870817

**Curatorial Notes**

Type and date: Mid C18 HOUSE. Date: from 1733 to 1766
Main material: limestone
Main material: ashlar
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99913 70817 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

**DesigUID:** DWI6043 **Name:**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

29 The Green, Calne, Wiltshire, SN11 8DJ

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI34243 Building: 29, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456950

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6044 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270881 | 1270881 | 755-1, 5, 166 |

**Name:**

**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/166 (North side)
19/05/50 No.30
GV II
House, formerly 2 dwellings. Early C19. Stucco with limestone dressings, brick gable stacks and slate roof. Double-depth plan, with rear wing remodelled in later C19. 2 storeys and attic; 3-window range. Double-fronted with quoins, frieze, cornice and parapet, with coped gables. Roman Doric attached pedimented porch to a recessed panelled door; 6/6-pane sashes, paired to the outside. 2 gabled dormers. Right-hand return a 3-window range, of rubble with altered openings, a left-hand doorway with bracketed pediment, and horned 2/2-pane sashes, paired to the right. INTERIOR not inspected.
Listing NGR: ST9992870826

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Later C19 HOUSE. Date: from 1833 to 1899
Main material: stucco
Main material: limestone
Covering material: slate

**DesigUID:** DWI6044 **Name:**

Main material: rubble

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99925 70825 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

30 The Green, Calne, Wiltshire, SN11 8DJ

**Designation History**

**Assignment**

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI34244 Building: 30, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456951

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6045 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247465 | 1247465 | 755-1, 5, 167 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/167 (North side)
08/07/76 Nos.31 AND 32
GV II

Pair of attached houses. Early C19. Painted limestone ashlar, brick ridge stack and slate roof. Double-depth plan. 2 storeys and attic; 1:2-window range. Left-hand and right-hand round-arched doorways with 3-pane overlights and 6-panel doors; an elliptical-arched carriageway to the right; 8/8-pane sashes. Left-hand mid C20 gabled casement dormer. INTERIOR not inspected.
Listing NGR: ST9992770836

**Curatorial Notes**

**DesigUID:** DWI6045 **Name:**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99923 70837 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Flat 1 4 The Green, Calne, Wiltshire, SN11 8DG

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI34245 Building: 31 AND 32, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456952

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6046 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247466 | 1247466 | 755-1, 5, 168 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/168 (North side)
08/07/76 No.33
GV II
House, converted into public house in C19, now house again. Late C17, altered early C18. Limestone rubble, squared, coursed limestone first floor, gable stacks and pantile roof. Double-depth plan. 2 storeys; 5-window range. Coved plaster cornice; timber lintels to a left-of-centre doorway with 6-panel

door, the top pair glazed, 3-light mid/late C19 ground-floor windows each side with plate-glass sashes, and a blocked right-hand window. 5 evenly-spaced first-floor 2-light stone-mullioned windows with cyma-moulded surrounds and late C19/C20 horizontal glazing bar casements. Formerly with a mid C19 shop window at left-hand end, described in 1976 list description. INTERIOR not inspected.
Listing NGR: ST9991970848

**Curatorial Notes**

Type and date: Late C17 HOUSE. Date: from 1667 to 1699
Type and date: Early C18 HOUSE. Date: from 1700 to 1732
Type and date: C19 PUBLIC HOUSE. Date: from 1800 to 1899
Type and date: Now HOUSE.
Type and date: Mid C19 SHOP. Date: from 1833 to 1866
Main material: limestone
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99921 70850 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

33 The Green, Calne, Wiltshire, SN11 8DJ

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36462 Building: 33, THE GREEN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456953

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6050 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247468 | 1247468 | 755-1, 4, 173 |

**Name:**

**DesigUID:** DWI6050 **Name:**

**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 THE PIPPIN
755-1/4/173 (East side) Nos.17 AND 19
II
Farmhouse, now 2 dwellings. Late C17. Limestone rubble with double-Roman pantile roof and large ridge stack to left of door. 2-unit central through-passage plan with rear right wing connected at the corner and gabled at both ends. No.17 to the left occupies the left half of the front range, No.19 the rest. 2 storeys with attics; symmetrical 2-window range. C19 three-light casement windows at eaves level to the first floor, 3-light windows with central sliding sash to the ground floor; C20 dormer to No.17. INTERIOR: the stack to the open fire (which has a Tudor-arched oak lintel) of No.17 backs onto passage; a chamfered axial beam has heart-shaped stops. To front right corner an early C18 wood-lined recess with shaped shelves and simple shell-type coving. First floor, once one room, now divided, has a quartered ceiling of various chamfers and stops and a crude joint to centre, possibly re-used timber, and an exposed pegged boxframe to right gable end. The 2-bay attic has boxed-in rafters and purlins.
Listing NGR: ST9996671236

**Curatorial Notes**

Type and date: Late C17 FARMHOUSE. Date: from 1667 to 1699
Type and date: Late C17 CROSS PASSAGE HOUSE. Date: from 1667 to 1699
Type and date: Late C17 TIMBER FRAMED HOUSE. Date: from 1667 to 1699
Type and date: Now HOUSE.
Main material: limestone
Main material: rubble
Main material: timber
Covering material: roman tile
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99966 71236 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

61 The Pippin, Calne, Wiltshire, SN11 8JG

**Designation History**

**Assignment**

22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI36465 Building: 17 AND 19, THE PIPPIN

**Associated Consultations - None**

**Additional Information**

**DesigUID:** DWI6050 **Name:**

**LBSUID:** 456957

**List Locality:** THE PIPPIN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6051 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270865 | 1270865 | 755-1, 4, 174 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 THE PIPPIN
755-1/4/174 (East side)
08/07/76 Nos.55 AND 57
II
House, now two dwellings. Late C17 or early C18. Limestone rubble with steeply-pitched roof, recently slated, originally thatched, brick stacks to gable ends. Each cottage now single-unit plan with flying freehold of No.55 to the left which is 2-window range, over part of No.57 which is one-window range. 2 storeys. Timber lintels and first-floor windows are at eaves level. The entrance to No.55 is in the left return where some timber insertions at the corners sneck up the rubblestone; the door opening to the right has been narrowed to accommodate a C19 planked door with an iron knocker: to the left of the door, the whole gable end is a projecting stack slightly corbelled out at first-floor level where there is a 2-light C18 leaded casement window with C20 glass. The west facade of No.55, facing The Pippin, has two C19 two-light casement windows without glazing bars to each floor and a vertical joint between them, implying that No.57 was once symmetrical. No.57 has a C20 door to the left and a C20 two-light casement window to each floor, a half submerged basement window remains. INTERIOR of No.55: the room to the ground floor is stone-flagged with an open fire to the rear left corner, a studded wall to the right and a chamfered crossbeam with slots and holes, probably re-used. The C20 staircase has been repositioned, the first floor has elm boards and 2 partly exposed pegged A-frame trusses.
Listing NGR: ST9996371088

**Curatorial Notes**

Type and date: Late C17 or early C18 HOUSE. Date: from 1667 to 1732
Main material: limestone
Main material: rubble
Main material: stone
Covering material: slate
Covering material: thatch

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99963 71088 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

**DesigUID:** DWI6051 **Name:**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

61 The Pippin, Calne, Wiltshire, SN11 8JG

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36466 Building: 55 AND 57, THE PIPPIN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456991

**List Locality:** THE PIPPIN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6052 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247492 | 1247492 | 755-1, 4, 175 |

**Name:**

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 THE PIPPIN
755-1/4/175 (East side)
08/07/76 No.61
GV II

Marked on OS as No.59. House. C17, remodelled mid/late C19. Course, squared limestone rubble with large ashlar gable stacks and slate roof. 2-room central-entry plan. 2 storeys and attic; 2-window range. Late C19 timber gabled porch; 3-light windows with cambered heads and casements, and 2 gabled casement dormers. Squared stone to centre around and above doorway, and to left-hand gable. Diagonally-set flues to stacks with weathered coping, external stack to right being large and heavily built. INTERIOR: reported to have a central stair, and 3 large roof trusses with tenoned purlins. HISTORICAL NOTE: built on the site of C16 workhouse, and possibly incorporates some earlier stonework in the right-hand gable.
Listing NGR: ST9996571067

**Curatorial Notes**

Type and date: C17 HOUSE. Date: from 1600 to 1699
Type and date: Mid/late C19 HOUSE. Date: from 1833 to 1899
Main material: limestone

**DesigUID:** DWI6052 **Name:**

Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99965 71067 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

61 The Pippin, Calne, Wiltshire, SN11 8JG

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36467 Building: 61, THE PIPPIN

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456992

**List Locality:** THE PIPPIN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6058 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247535 | 1247535 | 755-1, 4, 181 |

**Name:**
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 WOOD STREET
755-1/4/181 (East side)
08/07/76 No.5
GV II
House, now shop and offices. Early/mid C19, altered c1980. Limestone ashlar with truncated end stacks and slate hipped roof. Double-depth plan. 3 storeys; 3-window range. A symmetrical front has shop front with late C20 glazing bars and an ashlar plinth that curves in to a central recessed doorway; plain eaves band. Central first-floor window blocked, others have 8/8-pane and second-floor 4/8-pane sashes with thin bars. INTERIOR completely remodelled late C20.

**DesigUID:** DWI6058 **Name:**

Listing NGR: ST9975071198

**Curatorial Notes**

Type and date: Early/mid C19 HOUSE. Date: from 1800 to 1866
Type and date: Now SHOP.
Type and date: Now OFFICE.
Type and date: c1980 HOUSE. Date: from 1970 to 1990
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99743 71199 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

5 Wood Street, Calne, Wiltshire, SN11 0BZ

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36472 Building: 5, WOOD STREET

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 457098

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6030 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247413 | 1247413 | 755-1, 6, 153 |

**Name:** ADAM HOUSE
**Grade:** II* **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
SU0070 THE GREEN

**DesigUID:** DWI6030 **Name:** ADAM HOUSE

755-1/6/153 (North side)
19/05/50 No.13 Adam House
(Formerly Listed as: THE GREEN (East side) Adam House)
GV II*
Formerly known as: Nos.13 AND 13A THE GREEN. House. C17, refronted c1740, some C19 and C20 interior and rear additions. Limestone ashlar front, coursed rubblestone to the rear, stone slate roof with coped gables and moulded stacks to gable ends. L-shaped plan with central stairhall plan to front block and older rear left wing. 2 storeys with attic and basement; symmetrical 5-window range. Pilaster strips to quoins, cornice and parapet ramped up in centre with pineapple finials; ground-floor cill string; paired 6/6-pane sash windows in raised architraves flank a Venetian window over the 6-panel door. This, flanked by C19 leaded stained-glass windows, is set in a moulded architrave, all under a bracketed pediment. INTERIOR: room to right has early/mid C18 full-height panelling, a narrow box cornice, raised-and-fielded panelled shutters and a late C19 black marble fireplace and grate. C19 polychromatic tile floor to the central hall; to rear right of the hall an early C18 open-well, closed string oak staircase with turned balusters, swept rails and elm treads and painted raised-and-fielded pine panelling below the dado of the stairwell. To left of the stairs steps lead down to C17 rear wing where the floor is approx 1m lower than the hall; it has an ogee-moulded beam with run-out stops and a former exterior wall to right (now enclosed by C20 passage) has a 4-light ovolo-mullioned leaded window. The room to the end of this wing, slightly larger, has a former open fire with a repositioned lower bressumer against the left wall. A semi-elliptical vaulted basement extends forward under the C18 house; between this and the present kitchen are 2 cavities approx 1m high and 2.5m long. The first floor has some C18 hob grates to the front, the roof structure of the rear wing is of reused timbers, one being an inverted C17 moulded beam with roll-stop chamfers on the upper edge. HISTORICAL NOTE: photographs taken during replastering of the interior show rubblestone relieving arches spanning the floor levels of the C17 building. Adam House is said by Lord Shelbourne of Bowood House (qv) to be named after Robert Adam, architect, who worked on Bowood House and is said to have lived here.
Listing NGR: SU0002370794

**Curatorial Notes**

Type and date: C17 HOUSE. Date: from 1600 to 1699
Type and date: c1740 HOUSE. Date: from 1720 to 1760
Type and date: C19 HOUSE. Date: from 1800 to 1899
Type and date: C20 HOUSE. Date: from 1900 to 1999
Main material: limestone
Main material: ashlar
Main material: rubble
Main material: stone
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** SU 00023 70794 (point)
**Map sheet:** SU07SW **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 The Green, Calne, Wiltshire, SN11 8DG

**Listed Building Addresses**

Statutory
ADAM HOUSE

**DesigUID:** DWI6030 **Name:** ADAM HOUSE

Alternative
ADAM HOUSE
Former Statutory
ADAM HOUSE

**Designation History**

Assignment
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI34231 Building: ADAM HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456884

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6054 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247494 | 1247494 | 755-1, 5, 179 |

**Name:** BARCLAYS BANK AND THE OLD BANK HOUSE
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE STRAND
755-1/5/179 (East side)
08/07/76 Barclays Bank, The Old Bank House
(Formerly Listed as: THE STRAND (East side) The Old Bank House (Barclays Bank and Harris's Offices))
GV II
Office. Dated 1901. Squared, coursed limestone, ashlar lateral stacks, slate hipped roof. Jacobean Revival Free style. Single-depth plan with lower S range. 2 storeys; 3-window range. Plinth, cornice and tall parapet; projecting gabled wing has a right-hand entrance with bracketed canopy and curved dwarf wall with ball finials, a round-arched ground-floor window, and 6-light mullion and transom ovolo-moulded first-floor window; escutcheon in the gable dated 1901. Bay flanked by similar first-floor 2-light windows at each end. A large prostyle Ionic porch in the left-hand re-entrant, with a round-arched entrance and steps up to a panelled door. Left-hand return has 3 ground-floor round-arched windows, and 2:4:2 first-floor cross windows, and a small pediment with inscribed panel. Large rear stair light with stained glass. INTERIOR: details include a rear stair with uncut string, moulded rail, square newels and ball finials; panelled doors and round-arched openings.

**DesigUID:** DWI6054 **Name:** BARCLAYS BANK AND THE OLD BANK HOUSE

Listing NGR: ST9977970995

**Curatorial Notes**

Type and date: 1901 OFFICE. Date: 1901
Type and date: 1901 DATE STONE. Date: 1901
Type and date: STEPS.
Type and date: BANK (FINANCIAL).
Main material: limestone
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99776 70991 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

The Old Bank House The Strand, Calne, Wiltshire, SN11 0EN

**Listed Building Addresses**

Statutory
BARCLAYS BANK
Statutory
THE OLD BANK HOUSE
Former Statutory
BARCLAYS BANK
Former Statutory
HARRIS'S OFFICES
Former Statutory
THE OLD BANK HOUSE

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36469 Building: Barclays Bank
THE OLD BANK HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456994

**List Locality:** THE STRAND
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE

**DesigUID:** DWI6054 **Name:** BARCLAYS BANK AND THE OLD BANK HOUSE

**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5910 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271361 | 1271361 | 755-1, 5, 23 |

**Name:** BENTLEY HOUSE

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/23 (West side)
08/07/76 Nos.15 AND 17 Bentley House (No.17)
GV II
Pair of houses, now offices. Early C19, restored and altered late C20. Limestone ashlar with brick stacks and slate roof. Double-depth plan. Each of 3 storeys; symmetrical 3-window range. Each double-fronted with first-floor cill band and parapet, round-arched doorways with plate-glass fanlights and 6-panel doors; flanking Venetian windows, and a right-hand late C19 shop front with panelled jambs and bracketed cornice. 6/6-pane sashes, second-floor 3/6-pane sashes. INTERIOR altered. Formerly with C20 shop windows.
Listing NGR: ST9984970943

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Now OFFICE.
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Type and date: Late C19 SHOP. Date: from 1867 to 1899
Type and date: C20 SHOP. Date: from 1900 to 1999
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99848 70939 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

15 Church Street, Calne, Wiltshire, SN11 0HY
15 Church Street, Calne, Wiltshire, SN11 0HY
17 Church Street, Calne, Wiltshire, SN11 0HY

**Listed Building Addresses**

Statutory
BENTLEY HOUSE
Former Statutory
BENTLEY HOUSE

**DesigUID:** DWI5910 **Name:** BENTLEY HOUSE

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**
MWI36403 Building: BENTLEY HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455101

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5983 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247331 | 1247331 | 755-1, 4, 99 |

**Name:** CALNE FREE CHURCH
**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**
CALNE
ST9971 CHURCH STREET
755-1/4/99 (North side) Calne Free Church
GV II
Church. 1867. By W Stent of Warminster. Squared, rusticated limestone with ashlar dressings and quoins, crested plain tile roof. Rectangular plan with bell tower to the front left (NW); north aisle with higher north transept extending to the line of the aisle (no south aisle) and angled buttresses. Gothic Revival Middle Pointed style. The front gable end has a cinquefoil opening to the apex over a large pointed-arched, casement-moulded, 4-light window with foliate capitals to shafts and geometrical tracery. The planked doors with decorative hinges are set in a pointed-arched doorway with hollow-moulded stops springing from low offset buttresses, the intrados has soft red stone colonnettes with floral caps and plinths. The bell tower has a quatrefoiled parapet with dragon gargoyles; the 2-light bell opening has floral stops to the hoodmould, quatrefoil and trefoil tracery and scallop-edged slate louvres. A string course over a single-light pointed-arched window with similar tracery is above a smaller door than the main one, similar but with a stilted arch. The left return has a 2-light window to the tower, and the north aisle which projects to the same line has 3 paired trefoil-headed windows to the clerestory. The gabled north transept has a 3-light pointed-arched window without a hoodmould; the tall hipped square stair turret has circular windows and a timber porch to a pointed-arched door. To the rear the semicircular apse and curved hipped roof has a moulded eaves cornice, 5 pointed-arched windows and cill string. The right return is obscured by other premises, not included. INTERIOR: modest and virtually unchanged. 10-bay scissor-braced planked roof over clerestorey of paired coloured leaded windows; the north aisle is separated by an arcade of 4 Transitional-style round piers supporting pointed arches, smaller to the west end giving access to the belltower and

larger to the north-east transept. The arch to the apse is supported by colonnettes on high corbels. The apse has small polychromatic tiles to the floor and a dado approx 2m high of brown glazed geometrical relief-pattern tiles below 5 tall delicate geometrical-design stained-glass windows. These are flanked by panels of glazed tiles painted with mottos on scrolls around olive branches, after the style of William Morris. The glass of the west window is similar to that of the apse. The original painted organ, pinewood pews and pulpit remain. An unusually complete interior. HISTORICAL NOTE: the church was built under the patronage of the Harris family (local wholesale butchers). (The Buildings of England: Pevsner N & Cherry B: Wiltshire:
London: 1975-: 154).
Listing NGR: ST9985671018

**Curatorial Notes**

Type and date: 1867 CHURCH. Date: 1867
Type and date: Now NONCONFORMIST CHAPEL.
Main material: limestone
Main material: ashlar
Covering material: tile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99856 71018 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory
CALNE FREE CHURCH
Former Statutory
CALNE FREE CHURCH

**Designation History**

**Assignment**
22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI36371 Building: Calne Free Church, Church Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456696

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5983 **Name:** CALNE FREE CHURCH

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5980 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247321 | 1247321 | 755-1, 5, 100 |

**Name:** CALNE MILL
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 MILL STREET
755-1/5/100 (North West side)
08/07/76 No.9 Calne Mill
(Formerly Listed as: MILL STREET (North side) No.8 Mill House)
II
Cloth mill. 1858, closed 1866, converted c1980. Squared, coursed limestone, slate half-hipped roof. Open plan. 2 storeys and attic; 4-window range. Evenly-spaced segmental-arched windows, with a doorway one bay from the left to a lobby and late C20 door, and late C20 casements with leaded lights. 4 gabled half dormers. Right-hand return has 2 round-arched first-floor windows with glazing bars, and a former hoist door beneath the half hip. INTERIOR: reported to have a stone stair; extensively altered. HISTORICAL NOTE: formerly water-powered, the wheel pit is at the E end of the building. Forms a group with No.8 Pond Cottage (qv), the former miller's house, and the former millworkers' cottages at Nos 14-20 Mill Street (qv). (Rogers K: Woollen Mills of Wiltshire and Somerset: Edington, Wilts: 1976-).
Listing NGR: ST9997170970

**Curatorial Notes**

Type and date: 1858 TEXTILE MILL. Date: 1858
Type and date: c1980 BUILDING. Date: from 1970 to 1990
Main material: limestone
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99967 70967 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

9 Mill Street, Calne, Wiltshire, SN11 8DP

**Listed Building Addresses**

Statutory
CALNE MILL
Former Statutory
MILL HOUSE

**Designation History**

**DesigUID:** DWI5980 **Name:** CALNE MILL

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**
MWI36368 Building: CALNE MILL

**Associated Consultations - None**

**Additional Information**
**LBSUID:** 456693

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI16518 **Type:** Listed Building **Status:** Active
**NHLE number** **NHLE number** **Volume/Map/Item**
1438174 1438174
**Name:** Calne War Memorial
**Grade:** II **Assigned:** 22/08/2016 **Amended:** **Revoked:**

**Legal Description**
First World War memorial dating from circa 1920, altered following the Second World War.
MATERIALS: The memorial is constructed from Portland stone.
DESCRIPTION: The memorial takes the form of the Cross of Sacrifice designed by Sir Reginald Blomfield in 1918. It is a tall, Latin cross with a bronze downward facing sword affixed to the tapering octagonal shaft, which is set into an octagonal plinth. The plinth rests upon a base with a capping stone; and the whole stands on three octagonal steps, surrounded by paving. The principle dedicatory inscription on the front face of the plinth reads IN GRATEFUL/ AND/ ABIDING REMEMBRANCE/ OF THE MEN/ WHO WENT FROM THE/ PARISH OF CALNE/ TO THE/ GREAT WAR/1914 - 1918/ AND GAVE THEIR LIVES/ IN THE CAUSE OF/ FREEDOM AND RIGHT. The other sides of the plinth are inscribed with the names of the fallen from the First World War. The front face of the base bears the inscription ALSO/ IN MEMORY OF THOSE/ WHO GAVE THEIR LIVES/IN THE WAR OF/ 1939 - 1945. The names of the fallen from the Second World War are recorded on the remaining faces of the base.

**Curatorial Notes**
First World War memorial dating from circa 1920, altered following the Second World War.

**Designating Organisation:** Department of Culture, Media and Sport

**Location**
**Grid Reference:** Centred ST 9986 7088 (1m by 2m)
**Map sheet:** ST97SE **Area (Ha):** 1.96
**Administrative Areas**
Civil Parish Calne, North Wiltshire, Wiltshire
**Postal Addresses**
Churchyard of the Church of St Mary, Church Street, Calne, Wiltshire, SN11 0HU

**DesigUID:** DWI16518 **Name:** Calne War Memorial

**Listed Building Addresses**

Statutory

Calne War Memorial, Churchyard of the Church of St Mary, Church Street, Calne, Wiltshire, SN11 0HU

**Designation History**

**Assignment**

22/08/2016

**Sources - None recorded**

**Associated Monuments**

MWI74851 Building: Calne War Memorial

**Associated Consultations - None**

**Additional Information**

**LBSUID:**

**List Locality:**
**List Parish:**
**List District:**
**List County:**
**Group Value:** **Upload Date:**

---

**DesigUID:** DWI5929 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246444 | 1246444 | 755-1, 5, 44 |

**Name:** CHEST TOMB APPROXIMATELY 7 METRES FROM NORTH WEST CORNER OF CHURCH OF ST MARY

**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/44 (East side) Chest tomb approx 7 metres from north-west corner of Church of St Mary
GV II
Chest tomb. Late C17. Limestone. Narrow rectangular plan. A large flat slab to the top has a scroll frieze below the entablature, and articulated by Tuscan half-columns to each elevation; the long sides also have a central pilaster articulating wide shields with worn cherubs' heads in the lower corners of the panels. The narrow ends have a skull and crossbones to the south-facing panel and a skull over a worn cartouche to the north. An interesting classical design.
Listing NGR: ST9986870920

**Curatorial Notes**

Type and date: Late C17 CHEST TOMB. Date: from 1667 to 1699
Main material: limestone

**Designating Organisation:**

**DesigUID:** DWI5929 **Name:** CHEST TOMB APPROXIMATELY 7 METRES FROM NORTH WEST

**Location**

**Grid Reference:** ST 99873 70914 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory

CHEST TOMB APPROXIMATELY 7 METRES FROM NORTH WEST CORNER OF CHURCH OF ST MARY

**Designation History**

**Assignment**

22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI32982 Building: CHEST TOMB APPROXIMATELY 7 METRES FROM NORTH WEST CORNER OF CHURCH OF ST MARY

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455167

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5919 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1246438 | 1246438 | 755-1, 5, 32 |

**Name:** CHURCH HOUSE

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/32 (East side)
08/07/76 No.30 Church House
(Formerly Listed as: CHURCH STREET (East side) Nos.28 AND 30)
GV II
House, now hall and office. C17, refronted c1720, part of attic removed and re-roofed mid C19 to form first-floor hall. Limestone rubble and ashlar dressings, ashlar gable stacks and slate roof. Double-

depth plan. 2 storeys and attic; 3-window range. Coped gables with moulded kneelers. Central doorway with dressed surround and bracketed flat canopy, ashlar plinth, with squared, coursed rubble to upper wall. 6-panel door with 3-pane overlight. Raised ashlar surround to square ground-floor windows, blocked to the left, a 6-pane window to the right, and tall C18 6/9-pane sashes with thick bars. Left-hand gable has an ashlar plinth, blocked central doorway with ashlar jambs, traces of former steeper roof; timber lintels to paired ground-floor horned 4/4-pane sashes, flush first-floor 6/6-pane sashes in exposed frames, and a small attic casement. INTERIOR: details include on the ground-floor a C17 left-hand front dogleg stair with oak risers and treads which rises around internal wall, 4 heavy chamfered and stopped axial beams and a large right-hand fireplace with bressumer; first floor has original left-hand bays with axial and lateral ceiling beams with 3-inch chamfers and run out stops, and early C19 small rear dogleg stair with stick balusters to the attic, which has a collar truss 3-bay roof; longer left- hand section has a C19 king post roof with tusked purlins over full-height hall. The unusual plan form with a large first-floor hall suggests that this was used, at least from the C18, as a parish meeting room.
Listing NGR: ST9987970954

**Curatorial Notes**

Type and date: C17 HOUSE. Date: from 1600 to 1699
Type and date: c1720 HOUSE. Date: from 1700 to 1740
Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: From C18 MEETING HALL. Date: from 1700
Type and date: Now OFFICE.
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99874 70952 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

St Marys Church House 30 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory
CHURCH HOUSE

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36412 Building: CHURCH HOUSE

**Associated Consultations - None**

**Additional Information**

**DesigUID:** DWI5919 **Name:** CHURCH HOUSE

**LBSUID:** 455157

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5927 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271365 | 1271365 | 755-1, 5, 41 |

**Name:** CHURCH OF ST MARY
**Grade:** I **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/41 (East side)
19/05/50 Church of St Mary
GV I

Church. c1160-70 nave, late C14 St Edmund's N chapel, c1470 N porch, late C15 clerestory and nave roof; tower, chancel and crossing rebuilt c1638; W end, S porch, chapel and S transept rebuilt 1864; restored 1864 by Slater. Limestone ashlar and rubble, stone slate and lead roof. Norman nave, Perpendicular the rest, except for C17 Gothic Survival tower and chancel, and C19 Perpendicular Gothic Revival S porch, chapel and restoration work. PLAN: cruciform plan with an aisled nave, N and S porches and chapels, N transept tower, and chancel with N chapel and vestry and S chapel. EXTERIOR: rubble chancel has angle buttresses, plinth and low parapet, with a C19 four-centre arched 5-light window, with 2-light C17 mullion windows in each side with labels; side chapels have 3-light E windows, and the mid C19 NE vestry has a crenellated parapet and 2-centre arched N doorway. N elevation of N chapel has two 3-light flat-headed windows with labels. 4-stage tower has setback buttresses with attached pinnacles on the offsets, deeply moulded plinth and a crenellated parapet with corner pinnacles; 3-centre arched N door with original plank and batten door and hood, with a 3-light window above with intersecting tracery; 2-light Y-tracery windows, paired to the belfry, the E side has blind second-stage window and a clock to the third stage in a lozenge moulding. Nave, aisles and porches have cornices and moulded crenellated parapets with corner crocketed pinnacles, the nave with a continuous moulding and pinnacles to attached buttresses between the windows. 2-bay St Edmund's Chapel divided by buttresses with 2-light trefoil-headed windows, and a small doorway across the angle with the tower; 2 gargoyles to the cornice. Gabled N porch has a 2-centre arched doorway with hood mould and cusped octagonal stops; inside a good lierne vault with foliate bosses, timber boss to the pendant, church doorway with hollow moulded surround and shield hood stops, smaller similar entrance to N chapel. 2-bay aisle has wide 3-light flat-headed windows and 4-centre arched 3-light W window. 5-bay clerestory has 3-light windows. Gabled W end has a C19 5-light window similar to the E end, with a canopied statue niche in the gable above, and a C17 two-centre arched doorway in a label with shields in the spandrels, and a ribbed 2-leaf door. S aisle and clerestory as the N. C19 S porch has attached columns with moulded capitals, and 3 good C15 gargoyles to the E side; 2-bay S chapel, and gabled S transept with setback buttresses and a 2-centre arched window. Ashlar S chancel chapel with 2 flat-headed 3-light C17 windows. INTERIOR: details include chancel with C17 timber roof with moulded ties, arch braced to corbels; C19 piscina and sedilia with attached pinnacles; 2-bay open sides have Tuscan columns and responds to the chancel arch, to round arches, responds to 4-centre chapel W arches and crossing. Nave has mid C12 Transitional arcade with round columns, mid C17 rebuilt wide flat shafts with responds at E end, with scallop

capitals and square bases, the E arches 2-centred, the rest have round arches with a single step, with nail-head hood moulds. Five C12 columns to N side, the first from the E with a carved corner head to the capital, some with beads to the scallops, and billet hood moulds; W responds, 2 of the S columns rebuilt C19. C12, probably reset, 2-centre arch to N porch door with chevron moulding and billet mould. Good shallow C15 tie beam roof with alternate king posts on king and bishop head corbels, and Perpendicular tracery, and plain ties with cresting on the principal rafter. FITTINGS: fine chest dated 1579, inscribed on inside of lid QER/XXI, with 3 early C17 locks, set within a large oak trunk; C15 octagonal font with curved base, and panelled sides with quatrefoil heads; in the S chapel, a reset C15 piscina with cinquefoil head; C19 pulpit with the 12 Apostles to the sides; 1890 reredos by Pearson, lowered 1936; organ case and altar in S chapel designed by CR Ashbee, made by Alec Miller of the Campden Guild in 1907. Mid C19 bench pews. MONUMENTS: wall tablet to William Norborne, d.1659; wall tablet to Benedict John Angell, d.1836; reset in the S porch, 3 wall tablets to Boswell, King of the Gipsies, with a central horse relief. HISTORICAL NOTE: the former crossing tower and spire fell in 1638, destroying the chancel, and was rebuilt over the N transept: it is a notable example of Gothic Survival work. Inigo Jones is anecdotally associated with this phase, and reported to have surveyed the old tower in c1640. (The Buildings of England: Pevsner N & Cherry B: Wiltshire: London: 1963-1975: 154; Marsh AEW: History of the Borough and Town of Calne: 1903-: 150).
Listing NGR: ST9990670913

**Curatorial Notes**

Type and date: c1160-70 CHURCH. Date: from 1160 to 1170
Type and date: Late C14 CHURCH. Date: from 1367 to 1399
Type and date: c1470 CHURCH. Date: from 1450 to 1490
Type and date: Late C15 CHURCH. Date: from 1467 to 1499
Type and date: c1638 CHURCH. Date: from 1618 to 1658
Type and date: 1864 CHURCH. Date: 1864
Type and date: Mid C19 CHURCH. Date: from 1833 to 1866
Type and date: 1659 PLAQUE. Date: 1659
Type and date: 1836 PLAQUE. Date: 1836
Type and date: 1638 CHURCH. Date: 1638
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: stone
Covering material: lead

**Designating Organisation:**

**Location**

**Grid Reference:** Centred ST 99899 70904 (41m by 29m)
**Map sheet:** ST97SE **Area (Ha):** 809.49

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory
CHURCH OF ST MARY

**Designation History**

**Assignment**

**DesigUID:** DWI5927 **Name:** CHURCH OF ST MARY

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36420 Building: Church of St Mary

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455165

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5985 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247323 | 1247323 | 755-1, 6, 102 |

**Name:** COACH HOUSE, GAZEBO, GATE PIERS AND GARDEN WALLS TO THE VICARAGE

**Grade:** II **Assigned:** 20/02/1975 **Amended:** **Revoked:**

**Legal Description**

CALNE
SU0072 MILL STREET
755-1/6/102 (North side)
20/02/75 Coach house, gazebo, gate piers and garden walls to The Vicarage
(Formerly Listed as: MILL STREET (North side) Gazebo in Vicarage garden)
GV II
Coach house, gazebo and walls surrounding the garden to The Vicarage. C18 and early C19. Limestone rubble walls. The gazebo stands at the north-east corner of the garden. The gazebo is of coursed rubble with a pyramidal stone slate roof and ball finial. 2 storeys; one-window range to each elevation. The first-floor windows have been restored with 4 rows of 4 small panes and the cills raised to their former height, the small lower windows are missing. The wall to right of the gazebo is approx 4m high and 45m long with various blocked openings. The wall to left, in The Glebe, is approx 3m high and 70m long with various blocked openings, 2 later brick buttresses to the right and a semicircular rubblestone wellhead, probably later, against the left end. The coach-house entrance, at the south-east corner with The Glebe and Mill Street, has tall ashlar gate piers; to the left of it the wall, approx 3m high, sweeps down along Mill Street for approx 75m and in the centre is a semi-elliptical stone archway over a C20 gate. C20 brick piers and gates to the south-west corner are attached to the west part of the wall which is of rubblestone, ashlar and concrete repairs, approx 1.5m high and approx 45m long and which runs alongside a brook. The coach house is a 2-storey early C19 building of coursed limestone rubble with a hipped Welsh slate roof; semicircular arched doorways and lunette windows to 6-window front. INTERIOR not inspected.
Listing NGR: SU0005770978

**Curatorial Notes**

Type and date: Early C19 COACH HOUSE. Date: from 1800 to 1832

**DesigUID:** DWI5985 **Name:** COACH HOUSE, GAZEBO, GATE PIERS AND GARDEN WALLS TO

Type and date: Early C19 GAZEBO. Date: from 1800 to 1832
Type and date: C18 GAZEBO. Date: from 1700 to 1799
Type and date: C18 WALL. Date: from 1700 to 1799
Type and date: Early C19 WALL. Date: from 1800 to 1832
Type and date: Early C19 GARDEN. Date: from 1800 to 1832
Type and date: C18 GARDEN. Date: from 1700 to 1799
Type and date: WELL HEAD.
Type and date: C20 GATE PIER. Date: from 1900 to 1999
Type and date: C20 GATE. Date: from 1900 to 1999
Main material: limestone
Main material: rubble
Main material: brick
Covering material: stone
Main material: ashlar
Main material: stone
Main material: concrete
Covering material: welsh slate

**Designating Organisation:**

**Location**

**Grid Reference:** SU 00057 70978 (point)
**Map sheet:** SU07SW **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

21 Mill Street, Calne, Wiltshire, SN11 8DP

**Listed Building Addresses**

Statutory

COACH HOUSE, GAZEBO, GATE PIERS AND GARDEN WALLS TO THE VICARAGE

Former Statutory

GAZEBO IN VICARAGE GARDEN

**Designation History**

**Assignment**

20/02/1975

**Sources - None recorded**

**Associated Monuments**

MWI36373 Building: COACH HOUSE, GAZEBO, GATE PIERS AND GARDEN WALLS TO THE VICARAGE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456698

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5985 **Name:** COACH HOUSE, GAZEBO, GATE PIERS AND GARDEN WALLS TO

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5975 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270943 | 1270943 | 755-1, 4, 92 |

**Name:** DOMINION HOUSE

**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 MARKET HILL
755-1/4/92 (South side)
02/04/76 No.2 Dominion House
GV II
House, now offices. Early C19. Limestone rubble with painted ashlar; brick and ashlar gable stacks and pantile mansard roof. Single-depth plan and rear service range. 2 storeys and attic; 2-window range. Cornice and parapet, pilaster strips, plain central doorway and panelled door, blocked window above. Paired 6/6-pane sashes, and 2 dormers with hipped roofs and mid C20 casements. Lead downpipe. INTERIOR: through-passage, left-hand dogleg stair, 3-bay roof.
Listing NGR: ST9969671041

**Curatorial Notes**

Type and date: Early C19 CROSS PASSAGE HOUSE. Date: from 1800 to 1832
Type and date: Now OFFICE.
Type and date: SERVICE WING.
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99694 71043 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Dominion House 2 Market Hill, Calne, Wiltshire, SN11 0BT

**Listed Building Addresses**

Statutory
DOMINION HOUSE

**Designation History**

**Assignment**
02/04/1970

**Sources - None recorded**

**DesigUID:** DWI5975 **Name:** DOMINION HOUSE

**Associated Monuments**

MWI36461 Building: DOMINION HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456688

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5991 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270949 | 1270949 | 755-1, 5, 104 |

**Name:** FRONT CURTILAGE WALL TO NOS 1,2 AND 3 KERRY CRESCENT
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/104 (East side)
08/07/76 Front curtilage wall to Nos.1, 2 and 3, Kerry Crescent
(Formerly Listed as: KERRY CRESCENT Front curtilege wall of Nos 1-3 (Consec))
GV II
Wall. c1870s. Limestone ashlar. Eclectic Tudor Revival style. Garden wall pierced by lobed openings with moulded coping, and square piers with ball finials. Included for group value.
Listing NGR: ST9978770846

**Curatorial Notes**

Type and date: c1870s WALL. Date: from 1870 to 1879
Main material: limestone
Main material: ashlar

**Designating Organisation:**

---

**Location**

**Grid Reference:** ST 99790 70831 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

New Road, Calne, Wiltshire, SN11 0JJ

**Listed Building Addresses**

Statutory
FRONT CURTILAGE WALL TO NOS 1,2 AND 3 KERRY CRESCENT

**DesigUID:** DWI5991 **Name:** FRONT CURTILAGE WALL TO NOS 1,2 AND 3 KERRY CRESCENT

Former Statutory
FRONT CURTILEGE WALL OF NOS 1-3

**Designation History**

Assignment
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI32980 Building: FRONT CURTILAGE WALL TO NOS 1,2 AND 3 KERRY CRESCENT

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456737

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5928 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247111 | 1247111 | 755-1, 5, 42 |

**Name:** GATES, GATE PIERS AND WALLS TO ST MARY'S CHURCHYARD, INCLUDING PROCLAMATION STEPS

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/42 (East side)
08/07/76 Gates, gate piers and walls to St Mary's Churchyard, incl Proclamation Steps
(Formerly Listed as: CHURCH STREET (East side) North Gate to Churchyard of St Mary's)
(Formerly Listed as: CHURCH STREET (East side) West gate to Churchyard of St Mary's)
GV II
Gates, gate piers and walls to churchyard. Mostly mid C19 with some earlier fabric. Limestone ashlar gate piers, quoins to intermittent piers and capping to walls, rubblestone to the rest. Pairs of gate piers to the south, west, north-west and north-east corners have truncated stepped pyramidal tops and chamfered plinths. Those to the south at the foot of a wide flight of steps to the south porch, support an overthrow of square-section twisted iron scrolled to the sides and centre with an empty lantern frame to the centre. The piers to the north-west have double iron gates with various horizontal bands of pierced quincunx to top, bottom and centre; those to the north-east flank the top of Proclamation Steps. The walls, formerly supporting iron railings, are articulated by low square piers at approx 5m intervals; from Proclamation Steps at the NE corner they step up for approx 40m along the east side, step down for approx 75m along the south side, flanking the south gate, extend approx

**DesigUID:** DWI5928 **Name:** GATES, GATE PIERS AND WALLS TO ST MARY'S CHURCHYARD,

45m along the west side, 25m to the north and the wall to the north-east is a rubblestone revetment wall with widely spaced railings. Proclamation Steps, where Royal Proclamations were read, consist of a flight of 11 stone steps from Mill Street to the north-west corner of the churchyard, with railings to the east.
Listing NGR: ST9991370930

**Curatorial Notes**

Type and date: Mid C19 GATE. Date: from 1833 to 1866
Type and date: Mid C19 GATE PIER. Date: from 1833 to 1866
Type and date: Mid C19 WALL. Date: from 1833 to 1866
Type and date: Mid C19 CHURCHYARD. Date: from 1833 to 1866
Type and date: ARCH.
Type and date: STEPS.
Type and date: RAILINGS.
Type and date: REVETMENT.
Main material: limestone
Main material: ashlar
Main material: rubble
Main material: stone
Main material: iron

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99913 70930 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory

GATES, GATE PIERS AND WALLS TO ST MARY'S CHURCHYARD, INCLUDING PROCLAMATION STEPS

Former Statutory

NORTH GATE TO CHURCHYARD OF ST MARY'S

Former Statutory

WEST GATE TO CHURCHYARD OF ST MARY'S

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI32846 Building: GATES, GATE PIERS AND WALLS TO ST MARY'S CHURCHYARD, INCLUDING PROCLAMATION STEPS

**Associated Consultations - None**

**DesigUID:** DWI5928 **Name:** GATES, GATE PIERS AND WALLS TO ST MARY'S CHURCHYARD,

**Additional Information**

**LBSUID:** 455166

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5930 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271029 | 1271029 | 755-1, 5, 47 |

**Name:** GROUP OF THREE HEADSTONES APPROXIMATELY 8 METRES NORTH NORTH WEST OF CHURCH OF ST MARY

**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/47 Group of three headstones approx 8m NNW of Church of St Mary
GV II
Group of 3 headstones. Commemorate Katherine Thisham, d.1703; Thomas Heath, d.1732; Robert Smith, d.1739. Limestone. Tops of stones have carved winged cupid heads, that to Thisham in relief, that to Heath incised.
Listing NGR: ST9988370921

**Curatorial Notes**

Type and date: 1703 GRAVESTONE. Date: 1703
Type and date: 1732 GRAVESTONE. Date: 1732
Type and date: 1739 GRAVESTONE. Date: 1739
Main material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99884 70921 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory

GROUP OF THREE HEADSTONES APPROXIMATELY 8 METRES NORTH NORTH WEST OF CHURCH OF ST MARY

**Designation History**

**Assignment**

22/12/1995

**DesigUID:** DWI5930 **Name:** GROUP OF THREE HEADSTONES APPROXIMATELY 8 METRES

**Sources - None recorded**

**Associated Monuments**

MWI32749 Building: GROUP OF THREE HEADSTONES APPROXIMATELY 8 METRES NORTH NORTH WEST OF CHURCH OF ST MARY

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455168

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5931 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1271030 | 1271030 | 755-1, 5, 45 |

**Name:** HEADSTONE APPROXIMATELY 13 METRES WEST NORTH WEST OF CHURCH OF ST MARY

**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/45 (East side) Headstone approx 13 metres west-north-west of Church of St Mary
GV II
Headstone. C17. Limestone ashlar. Cinquefoil-headed panel, with an open Celtic cross on top.
Listing NGR: ST9987070915

**Curatorial Notes**

Type and date: C17 GRAVESTONE. Date: from 1600 to 1699
Main material: limestone
Main material: ashlar

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99868 70915 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory
HEADSTONE APPROXIMATELY 13 METRES WEST NORTH WEST OF CHURCH OF ST MARY

**DesigUID:** DWI5931 **Name:** HEADSTONE APPROXIMATELY 13 METRES WEST NORTH WEST

**Designation History**

Assignment
22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI33722 Building: HEADSTONE APPROXIMATELY 13 METRES WEST NORTH WEST OF CHURCH OF ST MARY

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456338

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6005 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247342 | 1247342 | 755-1, 5, 124 |

**Name:** HOUSE TO SOUTH OF PATFORD HOUSE
**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/124 (West side)
02/04/70 House to south of Patford House
(Formerly Listed as: PATFORD STREET (West side) Calne Municipal Offices)
GV II
House, now offices. Early C18, altered mid C20. Stucco over limestone rubble, limestone dressings, gable stacks and slate roof. Double-depth plan. 2 storeys; 3-window range. Part of a composed design with Patford House and No.5 (qv), from which it is set back, with a continuous frieze and cornice. Right-hand doorway with bracketed pediment to a recessed doorway with 6-panel door. Altered windows, 3-light ground-floor and 2-light above. Mid C20 two-storey extension to the S. INTERIOR: altered, an entrance passage and C20 stair. Included for group value.
Listing NGR: ST9969370930

**Curatorial Notes**

Type and date: Early C18 HOUSE. Date: from 1700 to 1732
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Type and date: Now OFFICE.
Type and date: LOCAL GOVERNMENT OFFICE.
Main material: stucco
Main material: limestone
Main material: rubble
Covering material: slate

**DesigUID:** DWI6005 **Name:** HOUSE TO SOUTH OF PATFORD HOUSE

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99693 70930 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Patford Street, Calne, Wiltshire, SN11 0EF

**Listed Building Addresses**

Statutory

HOUSE TO SOUTH OF PATFORD HOUSE

Former Statutory

CALNE MUNICIPAL OFFICES

**Designation History**

**Assignment**

02/04/1970

**Sources - None recorded**

**Associated Monuments**

MWI38639 Building: HOUSE TO SOUTH OF PATFORD HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456755

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5990 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247328 | 1247328 | 755-1, 5, 103 |

**Name:** KERRY CRESCENT

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/103 (East side)
08/07/76 Nos.1, 2 and 3, Kerry Crescent
(Formerly Listed as: KERRY CRESCENT (East side) Nos.1-3 (Consecutive))
GV II

**DesigUID:** DWI5990 **Name:** KERRY CRESCENT

Terrace of 3 houses. C1870s. Coursed squared limestone rubble with ashlar dressings, ashlar axial ridge stacks and a pantile hipped roof. Free Tudor and Jacobean Revival style. Double-depth plan. 2 storeys; 3:1:2-window range. A concave near-symmetrical front has a continuous ground-floor label mould, modillion eaves cornice, central segmental through carriage arch between Doric pilasters to a modillion cornice. Tudor-style stone-mullioned and transomed cross windows, outer ground-floor 4-light windows, inner 3-light windows; first-floor half dormers with cyma-shaped gables to ball finials, and a central pair of cross windows with a central carved monogram, cartouche panel and pediment in a Dutch gable on scrolled brackets. Doorways to Nos 1 & 3 in the left-hand section and right-hand return respectively, have console bracketed shell hoods and 5-centred doorways with 6-panel doors, to No.2 within the archway has a console bracket flat canopy and 4-panel door. Rear elevation has projecting ranges flanking the carriageway, with dormers as the front. INTERIOR not inspected.
Listing NGR: ST9980870845

**Curatorial Notes**

Type and date: c1870s TERRACE. Date: from 1870 to 1879
Type and date: c1870s TERRACED HOUSE. Date: from 1870 to 1879
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99808 70845 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

New Road, Calne, Wiltshire, SN11 0JJ

**Listed Building Addresses**

Statutory
KERRY CRESCENT

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36377 Building: Kerry Crescent

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456703

**List Locality:**
**List Parish:** CALNE

**DesigUID:** DWI5990 **Name:** KERRY CRESCENT

**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5958 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247212 | 1247212 | 755-1, 4, 74 |

**Name:** KINGS ARMS PUBLIC HOUSE
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/74 (West side)
08/07/76 No.18 Kings Arms Public House
GV II
Public house. Probably C18, extended to rear and remodelled in mid C19. Rendered, brick rear ranges, with ashlar and brick ridge stacks, and slate roof. Single-depth plan with 2 rear wings and right-hand rear courtyard. Single storey with attic and cellar; 3:2-window range. A long front with coped left-hand gable, right hand keyed, segmental-arched carriage entrance, and a central open Tuscan portico with steps up. Paired outer horned plate-glass sashes, and a single sash to the left of the entrance, and pilaster jambs to hipped attic windows just breaking the eaves with 6/6-pane sashes. INTERIOR: ground floor altered, otherwise not inspected.
Listing NGR: ST9970171109

**Curatorial Notes**

Type and date: C18 PUBLIC HOUSE. Date: from 1700 to 1799
Type and date: Mid C19 PUBLIC HOUSE. Date: from 1833 to 1866
Main material: render
Main material: brick
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99701 71112 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

18 High Street, Calne, Wiltshire, SN11 0BS

**Listed Building Addresses**

Statutory
KINGS ARMS PUBLIC HOUSE

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**DesigUID:** DWI5958 **Name:** KINGS ARMS PUBLIC HOUSE

**Associated Monuments**

MWI36446 Building: KINGS ARMS PUBLIC HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456524

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6048 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247467 | 1247467 | 755-1, 5, 170 |

**Name:** KINGSBURY HOUSE
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/170 (East side)
08/07/76 Kingsbury House
(Formerly Listed as: THE GREEN (East side) Red Cross HQ Building at rear of Nos.1 and 2)
GV II
House. Early C19, altered late C20. Coursed, squared and unsquared limestone rubble with a rendered front, and pantile roof. Single-depth plan. 2 storeys, basement and attic; 3-window range. A right-hand angled C20 porch, with a single ground-floor and 3 small first-floor windows, and 2 gabled dormers. Left-hand gable has rebuilt attic section with squared rubble, a basement French window, 2-light ground and first-floor windows, and 3-light attic window, with late C20 casements all with altered jambs. INTERIOR not inspected. Included for group value.
Listing NGR: ST9993870903

**Curatorial Notes**

Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Late C20 HOUSE. Date: from 1967 to 1999
Type and date: OFFICE.
Main material: limestone
Main material: rubble
Main material: render
Covering material: pantile

**Designating Organisation:**

---

**Location**

**Grid Reference:** ST 99933 70903 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

**DesigUID:** DWI6048 **Name:** KINGSBURY HOUSE

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Kingsbury Hall The Green, Calne, Wiltshire, SN11 8DG

**Listed Building Addresses**

Statutory

KINGSBURY HOUSE

Former Statutory

RED CROSS HQ BUILDING AT REAR OF NOS 1 AND 2

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36463 Building: KINGSBURY HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456955

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6055 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247495 | 1247495 | 755-1, 4, 177 |

**Name:** LANSDOWNE ARMS HOTEL AND FORMER COACH HOUSE, STABLE AND BREWHOUSE

**Grade:** II* **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 THE STRAND
755-1/4/177 (West side)
19/05/50 Lansdowne Arms Hotel and former coach house, stable and brewhouse
GV II*

Formerly known as: No.9 Lansdowne Arms Hotel THE STRAND. Formerly known as: The Catherine Wheel Inn THE STRAND. Inn and several houses, now hotel and former stables and brewery buildings. Mid-late C17 left-hand end, refronted early C18, left-hand range partly rebuilt mid C19, rear C18 and C19 brewery and stable buildings. Painted limestone rubble, coursed limestone left-hand gable, coursed rubble rear blocks, 5 limestone ashlar ridge stacks, stone slate roof, with slates and pantiles to rear blocks. Single-depth plan front range, with former stable and brewery buildings forming a large courtyard behind. 2 storeys and attic; 16-window range. A long parapeted front with

cornice has a segmental-arched carriage entrance 3 from the right with a late C20 door, bolection-moulded surrounds to 6/6-pane sashes. An incorporated C17 3-window left-hand range set back, with a ground-floor string, coped end gable with a finial and moulded kneelers, and 1:2 cyma-moulded cross windows with metal casements; on the first floor is a fire mark dated 1696, inscribed MC with a lion; 1-window gable end rebuilt c1866 has 3-light cross windows to each floor. Rear elevation has irregular fenestration reflecting earlier houses, with a left-hand 1-window gabled stair tower with a C18 6/6-pane first-floor stair light with thick bars and exposed frame, a wide central gable with 2 first-floor 6/6-pane sashes and an attic casement, and 2-storey right-hand lean-to with paired first-floor 6/6-pane sashes; a date stone is inscribed 1860. Large wrought-iron carriage lamp over the entrance, and a large round clock toward the right-hand end in a moulded surround. S former stable range, 2 storeys; 4 windows, has a right-hand segmental-arched carriage entrance. Mid C19 W range, 2 storeys; 2 windows to the courtyard, ground- and first-floor keyed segmental-arched windows with ashlar surrounds and first-floor 21/21-pane sashes, above paired segmental-arched doorways. Mid C18 NW range raised on side of slope with a splayed entrance corner and hipped roof, timber mullion windows beneath the eaves, and a C19 door with overlight. Castle Street end is half-hipped with timber lintels. Former brewery to N side, early-mid C19, coursed rubble with brick dressings and quoins. 3 storeys; 2-window range. Inserted concrete lintels to later windows, partly blocked wide entrance, with an octagonal banded brick gable chimney with cornice at the left-hand end. Former coach house. C17, rubble with stone slate roof. 2 storeys and attic; 1-window range. An irregular front has quoins and a splayed right-hand corner, steep gable, wide entrance, inserted first-floor window, and attic window with ashlar surround. INTERIOR: altered; details include a former through-passage to the rear courtyard, with a rear open-well stair to the left with column-on-vase balusters, a rear lateral passage; left-hand end has 6 bays with arch-braced collars, and moulded first-floor axial and lateral ceiling beams. HISTORICAL NOTE: mentioned as an inn from 1582, known as the Catherine Wheel. Existing building formed from amalgamation of up to 5 domestic properties, parts of which can be seen in the rear elevation. An important group including the ancillary buildings round the rear courtyard. (The Buildings of England: Pevsner N & Cherry B: Wiltshire: London: 1963-1975: 156). Listing NGR: ST9971571004

**Curatorial Notes**

Type and date: Mid-late C17 INN. Date: from 1633 to 1699
Type and date: Early C18 INN. Date: from 1700 to 1732
Type and date: Mid C19 INN. Date: from 1833 to 1866
Type and date: C18 STABLE. Date: from 1700 to 1799
Type and date: C19 STABLE. Date: from 1800 to 1899
Type and date: Early-midC19 BREWERY. Date: from 1800 to 1866
Type and date: Mid-late C17 CROSS PASSAGE HOUSE. Date: from 1633 to 1699
Type and date: Early C18 HOUSE. Date: from 1700 to 1732
Type and date: Mid C19 HOUSE. Date: from 1833 to 1866
Type and date: Now HOTEL.
Type and date: c1866 INN. Date: from 1846 to 1886
Type and date: c1866 HOUSE. Date: from 1846 to 1886
Type and date: 1860 DATE STONE. Date: 1860
Type and date: LAMP BRACKET.
Type and date: C17 COACH HOUSE. Date: from 1600 to 1699
Type and date: From 1582 INN. Date: from 1582
Main material: limestone
Main material: rubble
Main material: brick
Covering material: stone
Covering material: slate
Covering material: pantile

**DesigUID:** DWI6055 **Name:** LANSDOWNE ARMS HOTEL AND FORMER COACH HOUSE,

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99713 71007 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Patford Street, Calne, Wiltshire, SN11 0EF

**Listed Building Addresses**

Statutory

LANSDOWNE ARMS HOTEL AND FORMER COACH HOUSE, STABLE AND BREWHOUSE

Alternative

LANSDOWNE ARMS HOTEL

Alternative

THE CATHERINE WHEEL INN

**Designation History**

**Assignment**

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36470 Building: Lansdowne Arms Hotel

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456995

**List Locality:** THE STRAND

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6028 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247412 | 1247412 | 755-1, 6, 151 |

**Name:** LITTLE SHELDON

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
SU0070 THE GREEN
755-1/6/151 (East side)

**DesigUID:** DWI6028 **Name:** LITTLE SHELDON

08/07/76 No.11 Little Sheldon
GV II
House. Mid C17, extensively altered and remodelled early C20. Squared coursed limestone with ashlar gable stacks and stone slate roof. Single-depth, originally 3-room, plan. 2 storeys and attic; 4-window range. Coped gables and a large central gable dormer; left-of-centre C20 door beneath a wide slated canopy. Label moulds over restored stone-mullioned windows of 1, 2 and 4 lights with metal leaded casements. INTERIOR remodelled c1930.
Listing NGR: SU0001770813

**Curatorial Notes**
Type and date: Mid C17 HOUSE. Date: from 1633 to 1666
Type and date: Early C20 HOUSE. Date: from 1900 to 1932
Main material: limestone
Covering material: stone

**Designating Organisation:**

**Location**
**Grid Reference:** SU 00017 70813 (point)
**Map sheet:** SU07SW **Area (Ha):** 0.00

**Administrative Areas**
Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**
Flat 1 4 The Green, Calne, Wiltshire, SN11 8DG

**Listed Building Addresses**
Statutory
LITTLE SHELDON

**Designation History**
**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**
MWI32987 Building: LITTLE SHELDON

**Associated Consultations - None**

**Additional Information**
**LBSUID:** 456882

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5954 **Type:** Listed Building **Status:** Active
**NHLE number** **NHLE number** **Volume/Map/Item**

**DesigUID:** DWI5954 **Name:** LLOYDS BANK

1247210 1247210 755-1, 4, 70

**Name:** LLOYDS BANK

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/70 (East side)
08/07/76 Nos.10 AND 11 Lloyds Bank
GV II
Pair of attached houses, now one bank. c1870s. Limestone ashlar, large central ashlar ridge stack, hipped slate roof. Double-depth plan. 3 storeys; 4-window range. A symmetrical front divided by rusticated pilaster strips, rusticated ground floor with a cornice, first-floor modillion cornice, second-floor swagged frieze and cornice, and balustrade with panelled dies and 5 ball finials. Right-hand doorway with C20 door. Eared and shouldered architraves to first and second floors, the former with dentil cornice and pediments, segmental to the outside, the latter raised over carved keys, and horned plate-glass sashes. INTERIOR: the ground floor completely altered and made into one room.
Listing NGR: ST9975271097

**Curatorial Notes**

Type and date: c1870s HOUSE. Date: from 1870 to 1879
Type and date: Now BANK (FINANCIAL).
Main material: limestone
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99732 71089 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

T G Jeary Chemist 13 High Street, Calne, Wiltshire, SN11 0BW

**Listed Building Addresses**

Statutory
LLOYDS BANK

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36442 Building: Lloyds Bank, 10-11 High Street

**Associated Consultations - None**

**Additional Information**

**DesigUID:** DWI5954 **Name:** LLOYDS BANK

**LBSUID:** 456520

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5992 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247334 | 1247334 | 755-1, 5, 109 |

**Name:** MARDEN HOUSE CENTRE
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/109 (West side)
08/07/76 Marden House Centre
(Formerly Listed as: NEW ROAD (West side) Marden House (Harris's))
II
Former canal building at the termination of the Calne branch of the Wiltshire and Berkshire Canal, probably occupied by the wharfinger, now a community centre. C18 and c1830. Ashlar to the c1830 projecting central block and coursed limestone rubble to the rest, steep-pitched roofs to the side wings, pantile to the rear, slate to the front slope of left wing with a small square stack to the left gable end; pantile roof to the right; slate to the front of main block, truncated stone stack to the right. Single-depth plan to symmetrical 3-window-range central block which was built into the front of the former building creating a double-pitched double-depth plan. 2 storeys; 2 windows to each wing, making 7-window range overall. The C20 double doors have a C19 overlight of 4 panes, flanked by C19 flat arches with keystones to plate-glass sash windows with margin panes, those to the ground floor are wider. A cornice below the parapet has a fluted frieze. The C18 block to the left has a similar window to the first floor, an ashlar platband, a small C19 plate-glass window to the ground-floor left and a C20 door to the right. The wing to the right, probably older, is of softer limestone rubble with two C19 horned 2/2-pane sash windows to the first floor, a platband over a C20 door and porch to the right and a C20 plate-glass window to the far right. To apex of the gable end of the right return is a small C18 window. INTERIOR: the ground floor of the central block retains panelled window shutters and reveal to the door. In 1914 the first floor was removed and the roof timber trusses replaced with metal to create a scout hall. Included for group value and historical interest.
Listing NGR: ST9975070844

**Curatorial Notes**

Type and date: C18 CANAL WORKERS COTTAGE. Date: from 1700 to 1799
Type and date: c1830 CANAL WORKERS COTTAGE. Date: from 1810 to 1850
Type and date: Now COMMUNITY CENTRE.
Type and date: 1914 SCOUT HUT. Date: 1914
Main material: ashlar
Main material: limestone
Main material: rubble
Covering material: pantile
Covering material: slate

**Designating Organisation:**

**DesigUID:** DWI5992 **Name:** MARDEN HOUSE CENTRE

**Location**

**Grid Reference:** ST 99750 70844 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

New Road, Calne, Wiltshire, SN11 0JJ

**Listed Building Addresses**

Statutory

MARDEN HOUSE CENTRE

Former Statutory

HARRIS'S

Former Statutory

MARDEN HOUSE

**Designation History**

**Assignment**

08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36378 Building: Marden House Centre

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456738

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6056 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247534 | 1247534 | 755-1, 5, 178 |

**Name:** OLD FIRE STATION AT REAR OF TOWN HALL

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE STRAND
755-1/5/178 (South side)
08/07/76 Old Fire Station at rear of Town Hall
GV II

**DesigUID:** DWI6056 **Name:** OLD FIRE STATION AT REAR OF TOWN HALL

Fire station. Late C19. Limestone ashlar and coursed rubble, ashlar gable stack and pantile half-hipped roof. Rectangular plan. 2 storeys; 1-window range. Ashlar clasping corners with a ground-floor cornice, forms full-height round-headed archway, ashlar ground floor with a plinth, rubble above. Patford Street end has a lower 2-storey ashlar right-hand range with a right-hand door and paired first-floor windows in architraves. INTERIOR not inspected. Included for group value.
Listing NGR: ST9972270956

**Curatorial Notes**

Type and date: Late C19 FIRE STATION. Date: from 1867 to 1899
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99717 70955 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Patford Street, Calne, Wiltshire, SN11 0EF

**Listed Building Addresses**

Statutory
OLD FIRE STATION AT REAR OF TOWN HALL

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36471 Building: Old Fire Station, Rear of Town Hall

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 457096

**List Locality:** THE STRAND
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6004 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247341 | 1247341 | 755-1, 5, 123 |

**DesigUID:** DWI6004 **Name:** PATFORD HOUSE

**Name:** PATFORD HOUSE
**Grade:** II **Assigned:** 02/04/1970 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 PATFORD STREET
755-1/5/123 (West side)
02/04/70 Patford House
(Formerly Listed as: PATFORD STREET (West side) Calne Municipal Offices)
GV II
House, formerly included house to the S, now office. Early-mid C18, altered early C19, and mid C20. Stucco with limestone dressings, ashlar gable stacks and slate roof. Double-depth plan. 2 storeys and attic; 3:1:3-window range. Double-fronted with an ashlar plinth, ground-floor cill band, quoins, frieze, cornice and blocking course; fine pedimented doorcase with attached Tuscan columns, 6-panel door and overlight with pointed Gothic glazing bars and lantern. Horned plate-glass sashes in full-height 3-light bows, and 2 hipped dormers. INTERIOR: a good early C18 interior, details include an entrance hall divided by a round-headed arch, to a rear open-well stair with curtail, column on vase balusters, a modillion cornice and oval plaster ceiling panel; lateral corridor with dado, and a good marble fire surround in the front left-hand room; a good first-floor front room with raised and fielded panelling and boxed out cornice, with a central front dressing room; altered collar truss roof with wide boards. A composed design with No.5 (qv), which was refronted to match, and house to the south (qv), all of which have a matching continuous cornice.
Listing NGR: ST9970270939

**Curatorial Notes**

Type and date: Early-mid C18 HOUSE. Date: from 1700 to 1766
Type and date: Early C19 HOUSE. Date: from 1800 to 1832
Type and date: Mid C20 HOUSE. Date: from 1933 to 1966
Type and date: Now OFFICE.
Type and date: LOCAL GOVERNMENT OFFICE.
Main material: stucco
Main material: limestone
Covering material: slate
Main material: ashlar

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99695 70939 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

7 Patford Street, Calne, Wiltshire, SN11 0EF

**Listed Building Addresses**

Statutory
PATFORD HOUSE
Former Statutory
CALNE MUNICIPAL OFFICES

**Designation History**

**DesigUID:** DWI6004 **Name:** PATFORD HOUSE

**Assignment**
02/04/1970

**Sources - None recorded**

**Associated Monuments**
MWI38638 Building: PATFORD HOUSE

**Associated Consultations - None**

**Additional Information**
**LBSUID:** 456754

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5979 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247320 | 1247320 | 755-1, 5, 96 |

**Name:** POND COTTAGE
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**
CALNE
ST9970 MILL STREET
755-1/5/96 (North side)
08/07/76 No.8 Pond Cottage
(Formerly Listed as: MILL STREET (North side) No.8 Mill House)
GV II
Miller's house, now house, attached to mill. Early or mid C19, altered c1980. Coursed, squared limestone rubble with ashlar dressings, and a slate roof. Single-depth plan with rear wing. 2 storeys; 2-window range. Attached to the left-hand end of the Mill (qv), with coped gables and kneelers, a right-hand doorway with stone bracketed flat canopy and recessed C20 door, label moulds to ground-floor 3-light and 2-light first-floor flat-faced stone-mullioned windows with C20 leaded casements. Left return has a 2-light first-floor window, and the return of the rear wing, set in from the end, has similar mullioned 3-light ground- and 2-light first-floor windows. INTERIOR altered c1980.
Listing NGR: ST9996370963

**Curatorial Notes**
Type and date: Early or mid C19 MILL HOUSE. Date: from 1800 to 1866
Type and date: c1980 HOUSE. Date: from 1970 to 1990
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**DesigUID:** DWI5979 **Name:** POND COTTAGE

**Grid Reference:** ST 99959 70963 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**
Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**
8 Mill Street, Calne, Wiltshire, SN11 8DP

**Listed Building Addresses**
Statutory
POND COTTAGE
Former Statutory
MILL HOUSE

**Designation History**
**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**
MWI36367 Building: POND COTTAGE

**Associated Consultations - None**

**Additional Information**
**LBSUID:** 456692

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5924 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247102 | 1247102 | 755-1, 5, 38 |

**Name:** RAF CLUB
**Grade:** II* **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**
CALNE
ST9970 CHURCH STREET
755-1/5/38 (West side)
19/05/50 No.41 RAF Club
(Formerly Listed as: CHURCH STREET (West side) No.41 Masonic Hall)
GV II*
Priest's house or vicarage, now a services club. Early C17. Coursed limestone rubble, formerly limewashed, pantile roof with square stone stack with 2 diagonal brick shafts to left S gable end, brick stack to front right gable end and triple diagonal-shafted brick stack to central valley. Original stair

and entrance destroyed c1948-61. 2 rooms deep with entrance passage positioned to right of front parlour, left-hand and parallel S ranges. 2 storeys; 3-window range. A 2-storey central splayed bay with a hipped roof has leaded 5-light ovolo-mullioned and transomed windows, with left-hand cross windows, right-hand lower and smaller mullion window, possibly a former stair window. Below it a fine C17 planked and studded door with strap hinges set in a chamfered semi-elliptical-arched architrave. The S range has a first-floor 3-light ovolo-moulded window with C20 glass beneath a heavy relieving lintel; reported to have a 4-course dovecote in one of the gables. INTERIOR: a through-passage to the right has a C17 rear door similar to that at the front, both doors are horizontally planked on the inside. The ground-floor front room (formerly 2 rooms) has an open fire to the rear wall with a stone surround, cyma-moulded mantelshelf and a flat arch with curved corners and sunk spandrels. A crossbeam to the left has mortices for a stud wall, 2 axial beams have runout stops. A C19 staircase rises to the rear left. The room to the rear service area, on a higher level, has an open fire with a stone surround backing onto the same stack. The room to the first-floor front has wide oak floorboards, a similar but smaller fireplace to the rear wall and the ceiling is divided into 6 irregular panels, some with drilled wattle holes, some with slotted holes, all with run-out stops. The room to rear, on a higher level, has an open fire with a stone overmantel. Collar truss roof with cambered collars. No access to the attic or basement, both said to have original features. The best surviving C17 town house in Calne, and a notable example of its type with a fine façade. (Wiltshire Buildings Record: Trowbridge: B167).
Listing NGR: ST9985970826

**Curatorial Notes**

Type and date: Early C17 PRIESTS HOUSE. Date: from 1600 to 1632
Type and date: Early C17 VICARAGE. Date: from 1600 to 1632
Type and date: Now Servicemens Club.
Type and date: Early C17 CROSS PASSAGE HOUSE. Date: from 1600 to 1632
Type and date: SERVICE WING.
Type and date: Early C17 TOWN HOUSE. Date: from 1600 to 1632
Main material: limestone
Main material: rubble
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99859 70826 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

41 Church Street, Calne, Wiltshire, SN11 0HZ

**Listed Building Addresses**

Statutory

RAF CLUB

Former Statutory

MASONIC HALL

**Designation History**

**Assignment**

19/05/1950

**DesigUID:** DWI5924 **Name:** RAF CLUB

**Sources - None recorded**

**Associated Monuments**

MWI36417 Building: 41 Church Street

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 455162

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6027 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247410 | 1247410 | 755-1, 5, 150 |

**Name:** SHELDON HOUSE

**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/150 (East side)
19/05/50 No.10 Sheldon House
GV II

House. c1656, refronted and altered late C18-early C19, refaced. Limestone ashlar and rubble with left-hand and rear valley stack, with stone slate roof. 2-room plan with right-hand and rear parallel ranges. 2 storeys, cellar and attic; 3-window range. A symmetrical front has pilasters, cornice, and parapet with raised central section, coped gables with right-hand ball finial. Central doorway has a bracketed pediment and architrave to a 6-panel door, the top pair glazed. Plain ashlar surrounds with angle beads to paired outer and single central windows with late C19 plate-glass sashes with margin panes. 3 gabled dormers have 8-panes. The right-hand gable has a blocked ground-floor window, and blocked 3-light C17 attic window with chamfered surround and label mould, with a lead down pipe with original hopper to the front. The side wall behind is set in slightly, with a rear wide doorway and 6-panel door, and a 10/10-pane ground-floor sash. Rear extended early C20. INTERIOR: details include a flagged central hall, front rooms have moulded lateral beams, central early C18 rear dogleg stair with column-on-vase balusters and ramped rail. Front left-hand room has early C18 panelling, fireplace and overmantel, and a fine rear shell-head niche in a blocked window; right-hand room has fine and notable example of early faux panelling wallpaper. First-floor left-hand room has a good C17 scratch-moulded cupboard set in a blocked rear window; chamfered ceiling beams. Varied roof structure, with no ridge to the right-hand section, and threaded ridge to the centre; one arch brace visible in the wall. Early C19 stone fireplaces with hob grates. (Wiltshire Buildings Record: Trowbridge: 1991-).
Listing NGR: ST9999770809

**Curatorial Notes**

Type and date: c1656 HOUSE. Date: from 1636 to 1676
Type and date: Late C18-early C19 HOUSE. Date: from 1767 to 1832

**DesigUID:** DWI6027 **Name:** SHELDON HOUSE

Type and date: Early C20 HOUSE. Date: from 1900 to 1932
Main material: limestone
Main material: ashlar
Main material: rubble
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99992 70805 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

10 The Green, Calne, Wiltshire, SN11 8DG

**Listed Building Addresses**

Statutory
SHELDON HOUSE

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI34229 Building: SHELDON HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456880

**List Locality:** THE GREEN
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5966 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270992 | 1270992 | 755-1, 5, 83 |

**Name:** THE TOUNSON ALMSHOUSES
**Grade:** II* **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 KINGSBURY STREET
755-1/5/83 (South West side)

**DesigUID:** DWI5966 **Name:** THE TOUNSON ALMSHOUSES

19/05/50 Nos.10-13 (Consecutive) The Tounson Almshouses
GV II*
Formerly known as: Nos.10-17 The Tounson Almshouses KINGSBURY STREET. Terrace of 8 paired almshouses, now 4. c1682, altered 1973. For John Tounson. Limewashed limestone rubble with ashlar ridge stacks and a stone slate roof. Single-depth plan, originally of one room each. Each of 2 storeys; 2-window range. Paired central heavy 3-plank doors with wrought-iron strap hinges with fleur-de-lys ends, and grille-covered peep holes, in chamfered wood frames with bar stops. Stone-mullioned windows with ovolo-moulded surrounds, and ground-floor label moulds; leaded metal casements with stays. Each a single-room plan, now with through-passage and side entrances. Rear elevation has a late C20 full-width timber verandah, small single-light windows with timber lintels, and 3 C20 inserted half dormers with leaded lights. Over the second doorway from the left is an inscribed plaque giving details of the original benefaction by John Tounson in 1683. INTERIOR: heavy lateral beams with roll stopped chamfers. Roof reported to have been renewed. A fine and complete row, executed in the local vernacular style. (The Buildings of England: Pevsner N & Cherry B: Wiltshire: London: 1963-1975: 157).
Listing NGR: ST9990870868

**Curatorial Notes**

Type and date: c1682 TERRACE. Date: from 1662 to 1702
Type and date: c1682 TERRACED HOUSE. Date: from 1662 to 1702
Type and date: 1973 TERRACED HOUSE. Date: 1973
Type and date: 1973 TERRACE. Date: 1973
Type and date: Now CROSS PASSAGE HOUSE.
Type and date: 1683 PLAQUE. Date: 1683
Main material: limestone
Main material: rubble
Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99906 70867 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

10 Kingsbury Street, Calne, Wiltshire, SN11 8DF
13 Kingsbury Street, Calne, Wiltshire, SN11 8DF
12 Kingsbury Street, Calne, Wiltshire, SN11 8DF
11 Kingsbury Street, Calne, Wiltshire, SN11 8DF
11 Kingsbury Street, Calne, Wiltshire, SN11 8DF

**Listed Building Addresses**

Statutory
THE TOUNSON ALMSHOUSES
Alternative
THE TOUNSON ALMSHOUSES

**Designation History**

**Assignment**

**DesigUID:** DWI5966 **Name:** THE TOUNSON ALMSHOUSES

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36453 Building: The Tounson Almshouses

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456532

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5984 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247332 | 1247332 | 755-1, 6, 101 |

**Name:** THE VICARAGE
**Grade:** II **Assigned:** 20/02/1975 **Amended:** **Revoked:**

**Legal Description**

CALNE
SU0070 MILL STREET
755-1/6/101 (North side)
20/02/75 The Vicarage
GV II
House, extended. Dated 1600 by owner, extended early-mid C19. Limestone rubble and dressings, C19 ashlar, with ashlar front lateral and ridge stacks and a slate hipped roof. Single-depth 2-room plan right-hand and double-depth plan, with a central courtyard. 2 storeys; 2:3-window range. Earlier 3-window right-hand range divided 1:2 by a lateral stack, with a right-hand gable and decapitated stack; inserted C19 windows with ashlar surrounds and 3/6-pane sashes. Left-hand range has a plat band and deep overhanging eaves on paired moulded brackets. Right of centre porch has a half-glazed door. Window over porch has round-arched glazing bars, 3/6-pane sash to the left; left-hand 3-window return has deep 6/9-pane ground-floor and 3/6-pane first-floor sashes, and a rear canted bay window with moulded architraves to 8/8-panes sashes. INTERIOR not inspected.
Listing NGR: SU0002070980

**Curatorial Notes**

Type and date: 1600 HOUSE. Date: 1600
Type and date: Early-mid C19 HOUSE. Date: from 1800 to 1866
Type and date: VICARAGE.
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**DesigUID:** DWI5984 **Name:** THE VICARAGE

**Location**

**Grid Reference:** SU 00020 70980 (point)

**Map sheet:** SU07SW **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

21 Mill Street, Calne, Wiltshire, SN11 8DP

**Listed Building Addresses**

Statutory

THE VICARAGE

**Designation History**

**Assignment**

20/02/1975

**Sources - None recorded**

**Associated Monuments**

MWI36372 Building: THE VICARAGE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456697

**List Locality:**

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI6057 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270827 | 1270827 | 755-1, 5, 180 |

**Name:** TOWN HALL

**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE STRAND
755-1/5/180 (South side)
08/07/76 Town Hall
GV II

Town hall. c1884-6. By Oliver. Squared, coursed limestone rubble, with a slate roof. Tudor Revival style. Irregular plan, with left-hand council chamber and rear hall, central clock tower and carriage archway, and right-hand double-depth plan offices along Patford Street. 2 storeys and attic; 5-window range. An irregular front has a plinth, strings, and coped gables and parapet, with mullion and transom windows: a left-hand full-height gable with paired 3-light ground-floor windows, paired cross

windows above a carved panel on the first floor, and a 3-light attic mullion window under blind panelling beneath the gable; beneath the tower is a Tudor-arched doorway, 9-light first-floor stair window, and an ashlar clock tower with clock set in a shallow recess, and a pyramidal roof. A wide Tudor-arched carriageway beneath a 6-light window, and 8- and 3-light windows to the right-hand section beneath a pair of small gables. INTERIOR: details include an open-well stair with a lift inserted to the well, panelled council chamber, and rear meeting hall.
Listing NGR: ST9973670972

**Curatorial Notes**

Type and date: c1884-6 TOWN HALL. Date: from 1884 to 1886
Type and date: c1884-6 CLOCK TOWER. Date: from 1884 to 1886
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99728 70970 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

The Old Bank House The Strand, Calne, Wiltshire, SN11 0EN

**Listed Building Addresses**

Statutory
TOWN HALL

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI33730 Building: Calne Town Hall

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 457097

**List Locality:** THE STRAND
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5932 **Type:** Listed Building **Status:** Active

**DesigUID:** DWI5932 **Name:** TWO CHEST TOMBS APPROXIMATELY 15 METRES NORTH OF

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247116 | 1247116 | 755-1, 5, 43 |

**Name:** TWO CHEST TOMBS APPROXIMATELY 15 METRES NORTH OF THE TOWER OF CHURCH OF ST MARY

**Grade:** II **Assigned:** 22/12/1995 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 CHURCH STREET
755-1/5/43 (East side) Two chest tombs approx 15 metres north of the tower of Church of St Mary
GV II
Two chest tombs. Late C17/early C18 and early C19. Limestone. One approx 12m NE of the north porch is early C19. Moulded top swept up to a narrow ridge. The main block is of hard grey limestone with fluted pilasters to the corners; a frieze of horizontal rectangles with inverted corners alternates with patera; similar rectangular panels to all sides, those to the long sides are tapered toward the base. Later C17/early C18 chest tomb approx 15m to NNW of the tower. Plinth has sunk into the ground. A pulvinated frieze is over raised and fielded panels with worn pulvinated mouldings, 3 to the long sides one to each end, have worn inscriptions. The large, overhanging top slab has moulded edges.
Listing NGR: ST9989370932

**Curatorial Notes**

Type and date: Late C17/early C18 CHEST TOMB. Date: from 1667 to 1732
Type and date: Early C19 CHEST TOMB. Date: from 1800 to 1832
Main material: limestone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99893 70932 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

13 Church Street, Calne, Wiltshire, SN11 0HU

**Listed Building Addresses**

Statutory
TWO CHEST TOMBS APPROXIMATELY 15 METRES NORTH OF THE TOWER OF CHURCH OF ST MARY

**Designation History**

**Assignment**
22/12/1995

**Sources - None recorded**

**Associated Monuments**

MWI32984 Building: TWO CHEST TOMBS APPROXIMATELY 15 METRES NORTH OF THE TOWER OF CHURCH OF ST MARY

**DesigUID:** DWI5932 **Name:** TWO CHEST TOMBS APPROXIMATELY 15 METRES NORTH OF

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456339

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

**DesigUID:** DWI5959 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247213 | 1247213 | 755-1, 4, 76 |

**Name:** TWO K6 TELEPHONE KIOSKS APPROXIMATELY 20 METRES SOUTH OF KINGS ARMS PUBLIC HOUSE

**Grade:** II **Assigned:** 23/03/1989 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 HIGH STREET
755-1/4/76 (West side)
23/03/89 Two K6 telephone kiosks approx 20m S of Kings Arms Public House
(Formerly Listed as: HIGH STREET (East side) Pair of K6 Telephone Kiosks o/s Lloyds Bank)
GV II
Pair of telephone kiosks. Type K6. Designed 1935 by Sir Giles Gilbert Scott. Made by various contractors. Cast-iron. Square kiosks with domed roofs. Unperforated crowns to top panels and margin glazing to windows and doors.
Listing NGR: ST9972071081

**Curatorial Notes**

Type and date: 1935 TELEPHONE BOX. Date: 1935
Main material: cast iron

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99720 71081 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

T G Jeary Chemist 13 High Street, Calne, Wiltshire, SN11 0BW

**Listed Building Addresses**

Statutory

TWO K6 TELEPHONE KIOSKS APPROXIMATELY 20 METRES SOUTH OF KINGS ARMS PUBLIC HOUSE

**DesigUID:** DWI5959 **Name:** TWO K6 TELEPHONE KIOSKS APPROXIMATELY 20 METRES

Former Statutory
PAIR OF K6 TELEPHONE KIOSKS OUTSIDE LLOYDS BANK

**Designation History**

Assignment
23/03/1989

**Sources - None recorded**

**Associated Monuments**

MWI32908 Building: TWO K6 TELEPHONE KIOSKS APPROXIMATELY 20 METRES SOUTH OF KINGS ARMS PUBLIC HOUSE

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456525

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6049 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270883 | 1270883 | 755-1, 5, 172 |

**Name:** WEAVER'S HOUSE
**Grade:** II **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 THE GREEN
755-1/5/172 (East side)
19/05/50 Weaver's House
GV II
Formerly known as: Sawdust House THE GREEN. Cloth mill, now 3 flats. Late C18. Coursed limestone rubble with limestone dressings, gable stacks and stone slate roof. Single-depth plan. 3 storeys; 5-window range. A symmetrical front has quoins, coped gables and an ashlar plinth, a central doorway has a wide elliptical-arch with C20 door and margin lights. Paired stone mullioned windows in flat surrounds with angle beads to 8-light casements. Metal plates to wrought-iron ties at first- and second-floors. INTERIOR not inspected. An example of early workshop cloth manufacture. See Nos 8 & 9 (qv). (Rogers K: Woollen Mills of Wiltshire and Somerset: Edington: 1976-: 84).
Listing NGR: ST9995770839

**Curatorial Notes**

Type and date: Late C18 TEXTILE MILL. Date: from 1767 to 1799
Type and date: Now FLATS.
Main material: limestone
Main material: rubble

**DesigUID:** DWI6049 **Name:** WEAVER'S HOUSE

Covering material: stone

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99952 70839 (point)

**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

1 Weavers House The Green, Calne, Wiltshire, SN11 8DG

**Listed Building Addresses**

Statutory

WEAVER'S HOUSE

Alternative

SAWDUST HOUSE

**Designation History**

**Assignment**

19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36464 Building: Weaver's House, The Green

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456956

**List Locality:** THE GREEN

**List Parish:** CALNE

**List District:** NORTH WILTSHIRE

**List County:** WILTSHIRE

**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5977 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247319 | 1247319 | 755-1, 4, 94 |

**Name:** WEST HILL HOUSE

**Grade:** II* **Assigned:** 19/05/1950 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 MARKET HILL
755-1/4/94 (North side)
19/05/50 No.4 West Hill House
GV II*

**DesigUID:** DWI5977 **Name:** WEST HILL HOUSE

Includes: No.8 QUARR BARTON. Cottage and house, now office and flat. C17 rear cottage, incorporated into a later C17 central range, with a front range dated 1705. Limestone rubble with ashlar dressings, large left-hand rubble gable stack, right-hand ashlar stack, 2 right-hand lateral and rear gable stacks to rear range, pantile rear roof and slate front roof. L-shaped plan with 1705 parallel front range, left-hand C17 rear range, with an earlier single-room plan C17 cottage connected to the rear. 2 storeys, attic and cellar; 5-window front with 2-window left-hand return, and 1-storey and attic, 1-window range rear cottage. Principal front is symmetrical with quoins and a timber modillion cornice gutter, large rubble stack set in from the left-hand gable, and a ground-floor string. Timber bracketed pediment to a half-glazed door, and bolection-moulded architraves to early C19 6/6-pane sashes; 2 C19 gabled dormers. Good lead hopper and downpipe with joint clips inscribed H/IP/1705. Half-hipped gable of rear range rises above the ridge, with a C20 casement. Left-hand return has 2-window rear section set back with ground- and first-floor strings and coved cornice, with a late C19 ashlar porch in the angle; the right-hand side has a large lateral stack with a half gable, a first-floor window with label mould, and a straight joint with the front range. Rear cottage has timber lintel from earlier ground-floor window, exposed end of principal rafter, and later label moulds over the right-hand Tudor-arched door and 3-light mullion window with reserved chamfers; a C19 gabled casement dormer; rear elevation has a large lateral stack, and a wide right-hand C17 door. INTERIOR: details include an L-shaped cellar partly cut into bedrock, a heavy lateral beam with bracketed end supported by a turned timber post; a cyma-moulded mullion window to the side. Ground-floor left-hand room has a large fireplace with bressumer and left-hand niche, C17 scratch-moulded panelling; right-hand room with complete early C20 panelling and marble fireplace; central early C18 dogleg stair with column on vase balusters and uncut string; rear rooms with raised panelling. First floor has front room with early C18 panelling, overmantel and timber fire surround with fluted columns; right-hand stair, and rear bolection-moulded fireplaces. Rear cottage has a large fireplace, chamfered axial and lateral floor beams, inserted late C20 stair, and 2 sling-brace trusses, one set into the rear party wall with No.12 Quarr Barton (qv).
Listing NGR: ST9967271058

**Curatorial Notes**

Type and date: C17 HOUSE. Date: from 1600 to 1699
Type and date: Later C17 HOUSE. Date: from 1667 to 1699
Type and date: 1705 HOUSE. Date: 1705
Type and date: Now OFFICE.
Type and date: Now APARTMENT.
Type and date: 1705 RAINWATER HEAD. Date: 1705
Type and date: Late C19 HOUSE. Date: from 1867 to 1899
Main material: limestone
Main material: rubble
Main material: ashlar
Covering material: pantile
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99672 71058 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

Westhill House 4 Market Hill, Calne, Wiltshire, SN11 0BU

**Listed Building Addresses**

**DesigUID:** DWI5977 **Name:** WEST HILL HOUSE

Statutory
WEST HILL HOUSE

**Designation History**

**Assignment**
19/05/1950

**Sources - None recorded**

**Associated Monuments**

MWI36365 Building: West Hill House, 4 Market Hill

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456690

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI5993 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1270950 | 1270950 | 755-1, 5, 110 |

**Name:** WILTSHIRE COUNTY LIBRARY
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9970 NEW ROAD
755-1/5/110 (East side)
08/07/76 Wiltshire County Library
II
Library. c1904. Donated by Andrew Carnegie. Coursed, squared limestone rubble, limestone dressings, with slate hipped roof. Single-depth plan with rear wing. Eclectic Tudor and Jacobean Revival style. Single storey; 2-window range. Divided by octagonal panelled pilasters to onion finials, with a plinth, cornice and parapet with curved sunken cusped panels. A narrow right-hand bay, with the entrance to the left flanked by buttresses on foliate carved corbels and raised finials, to a round-arched entrance with raised voussoirs, foliate carved spandrels, and recessed 2-leaf door; a panel above with PUBLIC LIBRARY in raised letters, and a cartouche in the gable with Wiltshire coat of arms, and winged cupid. 3-light stone-mullioned and transomed ovolo-moulded cross windows with 9-pane top windows. Crested ridge with end finials. Rear 5-bay range has lunettes. INTERIOR: details include an arch-braced truss roof.
Listing NGR: ST9979770892

**Curatorial Notes**

Type and date: c1904 LIBRARY. Date: from 1894 to 1914
Type and date: PLAQUE.

**DesigUID:** DWI5993 **Name:** WILTSHIRE COUNTY LIBRARY

Main material: limestone
Main material: rubble
Covering material: slate

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99797 70892 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

New Road, Calne, Wiltshire, SN11 0JJ

**Listed Building Addresses**

Statutory
WILTSHIRE COUNTY LIBRARY

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36379 Building: Wiltshire County Library

**Associated Consultations - None**

**Additional Information**

**LBSUID:** 456740

**List Locality:**
**List Parish:** CALNE
**List District:** NORTH WILTSHIRE
**List County:** WILTSHIRE
**Group Value:** **Upload Date:** 15/06/2011

---

**DesigUID:** DWI6053 **Type:** Listed Building **Status:** Active

| NHLE number | NHLE number | Volume/Map/Item |
|---|---|---|
| 1247493 | 1247493 | 755-1, 4, 176 |

**Name:** ZION BAPTIST CHAPEL AND SCHOOL AND ZION CHAPEL
**Grade:** II **Assigned:** 08/07/1976 **Amended:** **Revoked:**

**Legal Description**

CALNE
ST9971 THE PIPPIN
755-1/4/176 (West side)
08/07/76 Zion Baptist Chapel and School
(Formerly Listed as: THE PIPPIN (West side) No.16)

**DesigUID:** DWI6053 **Name:** ZION BAPTIST CHAPEL AND SCHOOL AND ZION CHAPEL

(Formerly Listed as: THE PIPPIN (West side) Zion Chapel (Baptist))
II
Baptist chapel and school. Dated 1836; later school. Coursed, squared limestone rubble, limestone dressings, slate and pantile roof and brick lateral stack. Rectangular chapel with single-depth school room across E end. 2 storeys; 2-window range. Gabled entrance front has a moulded pediment and a late C20 gabled porch, with late C20 8/8-pane casement sashes. Former school attached to rear, has side and rear elevations have 8/8-pane sashes. INTERIOR: details of the chapel include a rear gallery on cast-iron posts, stairs with column newels and stick balusters, an octagonal pulpit and 2 open galleries behind to the school rooms with turned balusters. School altered, now meeting room.
Listing NGR: ST9982271170

**Curatorial Notes**

Type and date: 1836 BAPTIST CHAPEL. Date: 1836
Type and date: Later CHURCH SCHOOL. Date: from 1837
Type and date: Now MEETING HALL.
Main material: limestone
Main material: rubble
Covering material: slate
Covering material: pantile

**Designating Organisation:**

**Location**

**Grid Reference:** ST 99822 71170 (point)
**Map sheet:** ST97SE **Area (Ha):** 0.00

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Postal Addresses**

61 The Pippin, Calne, Wiltshire, SN11 8JG

**Listed Building Addresses**

Statutory
ZION BAPTIST CHAPEL AND SCHOOL
Statutory
ZION CHAPEL
Former Statutory
ZION CHAPEL (BAPTIST)

**Designation History**

**Assignment**
08/07/1976

**Sources - None recorded**

**Associated Monuments**

MWI36468 Building: Zion Baptist Chapel and School
ZION CHAPEL

**Associated Consultations - None**


**Additional Information**

**DesigUID:** DWI6053 **Name:** ZION BAPTIST CHAPEL AND SCHOOL AND ZION CHAPEL

| | |
|---|---|
| **LBSUID:** | 456993 |
| **List Locality:** | THE PIPPIN |
| **List Parish:** | CALNE |
| **List District:** | NORTH WILTSHIRE |
| **List County:** | WILTSHIRE |
| **Group Value:** | **Upload Date:** 15/06/2011 |

Wiltshire Council

# Archaeological Monuments for Former Co-op, Calne Wiltshire.
# Data from the Wiltshire and Swindon Historic Environment Record



# Wiltshire and Swindon HER Monument Full Report

**Former Co-op, Calne - Monuments Report**

Number of records: 57

For more details, please see the HER online at https://www.wiltshire.gov.uk/museums-history-heritage-archaeology-historic-environment-record

**Monument Number**
ST97SE400 - MWI5188

**Record Type**
Monument

**Site Name** Calne

Town having Saxon origins.

## Monument Types and Dates

TOWN (Early Medieval (Saxon) - 410 AD to 1065 AD)

## Description and Sources

### Description - None recorded

<1> **Gover, J. E. B. + Mawer, A. + Stenton, F. M.**, 1939, *English Place Name Society: The Place Names of Wiltshire, p.256* (Monograph). SWI12252.
Probable extent of Saxon settlement. Calnae AD997.
<2> 1998, *The Wiltshire Archaeological and Natural History Magazine - Volume 91 (master), p.154* (Serial). SWI995.
5th - 7th century pottery was found during an evaluation in 1996 on land to the rear of Church Street ST998708, thought to be associated with site clearance prior to building construction.
<3> **Pevsner, N. + Cherry, B.**, 1975, *The Buildings of England, Wiltshire (1975 Edition), pp.154-158* (Bibliographic reference). SWI16505.
<4> **Beamish, H.F.**, 1996, *Land at the Rear of Church Street, Calne* (Report). SWI23514.
<5> **Haslam, Jeremy**, 1984, *Anglo-Saxon Towns in Southern England, pp.102-106* (Bibliographic reference). SWI18246.
Anglo-Saxon settlement in Calne from documentary sources. By mid C9, Calne was a "villa regalis", the centre of a large royal estate and hundred, administered by a reeve. Probably also the site of a minster church (?C7-8 foundation).
<6> **Haslam, Jeremy + Edwards, Annette**, 1976, *Wiltshire Towns: The Archaeological Potential (master), pp.13-14 + p.76* (Bibliographic reference). SWI16785.
Saxon period in Calne, and recommendations for archaeological research.
<7> **Wilson, M.**, 1976, *The Archaeology of Anglo-Saxon England, p.90* (Monograph). SWI31451.
Reference in the Anglo-Saxon Chronicle to the upper floor of a C10 hall at Calne, which collapsed, killing several of the assembly.
<8> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 887778* (Digital archive). SWI29488.
<9> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 887779* (Digital archive). SWI29488.
(Sited to area around St Mary's church from authority and OS 1:10,560, 1960). Medieval settlement in Calne, from documentary evidence. Domesday borough, part in possession of king, part of church.

### Sources

(1) Monograph: Gover, J. E. B. + Mawer, A. + Stenton, F. M.. 1939. English Place Name Society: The Place Names of Wiltshire. Cambridge University Press. p.256

(2) Serial: 1998. The Wiltshire Archaeological and Natural History Magazine - Volume 91 (master). The Wiltshire Archaeological and Natural History Magazine. p.154

(3) Bibliographic reference: Pevsner, N. + Cherry, B.. 1975. The Buildings of England, Wiltshire (1975 Edition). pp.154-158

(4) Report: Beamish, H.F.. 1996. Land at the Rear of Church Street, Calne. Cotswold Archaeological Trust.

(5) Bibliographic reference: Haslam, Jeremy. 1984. Anglo-Saxon Towns in Southern England. pp.102-106

(6) Bibliographic reference: Haslam, Jeremy + Edwards, Annette. 1976. Wiltshire Towns: The Archaeological Potential (master). pp.13-14 + p.76

(7) Monograph: Wilson, M.. 1976. The Archaeology of Anglo-Saxon England. Methuen. p.90

(8) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 887778

(9) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 887779

**Associated resources - None recorded**

## Location

### National Grid Reference

| | | |
|---|---|---|
| Centred ST 9982 7102 (357m by 593m) | ST97SE | Dispersed |

### Administrative Areas

| | |
|---|---|
| Civil Parish | Calne, North Wiltshire, Wiltshire |

**Address/Historic Names - None recorded**

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM4 | Calne – Settlement Area | Active | DWI17302 |

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 887779 | Active |
| National Record of the Historic Environment to Historic Environment Records - 887778 | Active |
| SHINE Candidate (Probable) | Active |
| National Monuments Record - 017 | Active |
| Wiltshire SMR MapSMR - ST97SE400 | Active |

**Ratings and Scorings - None recorded**

## Land Use

### Associated Historic Landscape Character Records

HWI7764 Urban settlement - Terraced housing (Type Code: USE-TDHO)

HWI7947 Urban settlement - Terraced housing (Type Code: USE-TDHO)

HWI7949 Urban settlement - Detached housing (Type Code: USE-DTHO)

HWI7957 Urban settlement - Semi detached housing (Type Code: USE-SDHO)

**Monument Number** ST97SE400 - MWI5188

**Site Name** Calne

HWI7966 Urban settlement - Terraced housing (Type Code: USE-TDHO)
Broken Cross

HWI7967 Urban settlement - Terraced housing (Type Code: USE-TDHO)

HWI7970 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

HWI7971 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

## Other Land Classes

| | |
|---|---|
| Geology | Oxford Clay and Kellaway Beds |
| Landuse | Built Environment |

## Related Monuments - None Recorded

## Associated Finds

FWI11942 SHERD (Early Medieval (Saxon) - 410 AD to 1065 AD) (FWI11942) POTTERY

## Associated Events/Activities

EWI3225 Evaluation on Land at the Rear of Church Street, Calne (Interpretation)

## Associated Individuals/Organisations - None recorded

**Monument Number** ST97SE451 - MWI5191

**Site Name** Roman and Medieval Pottery, Site of Harris Bacon

| Monument Number | Record Type |
|---|---|
| ST97SE451 - MWI5191 | Find Spot |

**Site Name** Roman and Medieval Pottery, Site of Harris Bacon Factory

Roman and medieval pottery was recovered during construction of the power house at the Calne Bacon Factory in circa 1950.

## Monument Types and Dates

FINDSPOT (Medieval - 1066 AD to 1539 AD)

## Description and Sources

### Description - None recorded

<1> 1949-1950, *The Wiltshire Archaeological and Natural History Magazine - Volume 53 (master), p.394* (Serial). SWI938.
Several medieval objects and sherds.
<2> **Grinsell, L. V. + Hawkes, C. + Piggott, S.**, 1953, *Victoria County History Card Index* (Index). SWI30198.
<3> **Pugh, R. B. + Crittall, E. + Grinsell, L. V. + Gifford, J.**, 1957, *The Victoria County History of the Counties of England: A History of Wiltshire Vol.1.1 (master), p.54* (Serial). SWI13104.
<4> 1968, *Letter from R.J. Harris, Chilvester Lodge, Calne - 28.5.1968* (Correspondence). SWI31417.
<5> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212387* (Digital archive). SWI29488.
ST 998710. Among 'several objects, chiefly Medieval', found in digging for foundations at the Calne Bacon Factory were a flanged rim of New Forest ware and other R.B. pottery. The finds were presented to Devizes Museum by Mr. R.J. Harris. Mr. Harris says the finds were made c.1950, when digging the foundations for the power house which is at ST 99787101 and at the water oufall a few metres to the north. Finds not traceable in Devizes Museum.

### Sources

(1) Serial: 1949-1950. The Wiltshire Archaeological and Natural History Magazine - Volume 53 (master). The Wiltshire Archaeological and Natural History Magazine. p.394
(2) Index: Grinsell, L. V. + Hawkes, C. + Piggott, S.. 1953. Victoria County History Card Index.
(3) Serial: Pugh, R. B. + Crittall, E. + Grinsell, L. V. + Gifford, J.. 1957. The Victoria County History of the Counties of England: A History of Wiltshire Vol.1.1 (master). Oxford University Press. p.54
(4) Correspondence: 1968. Letter from R.J. Harris, Chilvester Lodge, Calne - 28.5.1968.
(5) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212387

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9978 7100 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

**Monument Number** ST97SE451 - MWI5191

**Site Name** Roman and Medieval Pottery, Site of Harris Bacon

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM15 | Calne – Roads | Active | DWI17313 |
| Extensive Urban Survey - COM8 | Calne – Market Place | Active | DWI17306 |

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 212387 | Active |
| SHINE Candidate (Unlikely) | Active |
| Wiltshire SMR MapSMR - ST97SE451 | Active |
| National Monuments Record - ST 97 SE 5 | Active |

### Ratings and Scorings

Condition Unknown

## Land Use

### Associated Historic Landscape Character Records

HWI7971 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes

| | |
|---|---|
| Geology | Coral Rag |
| Landuse | Built Environment |

### Related Monuments - None Recorded

### Associated Finds

| | | |
|---|---|---|
| FWI11945 | SHERD (Small quantity) (Roman to Medieval - 43 AD to 1539 AD) (FWI11945) | POTTERY |

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations

Quinnell, N. V. - Royal Commission on the Historical Monuments of England — Archaeological Field Investigator

**Monument Number** ST97SE458 - MWI5197

**Site Name** Medieval Pottery, Land off the Pippen

**Monument Number** | **Record Type**

ST97SE458 - MWI5197 | Find Spot

**Site Name** Medieval Pottery, Land off the Pippen

Four fragments of medieval pottery were found during an evaluation excavation in 1997.

## Monument Types and Dates

Associated finds (Medieval - 1066 AD to 1539 AD)

## Description and Sources

### Description - None recorded

<1> **Boismier, W.**, 1997, *Land off The Pippin, Calne* (Report). SWI23794.
Four residual sherds of pottery were found during an evaluation in 1997.

### Sources

(1) Report: Boismier, W.. 1997. Land off The Pippin, Calne. Wessex Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9980 7107 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM9 | Calne – Planned Settlement Area | Active | DWI17307 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - 7667 | Active |
| SHINE Candidate (Unlikely) | Active |
| Wiltshire SMR MapSMR - ST97SE458 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records

HWI7970 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes

Geology Coral Rag

### Related Monuments - None Recorded

### Associated Finds

FWI28450 SHERD (4) (Medieval - 1066 AD to 1539 AD) (FWI28450) POTTERY

### Associated Events/Activities

**Monument Number** ST97SE458 - MWI5197

**Site Name** Medieval Pottery, Land off the Pippen

EWI3565 Evaluation on Land off The Pippin, Calne (Intervention)

**Associated Individuals/Organisations - None recorded**

**Monument Number** ST97SE468 - MWI5206

**Site Name** Medieval Metal Working Site, Church Street

| Monument Number | Record Type |
|---|---|
| ST97SE468 - MWI5206 | Monument |

**Site Name** Medieval Metal Working Site, Church Street

By-products and waste material from medieval metal working associated with 12th-14th century pits and a ditch were excavated in 1996.

## Monument Types and Dates

INDUSTRIAL SITE (Medieval - 1066 AD to 1539 AD)

## Description and Sources

### Description - None recorded

<1> **Beamish, H.F.**, 1996, *Land at the Rear of Church Street, Calne* (Report). SWI23514.
A number of 12th-14th century pits and a ditch associated with metal working by-products and waste were found during an evaluation in 1996.
<2> 1998, *The Wiltshire Archaeological and Natural History Magazine - Volume 91 (master), p.154* (Serial). SWI995.

### Sources

(1) Report: Beamish, H.F.. 1996. Land at the Rear of Church Street, Calne. Cotswold Archaeological Trust.

(2) Serial: 1998. The Wiltshire Archaeological and Natural History Magazine - Volume 91 (master). The Wiltshire Archaeological and Natural History Magazine. p.154

### Associated resources - None recorded

## Location

### National Grid Reference

| | | |
|---|---|---|
| ST 9980 7080 (point) | ST97SE | Point |

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM10 | Calne – Organic Settlement Area | Active | DWI17308 |

### Other Statuses and Cross-References

| | |
|---|---|
| SHINE Candidate (Possible) | Active |
| Wiltshire SMR MapSMR - ST97SE468 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records

HWI7971 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes

Geology Oxford Clay and Kellaway Beds

**Monument Number** ST97SE468 - MWI5206

**Site Name** Medieval Metal Working Site, Church Street

**Related Monuments - None Recorded**

**Associated Finds**

| | | |
|---|---|---|
| FWI11950 | SHERD (FWI11950) | POTTERY |
| FWI11951 | WORKED OBJECT (FWI11951) | METAL |

**Associated Events/Activities**

EWI3225 Evaluation on Land at the Rear of Church Street, Calne (Interpretation)

**Associated Individuals/Organisations - None recorded**

**Monument Number** ST97SE527 - MWI5209

**Site Name** Probable 17th Century Meeting House, Wood Street

| Monument Number | Record Type |
|---|---|
| ST97SE527 - MWI5209 | Monument |

**Site Name** Probable 17th Century Meeting House, Wood Street

Site of a late 17th century Quaker meeting house, rebuilt in 1838 and converted to a shop in the mid 20th century. Also a burial ground.

## Monument Types and Dates

CEMETERY (1750 to 1867, Post Medieval - 1540 AD to 1900 AD)

FRIENDS MEETING HOUSE (Built 1838, Mid C19 - 1834 AD to 1866 AD)

Mid C19 - 1866 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> *Society of Friends Meeting Houses - WSRO 1699/104* (Map). SWI10612.
The site of a late 17th century Society of Friends (Quaker) Meeting House and burial ground.
<2> **Crowley, D. A. + Baggs, A. P. + Williamson + Freeman, J. + Smith, C.**, 2002, *The Victoria County History of the Counties of England: A History of Wiltshire Vol.17 (MASTER)* (Serial). SWI22225.
It was rebuilt in 1838 and converted to a shop since 1960.
<3> **Mumford, J.**, 2006, *9A Wood Street, Calne, Wiltshire* (Report). SWI25179.
During a watching brief undertaken in 2006 a number of graves and charnel pits of the Quaker's Burial ground dating to the 17th-19th centuries were uncovered.
<4> 2008, *The Wiltshire Archaeological and Natural History Magazine - Volume 101 (master), pp.275-276* (Serial). SWI26576.
<5> **Stell, Christopher; RCHME**, 1991, *An Inventory of Nonconformist Chapels and Meeting-Houses in South-West England, p.216* (Monograph). SWI19788.
Former friends meeting-house in Wood Street, built in 1838 with a burial ground to the rear. Ashlar front with moulded cornice, two sash windows to upper floor, central dorway between windows in rusticated lower stage replaced by shop front since 1960.
<6> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1487564* (Digital archive). SWI29488.

### Sources

(1) Map: Society of Friends Meeting Houses - WSRO 1699/104.

(2) Serial: Crowley, D. A. + Baggs, A. P. + Williamson + Freeman, J. + Smith, C.. 2002. The Victoria County History of the Counties of England: A History of Wiltshire Vol.17 (MASTER). Boydell & Brewer.

(3) Report: Mumford, J.. 2006. 9A Wood Street, Calne, Wiltshire. Oxford Archaeology.

(4) Serial: 2008. The Wiltshire Archaeological and Natural History Magazine - Volume 101 (master). The Wiltshire Archaeological and Natural History Magazine. pp.275-276

(5) Monograph: Stell, Christopher; RCHME. 1991. An Inventory of Nonconformist Chapels and Meeting-Houses in South-West England. p.216

(6) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1487564

### Associated resources - None recorded

## Location

**Monument Number** ST97SE527 - MWI5209

**Site Name** Probable 17th Century Meeting House, Wood Street

**National Grid Reference**
Centred ST 9976 7122 (36m by 14m) ST97SE Area

**Administrative Areas**
Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names - None recorded**

## Designations, Statuses and Scorings

**Associated Designations - None recorded**

**Other Statuses and Cross-References**

| | |
|---|---|
| NBR Index Number - 11252 | Active |
| National Monuments Record - ST 97 SE 107 | Active |
| SHINE Candidate (Probable) | Active |
| Wiltshire SMR MapSMR - ST97SE527 | Active |

**Ratings and Scorings**
Condition Buried

## Land Use

**Associated Historic Landscape Character Records**
HWI7970 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

**Other Land Classes**

| | |
|---|---|
| Geology | Corallian |
| Landuse | Built Environment |

**Related Monuments - None Recorded**

**Associated Finds**
FWI11952 HUMAN REMAINS (FWI11952)

**Associated Events/Activities**
EWI6733 Watching Brief at 9A Wood Street, Calne (Intervention)

**Associated Individuals/Organisations - None recorded**

**Monument Number** ST97SE552 - MWI5214

**Site Name** Undated Bones, North East of St. Mary's Church

| Monument Number | Record Type |
|---|---|
| ST97SE552 - MWI5214 | Find Spot |

**Site Name** Undated Bones, North East of St. Mary's Church

Excavation in 1989 revealed redeposited ground containing an assortment of human bones.

## Monument Types and Dates

Associated finds (Undated)

INHUMATION (Undated)

Unknown

Evidence SUB SURFACE DEPOSIT

## Description and Sources

### Description - None recorded

<1> 1991, *The Wiltshire Archaeological and Natural History Magazine - Volume 84 (master), p.143* (Serial). SWI988.
Excavation in 1989 by Wiltshire Rescue Archaeology Programme Unit, prior to demolition and rebuilding of a wall adjacent to a footpath, revealed redeposited ground containing an assortment of human bones. Saxon burials have previously been found close to this area.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1193111* (Digital archive). SWI29488.
During wall rebuilding adjacent to a footpath north-east of the church, a confused jumble of assorted human bones was discovered in redeposited ground. Other masses of confused bone jumbles have been found in Calne, (see SU 07 SW 18).

### Sources

(1) Serial: 1991. The Wiltshire Archaeological and Natural History Magazine - Volume 84 (master). The Wiltshire Archaeological and Natural History Magazine. p.143

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1193111

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9991 7091 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM1 | Calne – Church | Active | DWI17299 |
| Extensive Urban Survey - COM7 | Calne – Parish Church | Active | DWI17305 |

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 1193111 | Active |
| National Monuments Record - ST 97 NW 41 | Active |
| SHINE Candidate (Unlikely) | Active |
| Wiltshire SMR MapSMR - ST97SE552 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records**

HWI7971 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

**Other Land Classes**

Geology Corallian

**Related Monuments - None Recorded**

**Associated Finds**

FWI11957 HUMAN REMAINS (FWI11957)

**Associated Events/Activities**

EWI11191 Excavation of Undated Bones, North East of St. Mary's Church (Intervention)

**Associated Individuals/Organisations - None recorded**

**Monument Number** ST97SE553 - MWI5215

**Site Name** Undated Burial, Church Street

**Monument Number**
ST97SE553 - MWI5215

**Record Type**
Monument

**Site Name** Undated Burial, Church Street

An undated, but Christian burial found during groundworks associated with pavement renewal in 1997, and subsequently excavated.

## Monument Types and Dates

BURIAL (Undated)

## Description and Sources

### Description - None recorded

<1> **AC Archaeology**, 1997, *An Archaeological Watching Brief at Church Street, Calne* (Report). SWI23722.
The partial remains of a single burial were exposed and recorded, and an earlier graveyard boundary noted to the north of the burial. There are indication of more burials, probably from the medieval period onwards.

### Sources

(1) Report: AC Archaeology. 1997. An Archaeological Watching Brief at Church Street, Calne. AC Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

| | | |
|---|---|---|
| ST 9986 7091 (point) | ST97SE | Point |

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM1 | Calne – Church | Active | DWI17299 |
| Extensive Urban Survey - COM7 | Calne – Parish Church | Active | DWI17305 |

### Other Statuses and Cross-References

| | |
|---|---|
| SHINE Candidate (Possible) | Active |
| Wiltshire SMR MapSMR - ST97SE553 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records

HWI7971 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes

Geology Coral Rag

**Monument Number** ST97SE553 - MWI5215

**Site Name** Undated Burial, Church Street

**Related Monuments - None Recorded**

**Associated Finds**

FWI11958 HUMAN REMAINS (FWI11958)

**Associated Events/Activities**

EWI3567 Watching Brief at Church Street, Calne (Intervention)

**Associated Individuals/Organisations - None recorded**

**Monument Number** ST97SE554 - MWI5216

**Site Name** Probable Medieval Burial Ground, The Old Vicarage,

| Monument Number | Record Type |
|---|---|
| ST97SE554 - MWI5216 | Monument |

**Site Name** Probable Medieval Burial Ground, The Old Vicarage, Mill St/Anchor Rd

A burial ground consisting of six burials and partial remains of three others. Possibly associated with medieval monastic lodge or retreat.

## Monument Types and Dates

CEMETERY (Medieval - 1066 AD to 1539 AD)

## Description and Sources

### Description - None recorded

<1> **McMahon, Phillip**, 2002, *Note on Human Burials at the Old Vicarage, Mill Street/Anchor Road, Calne* (Unassigned). SWI24491.
A burial ground consisting of six burials and partial remains of at least three others was discovered during construction of a garage. The six burials were discovered in the south west facing section of the cut for the new garage but were not removed, and were instead preserved in situ (either within the garage retaining wall, below floor level, or behind the garden retaining wall at the mouth of the garage). The three partial skeletons had been disturbed by the groundworks and were re-buried on site underneath the garage. The site is known to have been the location of a monastic lodge or retreat since the 13th century and has documented associations with St Edmund so the burials could be interpreted as belonging to the medieval period.

### Sources

(1) Unassigned: McMahon, Phillip. 2002. Note on Human Burials at the Old Vicarage, Mill Street/Anchor Road, Calne.

### Associated resources - None recorded

## Location

### National Grid Reference

| | | |
|---|---|---|
| ST 9998 7098 (point) | ST97SE | Point |

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM13 | Calne – Rectory | Active | DWI17311 |

### Other Statuses and Cross-References

| | |
|---|---|
| SHINE Candidate (Probable) | Active |
| Wiltshire SMR MapSMR - ST97SE554 | Active |

### Ratings and Scorings

Condition Buried

## Land Use

### Associated Historic Landscape Character Records

HWI7764 Urban settlement - Terraced housing (Type Code: USE-TDHO)

**Monument Number** ST97SE554 - MWI5216

**Site Name** Probable Medieval Burial Ground, The Old Vicarage,

**Other Land Classes**

| | |
|---|---|
| Geology | Cornbrash |
| Landuse | Built Environment |

**Related Monuments - None Recorded**

**Associated Finds**

FWI11959 HUMAN REMAINS (FWI11959)

**Associated Events/Activities**

EWI9423 Excavations at The Old Vicarage, Mill Street/Anchor Road (Intervention)

**Associated Individuals/Organisations**

| | |
|---|---|
| Wiltshire County Archaeology Service | Recorder |

**Monument Number**
SU07SW459 - MWI9207

**Record Type**
Monument

**Site Name** Colemans Farm

Farmstead with medieval origins.

## Monument Types and Dates

SETTLEMENT (Medieval - 1066 AD to 1539 AD)

## Description and Sources

### Description - None recorded

<1> **Gover, J. E. B. + Mawer, A. + Stenton, F. M.**, 1939, *English Place Name Society: The Place Names of Wiltshire, p.259* (Monograph). SWI12252.
Associated with William Colman AD1547.

### Sources

(1) Monograph: Gover, J. E. B. + Mawer, A. + Stenton, F. M.. 1939. English Place Name Society: The Place Names of Wiltshire. Cambridge University Press. p.259

### Associated resources - None recorded

## Location

### National Grid Reference

Centred SU 0009 7114 (52m by 61m) SU07SW Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References

| | |
|---|---|
| SHINE Candidate (Probable) | Active |
| Wiltshire SMR MapSMR - SU07SW459 | Active |

### Ratings and Scorings

Condition Buried

## Land Use

### Associated Historic Landscape Character Records

HWI7764 Urban settlement - Terraced housing (Type Code: USE-TDHO)

### Other Land Classes

| | |
|---|---|
| Geology | Corallian |
| Landuse | Built Environment |

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

**Monument Number** SU07SW459 - MWI9207

**Site Name** Colemans Farm

**Associated Individuals/Organisations - None recorded**

**Monument Number** SU07SW468 - MWI9216

**Site Name** Possible Medieval Site, The Vicarage, Mill St/Anchor

| Monument Number | Record Type |
|---|---|
| SU07SW468 - MWI9216 | Monument |

**Site Name** Possible Medieval Site, The Vicarage, Mill St/Anchor Rd

Probably the site of a 13th century monastic lodge or retreat associated with St Edmund of Canterbury

## Monument Types and Dates

RETREAT (Medieval - 1066 AD to 1539 AD)

VICARAGE (C20 - 1901 AD to 2000 AD)

C20 - 2000 AD

## Description and Sources

### Description - None recorded

<1> **Marsh, A E W**, 1903, *A History of the Borough and Town of Calne* (Monograph). SWI11540. The land now occupied by The Vicarage, may be the location of the ancient rectory, in existence since at least 1234, when St. Edmund of Canterbury is known to been residing there at the time of his selection for the Archbishopric of Canterbury. (See ST97SE554)
<2> **McMahon, Phillip**, 2002, *Note on Human Burials at the Old Vicarage, Mill Street/Anchor Road, Calne* (Unassigned). SWI24491.

### Sources

(1) Monograph: Marsh, A E W. 1903. A History of the Borough and Town of Calne.

(2) Unassigned: McMahon, Phillip. 2002. Note on Human Burials at the Old Vicarage, Mill Street/Anchor Road, Calne.

### Associated resources - None recorded

## Location

### National Grid Reference

| | | |
|---|---|---|
| SU 0002 7098 (point) | SU07SW | Point |

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM13 | Calne – Rectory | Active | DWI17311 |

### Other Statuses and Cross-References

| | |
|---|---|
| SHINE Candidate (Possible) | Active |
| Wiltshire SMR MapSMR - SU07SW468 | Active |

### Ratings and Scorings

Condition Buried

## Land Use

### Associated Historic Landscape Character Records

HWI7764 Urban settlement - Terraced housing (Type Code: USE-TDHO)

### Other Land Classes

**Monument Number** SU07SW468 - MWI9216

**Site Name** Possible Medieval Site, The Vicarage, Mill St/Anchor

| | |
|---|---|
| Geology | Cornbrash |
| Landuse | Built Environment |

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** SU07SW525 - MWI9217

**Site Name** Former 16th/17th Century Cemetery, The Vicarage

| Monument Number | Record Type |
|---|---|
| SU07SW525 - MWI9217 | Monument |

**Site Name** Former 16th/17th Century Cemetery, The Vicarage

Post medieval burials.

### Monument Types and Dates

CEMETERY (16th/17th Century, Medieval to Late C17 - 1066 AD to 1700 AD)
Medieval - C17
HUMAN REMAINS (16th/17th Century, Medieval to Late C17 - 1066 AD to 1700 AD)
Medieval - C17
INHUMATION (16th/17th Century, Medieval to Late C17 - 1066 AD to 1700 AD)
Medieval - C17

### Description and Sources

**Description - None recorded**

<1> **Marsh, A E W**, 1904, *History of the Borough and Town of Calne - 1904* (Bibliographic reference). SWI11552.
A triangular piece of ground opposite the vicarage at Calne is traditionally the burial place of 16/17th c plague victims. About 1834 the ground was found to contain a large number of human skeletons in unconnected and confused heaps.
<2> **Reynolds, A. J. + Wilkinson, K. N.**, 1990, *The Compton Bassett Area Research Project: A Research Design* (Report). SWI22679.
<3> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 216480* (Digital archive). SWI29488.
The tradition seems to have died but the triangular plot was evidently that shown on the O.S.25" 2nd Edn., at SU 0001 7094. This is now partly built over (Field Investigators Comments: F1 NVQ 13-FEB-68).

**Sources**

(1) Bibliographic reference: Marsh, A E W. 1904. History of the Borough and Town of Calne - 1904.
(2) Report: Reynolds, A. J. + Wilkinson, K. N.. 1990. The Compton Bassett Area Research Project: A Research Design. Institute of Archaeology.
(3) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 216480

**Associated resources - None recorded**

### Location

**National Grid Reference**

| | | |
|---|---|---|
| SU 0000 7093 (point) | SU07SW | Point |

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names - None recorded**

### Designations, Statuses and Scorings

**Associated Designations - None recorded**

**Monument Number** SU07SW525 - MWI9217

**Site Name** Former 16th/17th Century Cemetery, The Vicarage

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 216480 | Active |
| SHINE Candidate (Probable) | Active |
| Wiltshire SMR MapSMR - SU07SW525 | Active |
| National Monuments Record - SU 07 SW 18 | Active |

### Ratings and Scorings

| | |
|---|---|
| Condition | Buried |
| Condition | Damaged |

## Land Use

### Associated Historic Landscape Character Records

HWI7967 Urban settlement - Terraced housing (Type Code: USE-TDHO)

### Other Land Classes

| | |
|---|---|
| Geology | Corallian |
| Landuse | Built Environment |

### Related Monuments - None Recorded

### Associated Finds

FWI15571 HUMAN REMAINS (Post Medieval - 1540 AD to 1900 AD) (FWI15571)

### Associated Events/Activities

EWI11003 RCHME: Avebury World Heritage Site Project (Survey)

### Associated Individuals/Organisations

| | |
|---|---|
| Quinnell, Norman Victor - RCHME | Compiler |
| Woodhouse, William C. - Ordnance Survey | Compiler |

**Monument Number** MWI31409

**Site Name** Probable Post Medieval Well, The Pippin, Calne

**Monument Number** **Record Type**

MWI31409 Monument

**Site Name** Probable Post Medieval Well, The Pippin, Calne

A probable post medieval well was encountered during an archaeological watching brief.

## Monument Types and Dates

WELL (Post Medieval - 1540 AD to 1900 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Reynish, S.**, 2008, *Phelps Parade, Calne, Wiltshire, p.7* (Report). SWI25476.
A probable post medieval well was encountered during an archaeological watching brief. This was of drystone wall construction and filled with grey clayey silt.

### Sources

(1) Report: Reynish, S.. 2008. Phelps Parade, Calne, Wiltshire. Cotswold Archaeology. p.7

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9980 7122 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References

SHINE Candidate (Possible) Active

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records

HWI7970 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI6972 Watching Brief at Phelps Parade, Calne (Intervention)

### Associated Individuals/Organisations - None recorded

**Monument Number** MWI33730

**Site Name** Calne Town Hall

| Monument Number | Record Type |
|---|---|
| MWI33730 | Building |

**Site Name** Calne Town Hall

Town hall, c1884-1886 in Tudor Revival style.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

TOWN HALL (Built 1884-1886, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995* (Scheduling record). SWI20967.
Town hall built circa 1884-1886 by Oliver. The Tudor Revival style building has an irregular plan and is of two storeys, with an attic. The building is of squared, coursed limestone rubble with a slate roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1371894* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995.

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1371894

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9973 7096 (15m by 24m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

TOWN HALL, THE STRAND

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Listed Building (II) - 1270827 | TOWN HALL | Active | DWI6057 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF108081 | Active |
| NBR Index Number - 108081 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1371894 | Active |
| National Monuments Record - ST 97 SE 98 | Active |

### Ratings and Scorings - None recorded

**Monument Number** MWI33730

**Site Name** Calne Town Hall

**Land Use**

Associated Historic Landscape Character Records - None recorded

Other Land Classes - None recorded

Related Monuments - None Recorded

Finds - None recorded

Associated Events/Activities - None recorded

Associated Individuals/Organisations - None recorded

**Monument Number** MWI36364

**Site Name** 3 Market Hill

**Monument Number**
MWI36364

**Record Type**
Building

**Site Name** 3 Market Hill

Dated 1683, restored c1980.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Late C17 - 1667 AD to 1700 AD)
Late C17 - 1700 AD
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976* (Scheduling record). SWI31442.
Mid C17, altered. 3 storeys, 3 windows. Hipped stone slate roof renewed C18/C19. Limestone rubble with long and short dressings to quoins. Cement rendered finish. Bolection moulded eaves cornice. Weathered string at 2nd floor level. 2nd floor with original mullioned and transomed casement windows of 2 lights with stone mouldings. Late C18 architraved 1st floor sash windows with exposed boxing and glazing bars. Mid C19 ground floor sash windows with wooden lintels. Original, square-headed stone doorway with moulded surround, C19 wooden bracketed hood and panelled door approached by step. West return to Castle Street with mullioned and transomed windows to 1st and 2nd floor with hoodmoulds. South facade with original moulded mullioned and transomed windows with 3:2:3 lights to 1st and 2nd floor; ground floor with C18 painted sash windows flanking central entrance with bolection moulded architraves, glazing bars and hood moulds. Square-headed, bolection moulded architrave to panelled ground floor door, with weathered string ramped up over to join hood mould. Below 2nd floor window slate sundial attached to wall inscribed `AE 183? RE'. Interior with good original open well staircase rising full height of house with square, panelled newels, closed moulded string and handrail, and carved balusters. Original oak floors and door surrounds. Some renewed panelling to ground floor rooms with boxed-out cornices. 1st and 2nd floor rooms with some original stone chimney pieces with bolection mouldings. Nos 1 to 3 (consec) form a group with No 6 High Street.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212458* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976.
(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212458

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9968 7104 (19m by 12m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

**Monument Number** MWI36364

**Site Name** 3 Market Hill

3, MARKET HILL

## Designations, Statuses and Scorings

### Associated Designations

| | | |
|---|---|---|
| Listed Building (II*) - 1247318 | Active | DWI5976 |

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 212458 | Active |
| National Monuments Record - ST 97 SE 32 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations - None recorded

**Monument Number** MWI36365

**Site Name** West Hill House, 4 Market Hill

| Monument Number | Record Type |
|---|---|
| MWI36365 | Building |

**Site Name** West Hill House, 4 Market Hill

Circa 1705 town house.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Early C18 - 1701 AD to 1733 AD)

Early C18 - 1733 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976, pp.39-40* (Scheduling record). SWI31442.
Circa 1705 town house. 2 storeys and dormers. Double fronted with 5 windows. Welsh slate roof with 2 gabled dormers. Moulded gable ashlar stacks. Ridge is intersected by 1/2 hipped gable end of rear wing. Painted limestone rubble with ashlar dressings to quoins. Moulded wooden modillion cornice. Weathered 1st floor string. Slightly recessed, architraved sash windows with glazing bars. Wooden doorcase with square-headed architraved doorway with bracketed pediment and 1/2 glazed door approached by 7 steps. Original lead rainwater head and pipe with joint clips inscribed 'H.I.P. 1705'. South return to Quarrbarton Street. 3 storeys and gabled dormer. Ashlar stacks. Pantile roof. Painted limestone random rubble with ashlar dressings to quoins. Weathered strings at floor levels. Wooden, moulded cavetto cornice. Slightly recessed windows with oak lintols, architraves and glazing bars. Rear entrance with semi-elliptical door head and fanlight. Earlier C19 porch with semi-elliptical arches, cornice and modern 1st floor addition. At rear C18 cottage. 1 storey and gabled dormer. 1 window. Pantile roof. Painted limestone rubble. Original openings with wooden lintols blocked and replaced by earlier C19 window and doorway in C17 manner. 3 light window with mullions and dripmould. Doorway with chamfered reveal, semi-elliptical head and dripmoulds, plank and batten door approached by step. (See also No 12 Quarrbarton Street adjoining.) Interior of main building Ground floor front room with later C19 panelling and wide stone fireplace with oak lintol and stone reveals. Oak ceiling beams with bracketed ends. Back ground floor room with raised and fielded panelled dado and cupboards flanking former fireplace. Good 1st floor front room with raised and fielded panellingand boxed out cornice; period fireplace inserted. Original oak floor boards. 1st floor back room with original stone chimneypiece with mantle. Upper part of house still retains twisted balusters from original staircase. Nos 4 and 5 Market Hill form a group with No 12 Quarrbarton Street.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212459* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976. pp.39-40

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212459

### Associated resources - None recorded

## Location

**Monument Number** MWI36365

**Site Name** West Hill House, 4 Market Hill

**National Grid Reference**

Centred ST 9966 7105 (23m by 15m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names**

WEST HILL HOUSE, 4, MARKET HILL

## Designations, Statuses and Scorings

**Associated Designations**

| | | | |
|---|---|---|---|
| Listed Building (II*) - 1247319 | WEST HILL HOUSE | Active | DWI5977 |

**Other Statuses and Cross-References**

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 212459 | Active |
| National Monuments Record - ST 97 SE 33 | Active |

**Ratings and Scorings - None recorded**

## Land Use

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36371

**Site Name** Calne Free Church, Church Street

**Monument Number** **Record Type**

MWI36371 Building

**Site Name** Calne Free Church, Church Street

Church of 1867 by W Stent of Warminster. The church was built under the patronage of the Harris family (local wholesale butchers).
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

NONCONFORMIST CHURCH (Built 1867, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Stell, Christopher; RCHME**, 1991, *An Inventory of Nonconformist Chapels and Meeting-Houses in South-West England, p.216* (Monograph). SWI19788.
Independent chapel formed by seceders from the parish church having a Congregational minister as its first pastor. By W Stent of Warminster in 1867. Squared, rusticated limestone with ashlar dressings and quoins, crested plain tile roof. Rectangular plan with bell tower to the front left (north-west); north aisle with higher north transept extending to the line of the aisle (no south aisle) and angled buttresses. Gothic Revival Middle Pointed style.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1487553* (Digital archive). SWI29488.

### Sources

(1) Monograph: Stell, Christopher; RCHME. 1991. An Inventory of Nonconformist Chapels and Meeting-Houses in South-West England. p.216

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1487553

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9985 7100 (22m by 29m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

CALNE FREE CHURCH, CHURCH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1247331 CALNE FREE CHURCH Active DWI5983

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 1487553 | Active |
| National Monuments Record - ST 97 SE 106 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36377

**Site Name** Kerry Crescent

**Monument Number**
MWI36377

**Record Type**
Building

**Site Name** Kerry Crescent

A terrace of three houses built in the 1870s in Free Tudor and Jacobean Revival style.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

TERRACED HOUSE (Built 1870s, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995* (Scheduling record). SWI20967.
A terrace of three houses built in the 1870s. The Free Tudor and Jacobean Revival style buildings are of two storeys and have a double-depth plan. Built of coursed, squared limestone rubble with ashlar dressings and a hipped, pantile roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1371888* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995.

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1371888

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9980 7084 (27m by 30m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

KERRY CRESCENT, 1,2 AND 3, NEW ROAD

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Listed Building (II) - 1247328 | KERRY CRESCENT | Active | DWI5990 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF108080 | Active |
| NBR Index Number - 108080 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1371888 | Active |
| National Monuments Record - ST 97 SE 97 | Active |

**Monument Number** MWI36377

**Site Name** Kerry Crescent

Ratings and Scorings - None recorded

**Land Use**

Associated Historic Landscape Character Records - None recorded

Other Land Classes - None recorded

Related Monuments - None Recorded

Finds - None recorded

Associated Events/Activities - None recorded

Associated Individuals/Organisations - None recorded

**Monument Number** MWI36378

**Site Name** Marden House Centre

| Monument Number | Record Type |
|---|---|
| MWI36378 | Building |

**Site Name** Marden House Centre

Former canal building, once the headquarters of the Canal Company, situated at the termination of the Calne branch of the Wilts & Berks Canal. Now a community centre.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

COMMUNITY CENTRE (Converted, Late 20th Century - 1988 AD)

1988 AD

Evidence EXTANT BUILDING

(Former Type) WATERMILL (Early C19 - 1801 AD to 1833 AD)

Early C19 - 1833 AD

Evidence RUINED BUILDING

Main Building Material RUBBLE

(Former Type) OFFICE (Early C19 to Mid C19 - 1801 AD to 1866 AD)

Early C19 - Mid C19

Evidence EXTANT BUILDING

Main Building Material ASHLAR

(Former Type) OFFICE (Early C19 to Mid C19 - 1801 AD to 1866 AD)

Early C19 - Mid C19

Evidence EXTANT BUILDING

Main Building Material ASHLAR

(Former Type) WHARFINGERS COTTAGE (Early C19 to Mid C19 - 1801 AD to 1866 AD)

Early C19 - Mid C19

Evidence EXTANT BUILDING

Main Building Material RUBBLE

## Description and Sources

### Description - None recorded

<1> **Slocombe, P.**, 2008, *A Guide to the Industrial Archaeology of Wiltshire, p.15* (Booklet). SWI28692.
End of the former Calne branch of the Wilts & Berks Canal which linked with the canalised River Marden in 1801. Marden House is in three sections: the rubble stone remains of a water mill at the river end; an ashlar stone central section, headquarters of the Canal Company and stores; and coursed rubble western section, the wharfinger's house, dating from the period 1830-1860. Beyond is a single storey stable block. Whole building converted to a community centre in 1988. The canal basin was to the south of the buildings and the wharf to the north.

### Sources

(1) Booklet: Slocombe, P.. 2008. A Guide to the Industrial Archaeology of Wiltshire. Association for Industrial Archaeology. p.15

**Monument Number** MWI36378

**Site Name** Marden House Centre

**Associated resources - None recorded**

**Location**

**National Grid Reference**

Centred ST 9972 7084 (28m by 8m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names**

MARDEN HOUSE CENTRE, NEW ROAD

**Designations, Statuses and Scorings**

**Associated Designations**

| | | | |
|---|---|---|---|
| Listed Building (II) - 1247334 | MARDEN HOUSE CENTRE | Active | DWI5992 |

**Other Statuses and Cross-References - None recorded**

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36379

**Site Name** Wiltshire County Library

**Monument Number**
MWI36379

**Record Type**
Building

**Site Name** Wiltshire County Library

Library c1904, donated by Andrew Carnegie. Since 2004 it has been the location of the Calne Heritage Centre
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

LIBRARY (Built 1904-1905, Edwardian - 1902 AD to 1910 AD)

Edwardian - 1910 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.80* (Scheduling record). SWI20967. Library built 1904-5, donated by Andrew Carnegie. Built of coursed, squared limestone rubble with limestone dressings and a slate roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544373* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.80

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544373

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9978 7088 (25m by 16m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

Calne Heritage Centre

WILTSHIRE COUNTY LIBRARY, NEW ROAD

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1270950 WILTSHIRE COUNTY LIBRARY Active DWI5993

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086326 | Active |
| NBR Index Number - 86326 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544373 | Active |
| National Monuments Record - ST 97 SE 80 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36386

**Site Name** 2 - 3 Patford Street

**Monument Number**
MWI36386

**Record Type**
Building

**Site Name** 2 - 3 Patford Street

Early-mid C17, altered. Formerly a double fronted house, later converted into 2 cottages.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Early C17 to Mid C17 - 1601 AD to 1666 AD)

Early C17 - Mid C17

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976, pp.46-47* (Scheduling record). SWI31442.
Earlier-mid C17, altered. Formerly a double fronted house, later converted into 2 cottages. 2 storeys and attic. Pantile roof with altered gable stacks. Gabled dormers. Random limestone rubble with cement rendered front. Boxed out eaves. Original splayed bays flanking former central entrance; 1st floor with small consoles bracketting hood board; ovolo transom and mullion windows altered. Original central doorway replaced by modern window. Modern rear extensions. Original roof trusses and purlins. No 3 with good interior features. 1st floor room with chamfered ceiling beam with carved stops. Window stops. Window bay with panelled reveals and moulded ledge; panelled double doors with wrought iron door hinges and panel door hinges and panel above with carved cornice; original fireplace blocked, but retains salt cupboard with part of panelled surround and cornice. Original oak floors to 1st floor and attic. Ground floor front room with cornice and chamfered ceiling beam with stopped ends. Nos 2 and 3 form part of No .Listed II* for interior features. Nos 1 to 3 (consec) and Calne Municipal Offices. Form a group.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212462* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976. pp.46-47

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212462

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9970 7096 (11m by 11m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

2 AND 3, PATFORD STREET

## Designations, Statuses and Scorings

**Monument Number** MWI36386

**Site Name** 2 - 3 Patford Street

**Associated Designations**

| | | |
|---|---|---|
| Listed Building (II) - 1247340 | Active | DWI6000 |

**Other Statuses and Cross-References**

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 212462 | Active |
| National Monuments Record - ST 97 SE 36 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36417

**Site Name** 41 Church Street

**Monument Number**
MWI36417

**Record Type**
Building

**Site Name** 41 Church Street

Vicarage of early 17th century origin but largely of a mid to late 19th century build. Some original features were destroyed in 1948-1961 when the building became a Masonic Hall.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

VICARAGE (Early C17 - 1601 AD to 1633 AD)
Early C17 - 1633 AD
Evidence EXTANT BUILDING
HOUSE (Rebuilt, Mid C19 to Late C19 - 1834 AD to 1900 AD)
Mid C19 - Late C19
Evidence EXTANT BUILDING
FREEMASONS HALL (Mid 20th Century - 1933 AD to 1966 AD)
Mid 20th Century - 1966 AD
Evidence EXTANT BUILDING
SERVICES CLUB (Mid 20th Century to Late 20th Century - 1933 AD to 2000 AD)
Mid 20th Century - Late 20th Century
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976, p.9* (Scheduling record). SWI31442.
Mid-later C19. 2 storeys. 3 window bays. Pantile roof with large stone gable stack at south end with red brick addition. Coursed limestone rubble with limewashed front. Central splayed bay rising full height of building with 5 light windows to each floor with ovolo transom and mullions, and leaded lights; ground floor window with hood mould. Flanking bays with 2 light windows, those at south end with transoms. Original doorway at north end with semi-elliptical arched head, chamfered reveals and studded boarded door with original hinges. Masonic monogram over door head. Rear facade irregular with dormers and 3 light windows with ovolo mullions and hood moulds; some windows with oak lintels. Gable wall with 4 tier openings to former pigeon loft. Large stone chimney with red brick diagonal stacks added. Modern side entrance with concrete lintel. Interesting interior with 3 original chimney pieces with moulded/chamfered depressed arches. Chamfered ceiling beams with tongue-stopped ends and some original oak flooring. Some original boarded doors with wrought iron fittings. The original staircase and arched entrance were destroyed circa 1948-61. Original timber roof. The building is said to have been the former vicarage of St Mary's Church. The 1st floor front room is reputed to be haunted by the ghost of a priest. Nos 31 and 31A, 37, 39 to 43 (consec) and 50 to 58 (consec) Church Street form a group, of which Nos 31, 31A and 50 to 58 (consec) are buildings of local interest.
<2> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.22* (Scheduling record). SWI20967.
<3> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212452* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976. p.9

(2) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.22

(3) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212452

**Associated resources - None recorded**

## Location

**National Grid Reference**

Centred ST 9984 7082 (35m by 18m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names**

RAF CLUB, 41, CHURCH STREET

St Edmunds Masonic Lodge

## Designations, Statuses and Scorings

**Associated Designations**

| | | | |
|---|---|---|---|
| Listed Building (II*) - 1247102 | RAF CLUB | Active | DWI5924 |

**Other Statuses and Cross-References**

| | |
|---|---|
| English Heritage Archives - BF083094 | Active |
| NBR Index Number - 83094 | Active |
| National Record of the Historic Environment to Historic Environment Records - 212452 | Active |
| National Monuments Record - ST 97 SE 26 | Active |

**Ratings and Scorings - None recorded**

## Land Use

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36418

**Site Name** 42 and 43, Church Street

**Monument Number**
MWI36418

**Record Type**
Building

**Site Name** 42 and 43, Church Street

A pair of attached houses, built in the late 18th century.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Late C18 - 1767 AD to 1800 AD)
Late C18 - 1800 AD
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976* (Scheduling record). SWI31442.
A Grade II listed building at ST9970. A pair of attached houses, built in the late 18th century. In the late 19th century, a shop front was added to number 43. The building is constructed of limestone rubble to double depth plan, with brick quoins to window and door openings. The roof is of pantiles.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1367815* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976.
(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1367815

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9984 7081 (31m by 20m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

42 AND 43, CHURCH STREET

## Designations, Statuses and Scorings

### Associated Designations

| | | |
|---|---|---|
| Listed Building (II) - 1246443 | Active | DWI5925 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF107671 | Active |
| NBR Index Number - 107671 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1367815 | Active |
| National Monuments Record - ST 97 SE 92 | Active |

**Monument Number** MWI36418

**Site Name** 42 and 43, Church Street

Ratings and Scorings - None recorded

**Land Use**

Associated Historic Landscape Character Records - None recorded

Other Land Classes - None recorded

Related Monuments - None Recorded

Finds - None recorded

Associated Events/Activities - None recorded

Associated Individuals/Organisations - None recorded

**Monument Number** MWI36419

**Site Name** 44 and 45, Church Street

**Monument Number**
MWI36419

**Record Type**
Building

**Site Name** 44 and 45, Church Street

A pair of attached houses. Number 44 was built in the early 19th century and number 45 was built in the mid 19th century, when number 44 was altered.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Early C19 to Mid C19 - 1801 AD to 1866 AD)

Early C19 - Mid C19

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976* (Scheduling record). SWI31442.
A Grade II Listed Building at ST9970. A pair of attached houses, number 44 was built in the early 19th century, number 45 was built in the mid 19th century, when number 44 was altered. The building is constructed of coursed limestone rubble, on a double depth plan with a slate roof. Number 44 has ashlar quoins to the left side.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1367821* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976.

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1367821

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9986 7080 (17m by 16m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

44 AND 45, CHURCH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1271047 Active DWI5926

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF107671 | Active |
| NBR Index Number - 107671 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1367821 | Active |
| National Monuments Record - ST 97 SE 93 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36420

**Site Name** Church of St Mary

| Monument Number | Record Type |
|---|---|
| MWI36420 | Building |

**Site Name** Church of St Mary

Norman church with later alterations and additions, and mainly perpendicular exterior.
For full details of this building, please check the Listed Building description.

### Monument Types and Dates

PARISH CHURCH (Medieval - 1066 AD to 1539 AD)

Medieval - 1539 AD

Evidence EXTANT BUILDING

### Description and Sources

#### Description - None recorded

<1> **Williams, H. + Swallow, R.**, 2017, *Report and Proceedings of the 162nd Summer Meeting of the Royal Archaeological Institute, 2016* (Article in serial). SWI28128.
The churches of industrialized villages of Castle Combe, Lacock and Steeple Ashton; and St Thomas Salisbury, Warminster, Westbury, Calne, Trowbridge and Melksham, reflect the wealth of their C15 cloth merchants.
<2> **Ordnance Survey**, 1936, *Ordnance Survey 25 inch Map 1936* (Map). SWI31073.
(ST 99917090) St. Mary's Church (TU).
<3> **Pevsner, N.**, 1963, *The Buildings of England, Wiltshire (1963 Edition), pp.140-141* (Bibliographic reference). SWI13567.
St. Mary's Church, Calne, contains Norman arcades and a reset Norman doorway. The exterior is nearly all Perpendicular with 17th c. and 1864 rebuilding.
<4> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976, July 1976* (Scheduling record). SWI31442.
<5> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, 14-May-1995* (Scheduling record). SWI20967.
<6> **Hase, P. + Aston, M. (ed) + Lewis, C. (ed)**, 1994, *The Medieval Landscape of Wessex, pp.43-81* (Monograph). SWI26812.
<7> **Knowles, D. + Hadcock, N.**, 1971, *Medieval religious houses in England and Wales - 1971, p.469* (Bibliographic reference). SWI30549.
<8> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212429* (Digital archive). SWI29488.
Norman with later alterations and additions, and mainly perpendicular exterior. Cruciform with 5 bay nave, clerestory, north and south aisles, chancel and transepts. The central tower fell in 1638 and was rebuilt in perpendicular style over north transept. Exterior with battlemented parapets and pinnacles with string below. Traceried 3-light clerestorey windows and 5-light west window. Interior with nave arcades of circa 1160-70 with circular piers and multi-scalloped capitals. Good 15th century timber roof with tie beams. Chancel and crossing rebuilt in the 17th century in classical style with Tuscan columns. North porch of circa 1470 with lierne-vault and pendant. Restorations in 1864 by Slater of chapels, south transept and south porch; and reredos of 1890 by Pearson.There is increasing evidence that Calne had a minster in the late Saxon period, particularly the extensive endowments documented in Domesday.

#### Sources

(1) Article in serial: Williams, H. + Swallow, R.. 2017. Report and Proceedings of the 162nd Summer Meeting of the Royal Archaeological Institute, 2016. Archaeological Journal.

(2) Map: Ordnance Survey. 1936. Ordnance Survey 25 inch Map 1936.
(3) Bibliographic reference: Pevsner, N.. 1963. The Buildings of England, Wiltshire (1963 Edition). pp.140-141
(4) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976. July 1976
(5) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. 14-May-1995
(6) Monograph: Hase, P. + Aston, M. (ed) + Lewis, C. (ed). 1994. The Medieval Landscape of Wessex. Oxbow. pp.43-81
(7) Bibliographic reference: Knowles, D. + Hadcock, N.. 1971. Medieval religious houses in England and Wales - 1971. p.469
(8) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212429

Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9989 7090 (41m by 29m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

CHURCH OF ST MARY, CHURCH STREET

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM7 | Calne – Parish Church | Active | DWI17305 |
| Listed Building (I) - 1271365 | CHURCH OF ST MARY | Active | DWI5927 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF108079 | Active |
| NBR Index Number - 108079 | Active |
| National Record of the Historic Environment to Historic Environment Records - 212429 | Active |
| National Monuments Record - ST 97 SE 17 | Active |

Ratings and Scorings - None recorded

## Land Use

Associated Historic Landscape Character Records - None recorded

Other Land Classes - None recorded

Related Monuments - None Recorded

Finds - None recorded

Associated Events/Activities - None recorded

**Associated Individuals/Organisations**

| | |
|---|---|
| Quinnell, Norman Victor - RCHME | Architectural Field Investigator |

**Monument Number** MWI36440

**Site Name** 8, High Street

| Monument Number | Record Type |
|---|---|
| MWI36440 | Building |

**Site Name** 8, High Street

House and inn built late 17th century
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Late C17 - 1667 AD to 1700 AD)
Late C17 - 1700 AD
Evidence EXTANT BUILDING
INN (Late C17 - 1667 AD to 1700 AD)
Late C17 - 1700 AD
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.44* (Scheduling record). SWI20967.
House and inn built late 17th century, probably together with the current No. 9; refronted and extended in early 18th century; extended and converted to a shop early 19th century; internal alterations in late 20th century. Rendered brick with stone dressings, side elevations of squared, coursed limestoNe rubble; roof of stone slates and pantiles.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544376* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.44
(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544376

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9974 7107 (36m by 11m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

8, HIGH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1247209 Active DWI5952

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086329 | Active |
| NBR Index Number - 86329 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544376 | Active |
| National Monuments Record - ST 97 SE 85 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36441

**Site Name** 9 High Street

**Monument Number**
MWI36441

**Record Type**
Building

**Site Name** 9 High Street

House and inn built mid to late 17th century.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Mid C17 to Late C17 - 1634 AD to 1700 AD)
Mid C17 - Late C17
Evidence EXTANT BUILDING
INN (Mid C17 to Late C17 - 1634 AD to 1700 AD)
Mid C17 - Late C17
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.45* (Scheduling record). SWI20967.
House and inn built mid to late 17th century, probably as part of the same complex as the current No. 8; refronted early 19th century with a late 19th century shop window. Rendered front with coursed limestone rubble returns, and a slate roof. Now shop and office.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544377* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.45
(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544377

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9973 7108 (27m by 11m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

9, HIGH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1270987 Active DWI5953

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086330 | Active |
| NBR Index Number - 86330 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544377 | Active |
| National Monuments Record - ST 97 SE 86 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36442

**Site Name** Lloyds Bank, 10-11 High Street

| Monument Number | Record Type |
|---|---|
| MWI36442 | Building |

**Site Name** Lloyds Bank, 10-11 High Street

Pair of attached houses built in the 1870s, then in use as a bank.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

BANK (FINANCIAL) (Built 1870s, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

HOUSE (Built 1870s, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, Vol 755-1* (Scheduling record). SWI20967.
Pair of attached houses built in the 1870s, now in use as a bank. Built of limestone ashlar with a slate roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544378* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. Vol 755-1

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544378

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9973 7109 (31m by 16m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

LLOYDS BANK, 10 AND 11, HIGH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1247210 LLOYDS BANK Active DWI5954

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086331 | Active |
| NBR Index Number - 86331 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544378 | Active |
| National Monuments Record - ST 97 SE 78 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36443

**Site Name** 12, High Street

**Monument Number**
MWI36443

**Record Type**
Building

**Site Name** 12, High Street

House built mid 18th century; altered early to mid 19th century and in use as the police station until circa 1886; shop front of mid 20th century date.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Mid C18 - 1734 AD to 1766 AD)
Mid C18 - 1766 AD
Evidence EXTANT BUILDING
POLICE STATION (C19 - 1801 AD to 1900 AD)
C19 - 1900 AD
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, Vol 755-1* (Scheduling record). SWI20967.
House built mid 18th century; altered early to mid 19th century and in use as the police station until circa 1886; shop front of mid 20th century date. Built of coursed limestone rubble with limestone dressings and a slate roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544379* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. Vol 755-1
(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544379

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9973 7110 (26m by 18m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

12, HIGH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1270988 Active DWI5955

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086332 | Active |
| NBR Index Number - 86332 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544379 | Active |
| National Monuments Record - ST 97 SE 79 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36444

**Site Name** 13 High Street

**Monument Number**
MWI36444

**Record Type**
Building

**Site Name** 13 High Street

House built early 19th century, altered mid 20th century
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Early C19 - 1801 AD to 1833 AD)
Early C19 - 1833 AD
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.47* (Scheduling record). SWI20967.
House built early 19th century, altered mid 20th century; now a shop. Render with slate roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544380* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.47

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544380

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9972 7110 (15m by 13m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

13, HIGH STREET

## Designations, Statuses and Scorings

### Associated Designations

| | | |
|---|---|---|
| Listed Building (II) - 1247211 | Active | DWI5956 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086333 | Active |
| NBR Index Number - 86333 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544380 | Active |
| National Monuments Record - ST 97 SE 48 | Active |

### Ratings and Scorings - None recorded

**Monument Number** MWI36444

**Site Name** 13 High Street

**Land Use**

Associated Historic Landscape Character Records - None recorded

Other Land Classes - None recorded

Related Monuments - None Recorded

Finds - None recorded

Associated Events/Activities - None recorded

Associated Individuals/Organisations - None recorded

**Monument Number** MWI36445

**Site Name** 15,16 and 17, High Street

| Monument Number | Record Type |
|---|---|
| MWI36445 | Building |

**Site Name** 15,16 and 17, High Street

Row of houses built 1876 of limestone rubble with rendered front and slate roof.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Built c1876, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.47* (Scheduling record). SWI20967.
Row houses built 1876 of limestone rubble with rendered front and slate roof. Now shops.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544381* (Digital archive). SWI29488.
<3> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544382* (Digital archive). SWI29488.
House built 1898, now shop with late 20th century brick shopfront. Buiilt of limestone rubble with rendered front and slate roof.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.47

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544381

(3) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544382

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9973 7111 (27m by 17m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

15,16 AND 17, HIGH STREET

## Designations, Statuses and Scorings

### Associated Designations

Listed Building (II) - 1270989 Active DWI5957

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086335 | Active |
| National Monuments Record - ST 97 SE 87 | Active |
| NBR Index Number - 86335 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544382 | Active |
| English Heritage Archives - BF086334 | Active |
| NBR Index Number - 86334 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544381 | Active |
| National Monuments Record - ST 97 SE 49 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36453

**Site Name** The Tounson Almshouses

**Monument Number**
MWI36453

**Record Type**
Building

**Site Name** The Tounson Almshouses

A terrace of eight paired almshouses, built in circa 1682, and altered in 1973.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

ALMSHOUSE (Built c1682, Late C17 - 1667 AD to 1700 AD)
Late C17 - 1700 AD
Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Ordnance Survey**, 1936, *Ordnance Survey 25 inch Map 1936* (Map). SWI31073.
(ST 99917086) Almshouses (GT).
<2> 1889, *The Wiltshire Archaeological and Natural History Magazine - Volume 24 (master), p.186* (Serial). SWI906.
The almshouses, for eight poor women, opposite the south side of the church are inscribed 1682 and were founded then by Dr. John Townson.
<3> **Marsh, A E W**, 1904, *A History of the Borough and Town of Calne, and Some Account of the Villages, etc., in its Vicinity, p.204* (Monograph). SWI11554.
<4> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976* (Scheduling record). SWI31442.
<5> **Pevsner, N. + Cherry, B.**, 1975, *The Buildings of England, Wiltshire (1975 Edition), p.157* (Bibliographic reference). SWI16505.
To the east of the church, Dr. (sic) Townson's Almshouses founded in 1682. Very modest, four pairs built on a curve. Rendered, with mullioned windows under hood moulds, interiors remodelled in 1973.
<6> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212435* (Digital archive). SWI29488.
Field Investigators Comments, NVQ 14-FEB-1968 - These almshouses are still in use - they are in good condition and externally retain their 17th century character. Of local interest and importance.

### Sources

(1) Map: Ordnance Survey. 1936. Ordnance Survey 25 inch Map 1936.
(2) Serial: 1889. The Wiltshire Archaeological and Natural History Magazine - Volume 24 (master). The Wiltshire Archaeological and Natural History Magazine. p.186
(3) Monograph: Marsh, A E W. 1904. A History of the Borough and Town of Calne, and Some Account of the Villages, etc., in its Vicinity. p.204
(4) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976.
(5) Bibliographic reference: Pevsner, N. + Cherry, B.. 1975. The Buildings of England, Wiltshire (1975 Edition). p.157
(6) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212435

### Associated resources - None recorded

## Location

**Monument Number** MWI36453

**Site Name** The Tounson Almshouses

**National Grid Reference**

Centred ST 9991 7086 (27m by 14m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names**

THE TOUNSON ALMSHOUSES, 10-13, KINGSBURY STREET

## Designations, Statuses and Scorings

**Associated Designations**

| | | | |
|---|---|---|---|
| Listed Building (II*) - 1270992 | THE TOUNSON ALMSHOUSES | Active | DWI5966 |

**Other Statuses and Cross-References**

| | |
|---|---|
| English Heritage Archives - BF107658 | Active |
| NBR Index Number - 107658 | Active |
| National Record of the Historic Environment to Historic Environment Records - 212435 | Active |
| National Monuments Record - ST 97 SE 19 | Active |

**Ratings and Scorings - None recorded**

## Land Use

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations**

Quinnell, Norman Victor - RCHME Architectural Field Investigator

**Monument Number** MWI36464

**Record Type** Building

**Site Name** Weaver's House, The Green

Weavers' House, now converted into flats, was a workshop that evolved into a cloth factory employing specialist Flemish weavers. Later it was used as a cheese store and during the 20th Century C&T Harris stored sawdust there, causing it to acquire the nickname of Sawdust House.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

HOUSE (Early 20th Century to C21 - 1901 AD to 2100 AD)

C20 - C21

Evidence EXTANT BUILDING

(Former Type) CLOTHING WORKSHOP (Late C18 - 1767 AD to 1800 AD)

Late C18 - 1800 AD

Evidence EXTANT BUILDING

Main Building Material LIMESTONE

Main Building Material RUBBLE

Covering Building Material STONE

(Former Type) CLOTHING FACTORY (By 1807, Early C19 - 1801 AD to 1833 AD)

Early C19 - 1833 AD

Evidence EXTANT BUILDING

Main Building Material LIMESTONE

Main Building Material RUBBLE

Covering Building Material STONE

(Former Type) STOREHOUSE (C20 - 1901 AD to 2000 AD)

C20 - 2000 AD

Evidence EXTANT BUILDING

Main Building Material LIMESTONE

Main Building Material RUBBLE

Covering Building Material STONE

## Description and Sources

### Description - None recorded

<1> **Slocombe, P.**, 2008, *A Guide to the Industrial Archaeology of Wiltshire, p.15* (Booklet). SWI28692.
Three-storey stone woollen workshop of 1799 with a large central arched doorway. Described 1807 as

a strong and well-built factory well adapted for a clothier. Machinery sold 1825. Now flats.
<2> **Rogers, K.H.**, 1976, *Wiltshire and Somerset Woollen Mills, p.84* (Monograph). SWI16783.
<3> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995* (Scheduling record). SWI20967.
<4> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1305356* (Digital archive). SWI29488.
3 storeyed cloth mill of 5 bays, built in the late 18th-early 19th century. Built of coursed limestone rubble with limestone dressings and a stone slate roof. The building is of three storeys with a single depth plan. There is a wide flat-arched central entrance to the front elevation and 2 light mullioned windows with slight edge mouldings. Now converted to flats. Possibly associated with nearby housing of similar date.

### Sources

(1) Booklet: Slocombe, P.. 2008. A Guide to the Industrial Archaeology of Wiltshire. Association for Industrial Archaeology. p.15
(2) Monograph: Rogers, K.H.. 1976. Wiltshire and Somerset Woollen Mills. p.84
(3) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995.
(4) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1305356

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9995 7083 (15m by 15m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

Sawdust House

WEAVER'S HOUSE, THE GREEN

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM16 | Calne – Woollen Industry Sites | Active | DWI17314 |
| Listed Building (II) - 1270883 | WEAVER'S HOUSE | Active | DWI6049 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - RCH01/063 | Active |
| South West Textile Mills Project Number - 990 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1305356 | Active |
| National Monuments Record - ST 97 SE 64 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

**Monument Number** MWI36464

**Site Name** Weaver's House, The Green

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations**

Slocombe, P. - Unassigned

**Monument Number** MWI36468

**Site Name** Zion Baptist Chapel and School

| Monument Number | Record Type |
|---|---|
| MWI36468 | Building |

**Site Name** Zion Baptist Chapel and School
ZION CHAPEL

Baptist chapel built 1836 with later school attached to rear.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

BAPTIST CHAPEL (Built 1836, Mid C19 - 1834 AD to 1866 AD)

Mid C19 - 1866 AD

Evidence EXTANT BUILDING

CHURCH SCHOOL (Mid C19 - 1834 AD to 1866 AD)

Mid C19 - 1866 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.123* (Scheduling record). SWI20967.
Baptist chapel built 1836 with later school attached to rear, now a meeting room; minor late 20th century alterations. Built of coursed, squared, limestone rubble, with limestone dressings; slate and pantile roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 602195* (Digital archive). SWI29488.
<3> **Stell, Christopher; RCHME**, 1991, *An Inventory of Nonconformist Chapels and Meeting-Houses in South-West England, p.215* (Monograph). SWI19788.
Baptist chapel and school. Dated 1836; later school. Coursed, squared limestone rubble, limestone dressings, slate and pantile roof and brick lateral stack. Rectangular chapel with single-depth school room across East end. 2 storeys; 2-window range.
<4> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1487464* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.123

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 602195

(3) Monograph: Stell, Christopher; RCHME. 1991. An Inventory of Nonconformist Chapels and Meeting-Houses in South-West England. p.215

(4) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1487464

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9981 7116 (19m by 12m) ST97SE Area

### Administrative Areas

**Monument Number** MWI36468

**Site Name** Zion Baptist Chapel and School

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names**

ZION BAPTIST CHAPEL AND SCHOOL, THE PIPPIN

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Listed Building (II) - 1247493 | ZION BAPTIST CHAPEL AND SCHOOL AND ZION CHAPEL | Active | DWI6053 |

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 1487464 | Active |
| National Monuments Record - ST 97 SE 105 | Active |
| English Heritage Archives - BF086363 | Active |
| NBR Index Number - 86363 | Active |
| National Record of the Historic Environment to Historic Environment Records - 602195 | Active |
| National Monuments Record - ST 97 SE 88 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations - None recorded

**Monument Number** MWI36469

**Site Name** Barclays Bank

| Monument Number | Record Type |
|---|---|
| MWI36469 | Building |

**Site Name** Barclays Bank
THE OLD BANK HOUSE

Bank built 1901 of squared coursed limestone with a slate roof.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

BANK (FINANCIAL) (Built 1901, Early 20th Century - 1901 AD to 1932 AD)

Early 20th Century - 1932 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of National Heritage**, 1995, *Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995, p.124* (Scheduling record). SWI20967.
Bank built 1901 of squared coursed limestone with a slate roof.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544374* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of National Heritage. 1995. Revised List of Buildings of Special Architectural or Historic Interest, District of North Wiltshire, Calne Area 1995. p.124

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544374

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9977 7099 (17m by 11m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

THE OLD BANK HOUSE, THE STRAND

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Listed Building (II) - 1247494 | BARCLAYS BANK AND THE OLD BANK HOUSE | Active | DWI6054 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086327 | Active |
| NBR Index Number - 86327 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544374 | Active |
| National Monuments Record - ST 97 SE 81 | Active |

**Monument Number** MWI36469

**Site Name** Barclays Bank

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI36470

**Site Name** Lansdowne Arms Hotel

**Monument Number**
MWI36470

**Record Type**
Building

**Site Name** Lansdowne Arms Hotel

An inn existed on this site as early as 1582, and until the early C19 was called the Catharine Wheel. The existing building is the result of amalgamating some 5 properties on either side of the original inn building. The building was reroofed and refronted in the early C19, although the rear still retains the irregular gabled character of the original C18 houses.
For full details of this building, please check the Listed Building description.

## Monument Types and Dates

INN (Post Medieval to Early C19 - 1540 AD to 1833 AD)

Post Medieval - Early C19

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Department of Environment (HHR)**, 1976, *List of Buildings of Special Architectural or Historic Interest: Calne Area 1976, pp.55-56* (Scheduling record). SWI31442.
An inn existed on this site as early as 1582, and until the early C19 was called the Catharine Wheel. The existing building is the result of amalgamating some 5 properties on either side of the original inn building. The building was reroofed and refronted in the early C19, although the rear still retains the irregular gabled character of the original C18 houses. At the southern end an additional building was incorporated, probably circa 1860, and was partly rebuilt in C17 style. In the later C19 stable buildings were added along the Castle Street frontage. Main range 2 storeys and cellars. 13 window. Stone slate roof with coped gables and 5 moulded ashlar ridge stacks. Coursed, squared limestone rubble with long and short dressings to quoins, painted and northern end stuccoed with joint lines. Plinth. Console bracketted cornice and parapet above. Architraved sash windows with roll-bolection mouldings and glazing bars. Between 1st pair of windows at 1st floor level of south end, large lunette with roll-bolection surround enclosing a barometer. Wide central carriage entrance with semi-elliptical arch with plain surround, key and impost blocks; modern doorway with 3/4 glazed doors, side-lights and radial fanlight. Window converted for use as modern doorway at north end. Late C19 wrought iron lamp bracket over entrance carrying Windsor lantern, and above this a painted signboard with the full achievement of the arms of the Marquis of Lansdowne. King post and collar truss roof. South block set back on different alignment from main range. 2 storeys. 3 windows. Stone slate roof with moulded ridge stack similar to those of main range. Coped gable with finial and kneelers. Coursed, squared limestone rubble with long and short dressings to quoins. Painted rubble front. 1st floor string. 2 and 3 light moulded ransom and mullion windows with leaded lights. King post roof reusing some older timbers. Southern stable block 2 storeys, 4 windows. Stone and Welsh slate roof. Coursed, squared limestone rubble with ashlar dressings. Recessed sash windows. Semi-elliptical arched entrance, with key. The former split-level coach-house adjoining in the stable yard have been demolished. West range. Mid C19 stable block. 2 storeys. 2 windows to stable yard. Welsh slate roof. Coursed squared limestone rubble. Windows with plain surrounds and semi-elliptical heads with keys and glazing bars. Doorways with segmental arched heads and boarded doors (including door at 1st floor level from former coach-house). Range at north-west corner. Earlier C18. 2 storeys. 2 windows and 1 window on splayed corner to stable yard. Hipped stone slate roof patched with pantiles. Random limestone rubble with modern cement patching. Openings with wooden lintols. 2 and 3 light casement windows, 1st floor with oak frames., mullions and leaded lights. C19 panelled door with fanlight. Former brewhouse on north side of stable yard. Earlier-mid C19. 3 storeys. 2 windows. Welsh slate roof with tall brick chimney at west end. Coursed squared limestone rubble with red brick dressings. Recessed windows

with glazing bars. Wide entrance now partly blocked, with timber lintol. Rear façade of main range Irregular gabled bays of former houses.
Limewashed limestone rubble with ashlar dressings. Recessed sash and casement windows with oak and stone lintols; some sash windows with exposed boxing and glazing bars; window opening with similar mouldings to those of south block with date stone over inscribed 1860.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 212460* (Digital archive). SWI29488.

### Sources

(1) Scheduling record: Department of Environment (HHR). 1976. List of Buildings of Special Architectural or Historic Interest: Calne Area 1976. pp.55-56

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 212460

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9969 7100 (46m by 59m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names

LANSDOWNE ARMS HOTEL AND FORMER COACH HOUSE, STABLE AND BREWHOUSE, CHURCH STREET

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Listed Building (II*) - 1247495 | LANSDOWNE ARMS HOTEL AND FORMER COACH HOUSE, STABLE AND BREWHOUSE | Active | DWI6055 |

### Other Statuses and Cross-References

| | |
|---|---|
| National Record of the Historic Environment to Historic Environment Records - 212460 | Active |
| National Monuments Record - ST 97 SE 34 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations - None recorded

**Monument Number** MWI36471

**Site Name** Old Fire Station, Rear of Town Hall

| Monument Number | Record Type |
|---|---|
| MWI36471 | Building |

**Site Name** Old Fire Station, Rear of Town Hall

Built as a sawdust house in 1884 and later converted to a fire station.
For full details of this building, please check the Listed Building description.

### Monument Types and Dates

HOUSE (Converted early 2000s, C21 - 2001 AD to 2100 AD)

C21 - 2100 AD

| | |
|---|---|
| Evidence | EXTANT BUILDING |
| Main Building Material | LIMESTONE |
| Main Building Material | ASHLAR |
| Main Building Material | RUBBLE |
| Covering Building Material | PANTILE |

(Former Type) STOREHOUSE (Built, Late C19 - 1884 AD)

1884 AD

| | |
|---|---|
| Evidence | EXTANT BUILDING |
| Main Building Material | LIMESTONE |
| Main Building Material | ASHLAR |
| Main Building Material | RUBBLE |
| Covering Building Material | PANTILE |

(Former Type) FIRE STATION (Converted, Late C19 - 1888 AD)

1888 AD

| | |
|---|---|
| Evidence | EXTANT BUILDING |
| Main Building Material | LIMESTONE |
| Main Building Material | ASHLAR |
| Main Building Material | RUBBLE |
| Covering Building Material | PANTILE |

### Description and Sources

Description - None recorded

<1> **Slocombe, P.**, 2008, *A Guide to the Industrial Archaeology of Wiltshire, p.15* (Booklet). SWI28692.
Behind the Town Hall and built as a sawdust house for Thomas Harris in 1884. Later converted to fire

station. The Fire Brigade was formed in 1888.

**Sources**

(1) Booklet: Slocombe, P.. 2008. A Guide to the Industrial Archaeology of Wiltshire. Association for Industrial Archaeology. p.15

**Associated resources - None recorded**

## Location

**National Grid Reference**

Centred ST 9971 7095 (14m by 10m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names**

OLD FIRE STATION AT REAR OF TOWN HALL, THE STRAND

## Designations, Statuses and Scorings

**Associated Designations**

| | | | |
|---|---|---|---|
| Listed Building (II) - 1247534 | OLD FIRE STATION AT REAR OF TOWN HALL | Active | DWI6056 |

**Other Statuses and Cross-References - None recorded**

**Ratings and Scorings - None recorded**

## Land Use

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations**

Slocombe, P. - Unassigned

**Monument Number** MWI49860

**Site Name** C and T Harris Bacon Factory

**Monument Number** | **Record Type**

MWI49860 | Monument

**Site Name** C and T Harris Bacon Factory

A butchers shop of circa 1770 which expanded into a factory complex in the early 20th century.

## Monument Types and Dates

FOOD PROCESSING PLANT (Demolished 1984-1985, Early C18 to Late 20th Century - 1701 AD to 2000 AD)

Early C18 - Late 20th Century

Evidence DESTROYED MONUMENT

FOOD PRESERVING FACTORY (Demolished 1984-1985, C20 - 1901 AD to 2000 AD)

Early 20th Century - Late 20th Century

Evidence DESTROYED MONUMENT

## Description and Sources

### Description - None recorded

<1> **Williams, H. + Swallow, R.**, 2017, *Report and Proceedings of the 162nd Summer Meeting of the Royal Archaeological Institute, 2016* (Article in serial). SWI28128.
A bacon factory founded circa 1770. The main five storey building dates back to the 1930s. Further additions by Robinson and Kay were completed in Church Street in 1954, and later in Mill Street by John Sharpe Associates in 1973. The building was demolished in the mid 1980s. Harris's of Calne began by processing Irish pigs being driven from Bristol to London by road. Then the railways made it easier to source pigs from a greater distance and to send the resulting bacon around the country and the world.
<2> **Pevsner, N. + Cherry, B.**, 1975, *The Buildings of England, Wiltshire (1975 Edition), p.156* (Bibliographic reference). SWI16505.
Bacon factory, founded circa 1770. The main building, of five storeys was built in 1923 and 1930. Further additions were built across Church Street in 1953-4 (by Robinson and Kay) and in Mill Street in 1972-3 (by John Sharpe Associates). The building was derelict and due for demolition in 1984.
<3> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1183577* (Digital archive). SWI29488.

### Sources

(1) Article in serial: Williams, H. + Swallow, R.. 2017. Report and Proceedings of the 162nd Summer Meeting of the Royal Archaeological Institute, 2016. Archaeological Journal.

(2) Bibliographic reference: Pevsner, N. + Cherry, B.. 1975. The Buildings of England, Wiltshire (1975 Edition). p.156

(3) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1183577

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9976 7101 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

**Monument Number** MWI49860

**Site Name** C and T Harris Bacon Factory

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM17 | Calne – Bacon Industry | Active | DWI17319 |

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF098559 | Active |
| English Heritage Archives - HAW/9416/31 | Active |
| NBR Index Number - 98559 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1183577 | Active |
| National Monuments Record - ST 97 SE 59 | Active |
| Wiltshire Buildings Record Number - 03180.1 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations

| | |
|---|---|
| English Heritage | Recorder |

**Monument Number** MWI66704

**Site Name** Site of Coleman's Farm

**Monument Number**
MWI66704

**Record Type**
Monument

**Site Name** Site of Coleman's Farm

Demolished 19th century farmstead.

## Monument Types and Dates

FARMSTEAD (C19 - 1801 AD to 1900 AD)

## Description and Sources

### Description - None recorded

<1> **Edwards, B.**, 2014, *Wiltshire Farmsteads Mapping Project Data, PRN602281* (Survey). SWI26655.
Site of Coleman's Farm, Calne. Demolished 19th century farmstead of regular courtyard plan. The farm buildings are dispersed across multiple yards. The farmhouse was detached with gable on to the yard. Located within or in association to a town. The farmstead and all historic buildings have been lost.
<2> **Edwards, B. + Lake, J.**, 2014, *Wiltshire & Swindon Farmsteads & Landscape Project* (Report). SWI26652.
<3> **Lake, J. + Edwards, B.**, 2014, *Wiltshire and Swindon Farmsteads Guidance. Farmsteads Assessment Framework* (Report). SWI26641.
<4> **Lake, J. + Edwards, B.**, 2014, *Wiltshire and Swindon Farmsteads Guidance. Wiltshire and Swindon Farmsteads Character Statement* (Report). SWI26643.

### Sources

(1) Survey: Edwards, B.. 2014. Wiltshire Farmsteads Mapping Project Data. Forum Heritage Services. PRN602281

(2) Report: Edwards, B. + Lake, J.. 2014. Wiltshire & Swindon Farmsteads & Landscape Project. Forum Heritage Services.

(3) Report: Lake, J. + Edwards, B.. 2014. Wiltshire and Swindon Farmsteads Guidance. Farmsteads Assessment Framework. English Heritage and Wiltshire Council.

(4) Report: Lake, J. + Edwards, B.. 2014. Wiltshire and Swindon Farmsteads Guidance. Wiltshire and Swindon Farmsteads Character Statement. English Heritage, Wiltshire Buildings Record, Wiltshire Council and Swindon Borough Council.

### Associated resources - None recorded

## Location

### National Grid Reference

SU 0009 7113 (point) SU07SW Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings

Confidence High

**Monument Number** MWI66704

**Site Name** Site of Coleman's Farm

**Land Use**

**Associated Historic Landscape Character Records**

HWI7764 Urban settlement - Terraced housing (Type Code: USE-TDHO)

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities**

EWI7531 Wiltshire Farmsteads Mapping Project (Interpretation)

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI66790

**Site Name** 17 & 19 The Pippin

**Monument Number**
MWI66790

**Record Type**
Building

**Site Name** 17 & 19 The Pippin

17th century farmstead.

## Monument Types and Dates

FARMSTEAD (C17 - 1601 AD to 1700 AD)

## Description and Sources

### Description - None recorded

<1> **Edwards, B.**, 2014, *Wiltshire Farmsteads Mapping Project Data, PRN602367* (Survey). SWI26655.
17 & 19 The Pippin, Calne. 17th century farmstead of regular courtyard plan. The farm buildings are dispersed across multiple yards. The farmhouse is set away from the yard. Located within or in association to a village. The farmhouse is the only surviving historic structure.
<2> **Edwards, B. + Lake, J.**, 2014, *Wiltshire & Swindon Farmsteads & Landscape Project* (Report). SWI26652.
<3> **Lake, J. + Edwards, B.**, 2014, *Wiltshire and Swindon Farmsteads Guidance. Farmsteads Assessment Framework* (Report). SWI26641.
<4> **Lake, J. + Edwards, B.**, 2014, *Wiltshire and Swindon Farmsteads Guidance. Wiltshire and Swindon Farmsteads Character Statement* (Report). SWI26643.

### Sources

(1) Survey: Edwards, B.. 2014. Wiltshire Farmsteads Mapping Project Data. Forum Heritage Services. PRN602367

(2) Report: Edwards, B. + Lake, J.. 2014. Wiltshire & Swindon Farmsteads & Landscape Project. Forum Heritage Services.

(3) Report: Lake, J. + Edwards, B.. 2014. Wiltshire and Swindon Farmsteads Guidance. Farmsteads Assessment Framework. English Heritage and Wiltshire Council.

(4) Report: Lake, J. + Edwards, B.. 2014. Wiltshire and Swindon Farmsteads Guidance. Wiltshire and Swindon Farmsteads Character Statement. English Heritage, Wiltshire Buildings Record, Wiltshire Council and Swindon Borough Council.

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9999 7124 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings

Confidence High

**Monument Number** MWI66790

**Site Name** 17 & 19 The Pippin

**Land Use**

**Associated Historic Landscape Character Records**

HWI7966 Urban settlement - Terraced housing (Type Code: USE-TDHO)
Broken Cross

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities**

EWI7531 Wiltshire Farmsteads Mapping Project (Interpretation)

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI74622

**Site Name** Graves, Zion Baptist Chapel

**Monument Number** **Record Type**

MWI74622 Monument

**Site Name** Graves, Zion Baptist Chapel

A number of graves of unknown date were identified by a geophysical survey.

## Monument Types and Dates

GRAVE (Unknown date)

Evidence SUB SURFACE DEPOSIT

## Description and Sources

### Description - None recorded

<1> **Sabin, D. + Donaldson, K.**, 2009, *Zion Baptist Chapel, Calne* (Report). SWI25529.
A number of graves of unknown date were identified by a geophysical survey.
<2> **Hart, J.**, 2009, *Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire* (Report). SWI25603.
Further graves were identified by an excavation during a watching brief.
<3> **Webb, H.**, 2008, *Zion Baptist Chapel, Calne, Wiltshire* (Report). SWI25497.

### Sources

(1) Report: Sabin, D. + Donaldson, K.. 2009. Zion Baptist Chapel, Calne. Archaeological Surveys Ltd.

(2) Report: Hart, J.. 2009. Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire. Cotswold Archaeology.

(3) Report: Webb, H.. 2008. Zion Baptist Chapel, Calne, Wiltshire. Oxford Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7116 (21m by 9m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records

HWI7970 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

**Monument Number** MWI74622

**Site Name** Graves, Zion Baptist Chapel

## Associated Events/Activities

| | |
|---|---|
| EWI6973 | Evaluation at Zion Chapel Burial Ground, Calne (Intervention) |
| EWI6974 | Geophysical Survey at Zion Chapel Graveyard, Calne (Survey) |
| EWI6975 | Watching Brief at Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire. (Intervention) |

## Associated Individuals/Organisations

| | |
|---|---|
| Archaeological Surveys Ltd | Geophysical Surveyor |

**Monument Number** MWI74623

**Site Name** Linear Features, Zion Baptist Chapel

| Monument Number | Record Type |
|---|---|
| MWI74623 | Monument |

**Site Name** Linear Features, Zion Baptist Chapel

A number of linear features of unknown date were identified by a geophysical survey and later found to be walls during a watching brief.

## Monument Types and Dates

LINEAR FEATURE (Unknown date)

Evidence SUB SURFACE DEPOSIT

## Description and Sources

### Description - None recorded

<1> **Sabin, D. + Donaldson, K.**, 2009, *Zion Baptist Chapel, Calne* (Report). SWI25529.
A number of linear features of unknown date were identified by a geophysical survey.
<2> **Hart, J.**, 2009, *Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire* (Report). SWI25603.
The linear features were found to be a walls during a watching brief.
<3> **Webb, H.**, 2008, *Zion Baptist Chapel, Calne, Wiltshire* (Report). SWI25497.

### Sources

(1) Report: Sabin, D. + Donaldson, K.. 2009. Zion Baptist Chapel, Calne. Archaeological Surveys Ltd.

(2) Report: Hart, J.. 2009. Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire. Cotswold Archaeology.

(3) Report: Webb, H.. 2008. Zion Baptist Chapel, Calne, Wiltshire. Oxford Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7116 (25m by 13m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records

HWI7970 Urban settlement - Historic urban core (Type Code: USE-HSCO)
Calne

### Other Land Classes - None recorded

### Related Monuments - None Recorded

**Monument Number** MWI74623

**Site Name** Linear Features, Zion Baptist Chapel

**Finds - None recorded**

**Associated Events/Activities**

| | |
|---|---|
| EWI6973 | Evaluation at Zion Chapel Burial Ground, Calne (Intervention) |
| EWI6974 | Geophysical Survey at Zion Chapel Graveyard, Calne (Survey) |
| EWI6975 | Watching Brief at Zion Baptist Chapel, Phelps Parade, Calne, Wiltshire. (Intervention) |

**Associated Individuals/Organisations**

| | |
|---|---|
| Archaeological Surveys Ltd | Geophysical Surveyor |

**Monument Number** MWI75861

**Site Name** Medieval Ditches, The Pippins

**Monument Number** **Record Type**

MWI75861 Monument

**Site Name** Medieval Ditches, The Pippins

Ditches of a medieval date were found during evaluations.

## Monument Types and Dates

DITCH (Medieval - 1066 AD to 1539 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Lovett, P.**, 2016, *83, The Pippin, Calne* (Report). SWI27907.
A curvilinear ditch of a medieval date was found during an excavation.
<2> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
Further ditches were found during a second evaluation.

### Sources

(1) Report: Lovett, P.. 2016. 83, The Pippin, Calne. Worcestershire Archaeology.

(2) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7111 (18m by 25m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Associated Finds

FWI29179 SHERD (Medieval - 1066 AD to 1539 AD) (FWI29179) POTTERY

### Associated Events/Activities

EWI8852 Evaluation at 83, The Pippin (Intervention)

EWI10243 Excavation at Land at The Pippin (Intervention)

**Monument Number** MWI75861

**Site Name** Medieval Ditches, The Pippins

## Associated Individuals/Organisations

| | |
|---|---|
| Worcestershire Archaeology | Excavator |

**Monument Number** MWI75863

**Record Type** Monument

**Site Name** Medieval Pits, 83 The Pippin

Pits of a medieval date were found during an excavation.

## Monument Types and Dates

PIT (Medieval - 1066 AD to 1539 AD)

Medieval - 1539 AD

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Lovett, P.**, 2016, *83, The Pippin, Calne* (Report). SWI27907.
Pits of an unknown date were found during an excavation.
<2> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
More pits were found during an evaluation

### Sources

(1) Report: Lovett, P.. 2016. 83, The Pippin, Calne. Worcestershire Archaeology.

(2) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7112 (43m by 34m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI8852 Evaluation at 83, The Pippin (Intervention)

EWI10243 Excavation at Land at The Pippin (Intervention)

### Associated Individuals/Organisations

| | |
|---|---|
| Worcestershire Archaeology | Excavator |

**Monument Number** MWI75864

**Site Name** Medieval Gullies, The Pippins

**Monument Number** **Record Type**

MWI75864 Monument

**Site Name** Medieval Gullies, The Pippins

Gullies of a medieval date were found during an excavation.

## Monument Types and Dates

GULLY (Medieval - 1066 AD to 1539 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Lovett, P.**, 2016, *83, The Pippin, Calne* (Report). SWI27907.
Gullies of a medieval date were found during an excavation.
<2> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
More gullies were found during a second evaluation. A shallow gully [1021], 0.28m wide and 0.1m deep, contained a single fill, a light brownish grey clay silt (1022) without finds. It may have either terminated to the ENE or been truncated from this point. A gully [1014] crossed the area WNW-ESE, perpendicular to the plot boundary. It was 0.55m wide and 0.12m deep containing a single fill of friable mid greenish-grey clay (1013), from which no dateable material was retrieved.
A narrow gully in parts was probably all the same feature (viz [2127], [2157], [2175]). Slightly curving gully [2127] to the west was 0.34m wide, had steep sides and a flat base, but with no finds from its fill (2128), a loose greyish brown sandy silt. Gully [2157] to the east was 0.28m wide, though shallower than [2127] at 0.28m depth, and had a mid-yellowish brown silty sand fill (2158) associated with pottery dated to 12th-13th century. Gully 2175, (which lay beneath the Group 13 building described below) was, again only 0.1m deep and filled by a mid-greyish black sandy silt (2176), but was without finds.

### Sources

(1) Report: Lovett, P.. 2016. 83, The Pippin, Calne. Worcestershire Archaeology.

(2) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7111 (49m by 47m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

**Monument Number** MWI75864

**Site Name** Medieval Gullies, The Pippins

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Associated Finds**

| | | |
|---|---|---|
| FWI29353 | SHERD (Medieval - 1066 AD to 1539 AD) (FWI29353) | POTTERY |

**Associated Events/Activities**

| | |
|---|---|
| EWI8852 | Evaluation at 83, The Pippin (Intervention) |
| EWI10243 | Excavation at Land at The Pippin (Intervention) |

**Associated Individuals/Organisations**

| | |
|---|---|
| Worcestershire Archaeology | Excavator |

**Monument Number** MWI75865

**Site Name** Medieval Pits, The Pippins

**Monument Number** **Record Type**

MWI75865 Monument

**Site Name** Medieval Pits, The Pippins

Pits of a medieval date were found during an excavation.

## Monument Types and Dates

PIT (Medieval - 1066 AD to 1539 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Lovett, P.**, 2016, *83, The Pippin, Calne* (Report). SWI27907.
Pits of a medieval date were found during an excavation.

### Sources

(1) Report: Lovett, P.. 2016. 83, The Pippin, Calne. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9977 7110 (2m by 1m) ST97SE Line

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI8852 Evaluation at 83, The Pippin (Intervention)

### Associated Individuals/Organisations

Worcestershire Archaeology Excavator

**Monument Number** MWI75866

**Site Name** Post Medieval Walls, The Pippins

**Monument Number** **Record Type**

MWI75866 Monument

**Site Name** Post Medieval Walls, The Pippins

Walls of a post medieval date were found during an excavation.

## Monument Types and Dates

WALL (Post Medieval - 1540 AD to 1900 AD)

Post Medieval - 1900 AD

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
Walls of a post medieval date were found during an excavation.

### Sources

(1) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7112 (46m by 33m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI10243 Excavation at Land at The Pippin (Intervention)

### Associated Individuals/Organisations

Worcestershire Archaeology Excavator

**Monument Number** MWI76170

**Site Name** Calne Wharf

**Monument Number** **Record Type**

MWI76170 Monument

**Site Name** Calne Wharf

A wharf on the Calne Branch Canal and River Marden.

## Monument Types and Dates

CANAL WHARF (C19 - 1801 AD to 1900 AD)

Evidence EXTANT STRUCTURE

## Description and Sources

### Description - None recorded

<1> **Oliver, K.**, 2015, *Gazetteer of Sites Relating to The Wilts and Berks Canal* (Report). SWI27137.
A wharf on the Calne Branch Canal and River Marden.

### Sources

(1) Report: Oliver, K.. 2015. Gazetteer of Sites Relating to The Wilts and Berks Canal. Wilts and Berks Canal Trust.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9975 7086 (27m by 186m) ST97SE Area

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM21 Calne – Canal and Railway Land Active DWI17323

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations

| | |
|---|---|
| Wilts and Berks Canal Trust | Surveyor |
| Wilts and Berks Canal Trust | Researcher |

**Monument Number** MWI76831

**Site Name** Medieval/Post Medieval Boundary Ditches, The Old

| Monument Number | Record Type |
|---|---|
| MWI76831 | Monument |

**Site Name** Medieval/Post Medieval Boundary Ditches, The Old Vicarage, Anchor Road

Two adjacent boundary ditches of a medieval to post-medieval date were found during an excavation.

## Monument Types and Dates

BOUNDARY DITCH (Medieval to Late C19 - 1066 AD to 1900 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Froud, S.**, 2019, *The Old Vicarage, Anchor Road, Calne* (Report). SWI28486.
Two adjacent boundary ditches of a medieval to post-medieval date were found during an excavation. They may have been used to demarcate the boundary of a medieval monastic lodge.

### Sources

(1) Report: Froud, S.. 2019. The Old Vicarage, Anchor Road, Calne. Wessex Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred SU 0002 7100 (7m by 4m) SU07SW Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

| | | | |
|---|---|---|---|
| Extensive Urban Survey - COM13 | Calne – Rectory | Active | DWI17311 |

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities - None recorded

### Associated Individuals/Organisations

| | |
|---|---|
| Wessex Archaeology | Excavator |

**Monument Number** MWI76831

**Site Name** Medieval/Post Medieval Boundary Ditches, The Old

**Monument Number** MWI78424

**Site Name** Medieval Postholes, The Pippins

**Monument Number** **Record Type**

MWI78424 Monument

**Site Name** Medieval Postholes, The Pippins

Postholes of a medieval date were found during an excavation.

## Monument Types and Dates

POST HOLE (Medieval - 1066 AD to 1539 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
Postholes were found during an evaluation.

### Sources

(1) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9981 7112 (8m by 10m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI10243 Excavation at Land at The Pippin (Intervention)

### Associated Individuals/Organisations

Worcestershire Archaeology Excavator

**Monument Number** MWI78425

**Site Name** Medieval Lime Kiln, The Pippins

| Monument Number | Record Type |
|---|---|
| MWI78425 | Monument |

**Site Name** Medieval Lime Kiln, The Pippins

A lime kiln of a medieval date was found during an excavation.

## Monument Types and Dates

POST HOLE (Medieval - 1066 AD to 1539 AD)

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
A lime kiln of a medieval date was found during an excavation. The remains of a lime kiln survived comprising curved stone structures set in a bowl-shaped cut into the natural substrate. The kiln was largely filled with loose rubble collapse from its own walls, and the entire structure was buried beneath a thick layer of post-medieval lower garden soil. The subcircular bowl-shaped cut had shallow sides and a convex base about 4m wide at its widest point. In the centre of this was a tear-shaped deeper area which led into a flue extending southwards from the kiln. This was 0.49m wide and 0.37m deep containing a single fill a loose mid reddish brown sandy silt containing frequent stone fragments. The flue (2.7m long), at the point where it entered the bowl-shaped cut, was lined on both sides by a wall, comprising three courses of unbonded, flattish limestone slabs up to 0.25m long. Extending from this into the bowl on the western side was comprising similar stones that appeared to have been the remains of a revetment to the bowl which probably originally extended round to join on the eastern side. Extending around the northern side of the bowl-shaped cut, there was a section of wall built of limestone slabs with rubble. This was unbonded, c 1m wide and 0.55m at its highest point, and built within a construction cut. Within the bowl, and covering the partial wall, there was a dark grey-brown clay silt associated with pottery no earlier than the 12th century, though maybe as late as the 15th century. Over this was a limestone rubble in a silty matrix, presumably the collapsed remains of wall and the dome of the kiln.

### Sources

(1) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9980 7111 (5m by 6m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

**Monument Number** MWI78425

**Site Name** Medieval Lime Kiln, The Pippins

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities**

EWI10243 Excavation at Land at The Pippin (Intervention)

**Associated Individuals/Organisations**

| | |
|---|---|
| Worcestershire Archaeology | Excavator |

**Monument Number** MWI78426

**Site Name** Early Medieval Ditches, The Pippins

**Monument Number** **Record Type**

MWI78426 Monument

**Site Name** Early Medieval Ditches, The Pippins

Ditches of an early medieval date were found during an evaluation.

## Monument Types and Dates

DITCH (Early Medieval (Saxon) - 410 AD to 1065 AD)

Early Medieval (Saxon) - 1065 AD

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
Ditches of an early medieval date were found during an evaluation.

### Sources

(1) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9979 7111 (35m by 10m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI10243 Excavation at Land at The Pippin (Intervention)

### Associated Individuals/Organisations

Worcestershire Archaeology Excavator

**Monument Number** MWI78427

**Site Name** Early Medieval Gullies, The Pippins

**Monument Number** **Record Type**

MWI78427 Monument

**Site Name** Early Medieval Gullies, The Pippins

Gullies of an early medieval date were found during an evaluation.

## Monument Types and Dates

GULLY (Early Medieval (Saxon) - 410 AD to 1065 AD)

Early Medieval (Saxon) - 1065 AD

Evidence EXCAVATED FEATURE

## Description and Sources

### Description - None recorded

<1> **Hurst, D.**, 2023, *Land at The Pippin, Calne, Wiltshire* (Report). SWI29516.
Gullies of an early medieval date were found during an evaluation.

### Sources

(1) Report: Hurst, D.. 2023. Land at The Pippin, Calne, Wiltshire. Worcestershire Archaeology.

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9981 7112 (13m by 17m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations

Extensive Urban Survey - COM9 Calne – Planned Settlement Area Active DWI17307

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

### Associated Events/Activities

EWI10243 Excavation at Land at The Pippin (Intervention)

### Associated Individuals/Organisations

Worcestershire Archaeology Excavator

**Monument Number** MWI78868

**Site Name** Wiltshire and Berkshire Canal: Calne Branch

| Monument Number | Record Type |
|---|---|
| MWI78868 | Monument |

**Site Name** Wiltshire and Berkshire Canal: Calne Branch

A branch of the Wiltshire and Berkshire Canal connecting to Calne.

## Monument Types and Dates

CANAL (Early C19 to First World War - 1810 AD to 1914 AD)

1810 AD - 1914 AD

Evidence EARTHWORK

## Description and Sources

### Description - None recorded

<1> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, NRHE 975884* (Digital archive). SWI29488.

### Sources

(1) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. NRHE 975884

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9792 7160 (3683m by 1947m) ST97SE Line

### Administrative Areas

| | |
|---|---|
| Civil Parish | Calne Without, North Wiltshire, Wiltshire |
| Civil Parish | Calne, North Wiltshire, Wiltshire |

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References - None recorded

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments

| | | |
|---|---|---|
| MWI76166 | Conigre Lock, Calne | Geographical |
| MWI76167 | Calne Tunnel | Geographical |
| MWI76168 | Calne Lock | Geographical |
| MWI76169 | Chaveywell Bridge, Calne | Geographical |
| ST97SW535 | Wiltshire and Berkshire Canal: Chippenham Branch | All Groups |
| SU09NE530 | Wiltshire and Berkshire Canal | All Groups |

**Monument Number** MWI78868

**Site Name** Wiltshire and Berkshire Canal: Calne Branch

| | | |
|---|---|---|
| MWI78867 | Wiltshire and Berkshire Canal: North Wiltshire Branch | All Groups |

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI80028

**Site Name** The Green, Calne

**Monument Number** MWI80028

**Record Type** Monument

**Site Name** The Green, Calne

A triangular shaped green, with a number of Georgian and 16th century houses and buildings.

### Monument Types and Dates

HOUSE (Medieval to Late C19 - 1066 AD to 1900 AD)
Medieval - Post Medieval
INN (Post Medieval - 1540 AD to 1900 AD)
Post Medieval - 1900 AD
SCHOOL (Post Medieval - 1540 AD to 1900 AD)
Post Medieval - 1900 AD
WORKSHOP (Post Medieval - 1540 AD to 1900 AD)
Post Medieval - 1900 AD

### Description and Sources

**Description - None recorded**

<1> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, NRHE 1366934* (Digital archive). SWI29488.
<2> **Pevsner, N. + Cherry, B.**, 1975, *The Buildings of England, Wiltshire (1975 Edition), p.158* (Bibliographic reference). SWI16505.
Pevsner describes The Green as" A spacious triangle with the the wealthiest houses of Georgian Calne". He lists The White Hart Hotel, of circa 1800, the Boys school with its Gothic stone front of 1829, Adam House, and 18th century house with a 3-bay front and the woolen mill now converted to flats as being the most notable buildings.

**Sources**

(1) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. NRHE 1366934
(2) Bibliographic reference: Pevsner, N. + Cherry, B.. 1975. The Buildings of England, Wiltshire (1975 Edition). p.158

**Associated resources - None recorded**

### Location

**National Grid Reference**

Centred ST 9997 7078 (103m by 140m) ST97SE Area

**Administrative Areas**

Civil Parish Calne, North Wiltshire, Wiltshire

**Address/Historic Names - None recorded**

### Designations, Statuses and Scorings

**Associated Designations - None recorded**

**Other Statuses and Cross-References**

| | |
|---|---|
| English Heritage Archives - BF107659 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1366934 | Active |
| National Monuments Record - ST 97 SE 91 | Active |

**Ratings and Scorings - None recorded**

**Land Use**

**Associated Historic Landscape Character Records - None recorded**

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities**

EWI10432 Investigation by RCHME/EH Architectural Survey (Extensive Survey)

**Associated Individuals/Organisations**

| | |
|---|---|
| Page, Robin - English Heritage | Compiler |
| Williams, Peter - RCHME | Photographer |

**Monument Number** MWI80080

**Site Name** Former Late 17th Century House, Market Hill

| Monument Number | Record Type |
|---|---|
| MWI80080 | Monument |

**Site Name** Former Late 17th Century House, Market Hill

Late 17th century house of stone rubble with roof of stone slates and demolished in 1976. Formerly immediately to the rear of No. 3 Market Hill.

## Monument Types and Dates

HOUSE (Late C17 - 1667 AD to 1700 AD)

Late C17 - 1700 AD

Evidence DESTROYED MONUMENT

## Description and Sources

### Description - None recorded

<1> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 522325* (Digital archive). SWI29488.
House built late 17th century of stone rubble with roof of stone slates; demolished 1976. Formerly immediately to the rear of No. 3 Market Hill.

### Sources

(1) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 522325

### Associated resources - None recorded

## Location

### National Grid Reference

| | | |
|---|---|---|
| ST 9968 7103 (point) | ST97SE | Point |

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF042856 | Active |
| NBR Index Number - 42856 | Active |
| National Record of the Historic Environment to Historic Environment Records - 522325 | Active |
| National Monuments Record - ST 97 SE 83 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

**Monument Number** MWI80080

**Site Name** Former Late 17th Century House, Market Hill

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI80090

**Site Name** 83a The Pippin

**Monument Number**
MWI80090

**Record Type**
Monument

**Site Name** 83a The Pippin

House built early 19th century.

## Monument Types and Dates

HOUSE (Early C19 - 1801 AD to 1833 AD)

Early C19 - 1833 AD

Evidence EXTANT BUILDING

## Description and Sources

### Description - None recorded

<1> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 544375* (Digital archive). SWI29488.
House built early 19th century.

### Sources

(1) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 544375

### Associated resources - None recorded

## Location

### National Grid Reference

ST 9981 7121 (point) ST97SE Point

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References

| | |
|---|---|
| English Heritage Archives - BF086328 | Active |
| NBR Index Number - 86328 | Active |
| National Record of the Historic Environment to Historic Environment Records - 544375 | Active |
| National Monuments Record - ST 97 SE 84 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

### Other Land Classes - None recorded

### Related Monuments - None Recorded

### Finds - None recorded

**Monument Number** MWI80090

**Site Name** 83a The Pippin

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations - None recorded**

**Monument Number** MWI80155

**Site Name** St Margaret House, Church Street

| Monument Number | Record Type |
|---|---|
| MWI80155 | Monument |

**Site Name** St Margaret House, Church Street

A former Constitutional Club built in the late 1880s in 'Queen Anne' revival style. From the 1950s it became the Conservative Club and subsequently a large extension was built to the rear.

### Monument Types and Dates

CLUB (Built late 1880s, Late C19 - 1867 AD to 1900 AD)

Late C19 - 1900 AD

Evidence EXTANT BUILDING

### Description and Sources

**Description - None recorded**

<1> **English Heritage**, *English Heritage Listing Files, Adviser's report in file 504314/001, case number 164939.* (Unpublished document). SWI26310.

Not much is known about the history of the former Conservative Club, but it is very likely that it was built in the late-19th century as the Calne Constitutional Club. Kelly's Directory of 1889 states the latter was indeed situated in Church Street, however, later editions (1898, 1907 and 1915) suggest that its address was The Priory on New Road. One of the applicants states that the building was used by Calne Savings Bank prior to becoming the Calne Constitutional Club. Unfortunately, no conclusive evidence has been found to support this, but Kelly's Directory of 1889, 1898, 1907 and 1915 record that the Calne & District Building Society and the Calne Friendly Society had their offices on Church Street. The building marked on the Ordnance Survey map of 1886, appears to have a different footprint than that shown on the Ordnance Survey map of 1900, which shows a group of buildings, suggesting that by that date the building may have had undergone alterations, or possibly had been fully replaced. This group of buildings is described as a ¿Club¿ on the Ordnance Survey map of 1936. From the 1950s it became the Conservative Club and subsequently a large extension was built to the rear.

A former Constitutional Club built in the late 1880s by an unknown architect, in 'Queen Anne' revival style. The three storey high building has a tiled mansard roof resting on a block cornice. It has a central ashlar stone chimney stack to the front and rear, and north side. It is built in dressed stone with ashlar stone quoins and stone dressings. It has a double depth rectangular plan form, with a large one storey extension to the rear. The first and second floors of the two left-hand bays are in use as apartments, with the remainder of the building containing two large bar areas and function rooms to the front and rear with further function rooms on the floors above.

The front elevation has five bays, emphasised by plain Dutch gables to the top floor, each with a double casement window set above a string course. The floor below has five cross windows, and on the ground floor, articulated by a distinctive continuous hood mould above all its openings, are two entrances with arched door ways adorned with shell door hoods (the one to the left was recently removed). The decorative doors with Art Nouveau detailing are probably of early-20th century date, with later alterations. Each door is flanked to its right by large two light (shop) windows with a row of small, round arched fixed lights above. The large (shop) window to the right, now blocked, has a door to the far right, also blocked. The north side elevation is two bays wide with an entrance to the left flanked to the right by a casement window (late-20th century) and a three-light casement (probably late-20th century). On first floor level is a cross window to the left with to its right a decorative corbel stack. From the north-east corner of the building, at first floor level, springs a decorative arch (linked with the building to its north), marking the access to Ivy Walk from Church Street. From Ivy Walk the rear elevation is partly visible above the large single storey extension, and appears to have Dutch gables to the bays, some of which are projecting forward.

Internally, the apartment block to the left contains various late 19th century features including a tiled

floor in the narrow hallway, door and window carpentry throughout, stairs with turned balusters resting on a panelled balustrade to the bottom half, small fire places with decorative surrounds and original grates in most of the rooms. The former Club next door has some late-19th century features on the top floor, including part of the stairs, door and window carpentry, and two small fireplaces with decorative surrounds and original grates, all to the same design as in the apartment block.
Due to their increase in popularity, many political and/or gentlemen's clubs appeared in the late 19th century. They were either newly built or adopted and converted from an existing townhouse. In order for a building of this type and date to merit designation, its design, layout and decorative features, both internally and externally, have to be of a high standard and mostly intact. The building has a monumental facade with some interesting architectural detailing. It also contains some late-19th century internal features surviving on the upper floors. However, overall, both the exterior and interior do not display the quality or architectural distinction needed for the building to merit designation on a national level. Additionally, the loss of most of its ground floor interior, mainly through the impact of the large, late-20th century rear extension, has not only had a very negative impact on its historic character, but also resulted in the loss of most of its rear elevation. Nevertheless, although the building is not of special interest in the national context, it does continue to make a very positive contribution to the local historic street scene. This is confirmed by its inclusion within the Calne Conservation Area since 1973, and it was noted that within this area it takes a very prominent position, standing opposite St Mary's Church.
<2> **Historic England**, Various, *National Record of the Historic Environment (NRHE) Entry, 1479321* (Digital archive). SWI29488.

### Sources

(1) Unpublished document: English Heritage. English Heritage Listing Files. Adviser's report in file 504314/001, case number 164939.

(2) Digital archive: Historic England. Various. National Record of the Historic Environment (NRHE) Entry. 1479321

### Associated resources - None recorded

## Location

### National Grid Reference

Centred ST 9984 7085 (36m by 20m) ST97SE Dispersed

### Administrative Areas

Civil Parish Calne, North Wiltshire, Wiltshire

### Address/Historic Names - None recorded

## Designations, Statuses and Scorings

### Associated Designations - None recorded

### Other Statuses and Cross-References

| | |
|---|---|
| Legacy System Number - 164939 | Active |
| National Record of the Historic Environment to Historic Environment Records - 1479321 | Active |
| National Monuments Record - ST 97 SE 104 | Active |

### Ratings and Scorings - None recorded

## Land Use

### Associated Historic Landscape Character Records - None recorded

**Monument Number** MWI80155

**Site Name** St Margaret House, Church Street

**Other Land Classes - None recorded**

**Related Monuments - None Recorded**

**Finds - None recorded**

**Associated Events/Activities - None recorded**

**Associated Individuals/Organisations**

| | |
|---|---|
| Duterloo-Morgan, Fridy - English Heritage | Site Inspector |