Existing Internal Door Schedule

		Location	Leaf Configuration	Approx. Leaf Width	Approx. Leaf Height	Required Fire Rating	Required Acoustic Rating	Door & Frame Finish	Vision Panel	Ironmongery Set	Kick Plates	Works Required	Notes
X-IDG	01	G.06 Dame's Office	Single Leaf	900	2100	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-IDG	02	C.01 Entrance Foyer	Single Leaf	1020	2200	-		White painted timber 4 panel door - arched head	-		-	Dual direction swing	
X-IDG	03a	C.01 Entrance Foyer	Single Leaf	960	2100	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-IDG	03b	G.02 Master's Study	Single Leaf	960	2100	-		White painted timber 4 panel door	-		-		
X-IDG	04	G.02 Master's Study	Single Leaf	900	2100	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-IDG	05	G.03 Social Space	Single Leaf	900	2100	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-IDG	06	G.04 Social Space	Single Leaf	900	2100	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-IDG	07	G.05 Staf WC	Single Leaf	730	2000	-		White painted timber 4 panel door	-		-		
X-IDG	09	G.04 Social Space	Single Leaf	880	2100	-		White painted timber 4 panel door	-		-		
X-IDG	24	G.11 Brew	Single Leaf	825	1900	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-IDG	31	C.02 Corridor	Single Leaf	700	2000	FD30s		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	01	1.01 Tutor Room	Single Leaf	820	2060	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	02	C.11 Corridor	Single Leaf	790	2050	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	03	1.04 Collaborative Working	Single Leaf	850	2050	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	04	1.03 Collaborative Working	Single Leaf	850	2050	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	05	1.02 Social Space	Single Leaf	788	2000	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	09	1.03 Collaborative Working	Single Leaf	740	2120	-		White painted timber 4 panel door				Locked Shut	
X-ID1	11	1.04 Collaborative Working	Single Leaf	810	2030	-		White painted timber 4 panel door				Locked Shut	
X-ID1	12	1.05 Collaborative Working	Single Leaf	824	2060	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	14	1.06 Laundry	Single Leaf	780	1850	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	15	C.12 Corridor	Single Leaf	830	1850	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	16	1.07 Laundry	Single Leaf	745	1950	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	17	1.08 Store	Single Leaf	695	1850	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	19	1.09 Collaborative Working	Single Leaf	745	2130	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	20	C.14 Corridor	Single Leaf	835	2080	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	22	1.11 Social Space	Single Leaf	820	2080	-		White painted timber 4 panel door	-		-		
X-ID1	23	1.10 Collaborative Working	Single Leaf	820	2080	FD30S		White painted timber 4 panel door	-		-	*Fire Upgrade	
X-ID1	24	1.10 Collaborative Working	Single Leaf	840	2090	-		White painted timber 4 panel door				Locked Shut	
X-ID1	25	1.11 Social Space	Single Leaf	840	2070	-		White painted timber 4 panel door				Locked Shut	

Note:
To be read in conjuction with floor plans 241108-1410 - 1413

Refer to Ironmongery Scheudle

Doors to NBS spec L20 280

***Fire upgrade**
Where existing panellled timber doors are required to be fire doors, these are to be upgraded or made fire resistant by an approved competent historic door contractor to provide the correct level of fire resistance. Methods to upgrade fire doors include using fire resistant paint, splitting the door and providing a fire-resistant core. Where existing listed doors are deemed not suitable to be upgraded due to them not being solid timber doors or damaged then they should be replaced with a certified FD30s fire door and the original door stored for future preservation.

Rev	Date	By	Ap	Note
P04	22/05/2026	JY	LB	Planning Update

Do not scale this drawing

Kendall Kingscott
Glentworth Court, Lime Kiln Close,
Stoke Gifford, Bristol, BS34 8SR
+44 (0)117 931 2062
www.kendallkingscott.co.uk

Project
Masters Lodge Conversion

Client
Marlborough College

Date: March 2025
Purpose/Status: TENDER
Scale: 1:100
Drawn: BM
Checked: GA
Paper Size: ISO A2
Filename: 241108 Masters Lodge_GA Master Planning.vwx

Drawing Title
Internal Door Schedule Existing

Project Number/Drawing Number: 241108-5200
Check all dimensions and levels on site
Revision: P04

© Copyright
Only to be used on the site for which designed. The electronic transmission of designs/information contained in this drawing is carried out entirely at the User's risk and Kendall Kingscott Ltd. will have no liability for any errors or inaccuracies arising therefrom. The production of amended or updated information from the said designs/information by the User is entirely the responsibility of the User and Kendall Kingscott Ltd. shall have no responsibility in respect thereof whatsoever.