

Stonekraft Restoration
1-3 Chichester Park
Court
Westbury
Wiltshire
BA13 3AN

Helen Garside
Regarding 36 - 41 Hill Steet

Trowbridge
BA14 8LB

[REDACTED]
[REDACTED]
[REDACTED] (mobile
1st August 2026

**Stonekraft Restoration :- Bath stone window surround
replacement\Brickwork 36 – 41 Hill St Court, Trowbridge**

Dear Helen,

I can confirm that all sections A,B,C,D indicated in the stone window surround photo as discussed would need carefully need replacing as the stone is badly decayed and beyond repair. From ordering stone to taking out carefully existing stone work would take a week with use of safely propping and supporting and fixing in with new Bath stone Stokes ground base bed a hard wearing durable stone we have used many times before and would be a good colour match to existing and using masons putty (lime mortar) for fixing .

Regarding the brick façade ,take out numbers of damaged bricks and replace with near matching as possible and fix with lime mortar .Brush off much as possible loose paint so surface left ready for possible for painting what ever is decided .

The overall works in total would be 7 to 8 weeks with painting also for scaffolders to erect and take down scaffolding .Also taking away hardcore rubbish .

We would require a permit for parking .

Please be assured we we would carry out the restoration with care and attention we are on list for Historic England previously carrying out repairs on Monkton Combe Lockup and also for in the past for The National Trust at Westwood Manor, Stourhead House & Montacute House.

If you have any queries please do not hesitate to contact us,

Yours sincerely Brian & Martin Turk.