

From: Stephen Gray
Subject: Fwd: Revised quote / stove installation
Date: 21 Jul 2026 at 18:51:07
To: lornagray.

Sent from my iPhone

Begin forwarded message:

From: Lee Conway <lee.conway@stanleystoves.co.uk>
Date: 17 June 2026 at 10:54:20 BST
To:
Subject: Revised quote / stove installation

Hi Steve ,

It was great to chat yesterday to potentially install your Stanley stove already onsite.

As you mentioned yesterday, you are due to have a new thatch roof installed and all brickwork ect to make the 1.82 clearance needed for building regs.
Also scaffolding will be in place. (please don't install the pot until installation)

As discussed, as you have a thatch property , the plan is to install a Twinwall chimney system from the top down as it passes through the thatch area (please leave chimney open) roughly 3 m including a meter above. This will provide the best protection.
It will then adapt into a flexible chimney liner for the rest of the chimney to a point above the stove where additional Twinwall flue will be needed to protect the oak beam exposed inside the chimney breast.

After investigation all works seem very straightforward.

The quote is as follows:

- 1 x Twinwall all weather cowl / birdguard
- 3 x 1 m Twinwall lengths
- 1 x 30 / 45 degree Twinwall bend (above stove)
- 1 x 500 Twinwall length (above stove to protect beam)

1 x flat base support plate
1 x Twinwall to flexible liner adaptor
6 m flexible liner
1 x ma adaptor yo flexible liner
All connecting flue to stove
1 x register plate

1 x carbon monoxide alarm
1 x stove thermometer
1 x HETAS certification (j4 notice)
Sundries

Labour 1 day =

Grand total =

This price includes all materials for a complete installation & sign off.
All works can be completed using a scaffold that I presume will be in place for chimney build.,
All furniture and floors will be covered & protected.

If you have any questions or queries, please get in touch ,
Thanks
Lee

LMC Fires 