




NOTES:

1. Existing window re-opened to increase natural light to Bedroom 5. New timber-framed double glazed casement windows to match existing. Refer to joinery details.
2. Existing timber-paneled wall replaced with new stud wall to improve sound insulation and privacy in Bedroom 7.
3. Fixtures and fittings removed and bathrooms refurbished to modern standards.
4. 2 no. modern fixed lights to floor in Hallway 2 removed and floor repaired.
5. Door from the Landing to Bedroom 1 blocked up to form new Dressing Room. Door re-used for new ensuite.
6. Bedroom 1 converted into a new dressing room and ensuite bathroom for the Master Bedroom.
7. Floor generally refurbished. All existing wallpaper removed, plaster assessed and walls replastered as necessary in lime plaster.
8. All existing secondary glazing removed and windows refurbished and redecorated.
9. Services, including heating, hot water, incoming cold water supply and the electrical installation assessed and upgraded to modern standards.
10. New wall-mounted air conditioning system to the Master Bedroom.



Built fabric to be removed.

A

AUGUST 2026

MURHILL HOUSE
MURHILL

REFURBISHMENT
DRW REF: HS-04-26-03
FIRST FLOOR

AS PROPOSED

SCALE: 1/100@A3

Scale— 1:100

