

To all church roof areas: roof tiles, felt and battens removed. Any damaged roof timbers replaced or treated as appropriate. New bat-friendly felt and insulation installed between battens, where feasible. Existing tiles of appropriate condition to be reinstated, with new tiles to match the existing replacing those that cannot be reinstated. Reinstated and new clay tiles to be laid in a pattern replicating the existing. Flashings in lead.

Crevice bat box for Common Pipistrelles

Cavity bat box for Brown Long-eared bats

Extract fan discharge terminal

Existing door removed. opening infilled; stone up to internal FFL, timber panelling above with window. Timber finish to match refurbished entrance doors.

Removal of gas supply pipes to exterior of building

Hall building outline (behind)

Proposed Southeast Elevation

C	22/09/2026	Bat boxes added per Alder Ecology advice
B	13/08/2026	Note added for works to roof
A	15/01/2026	Drawing label corrected

Rev.	Issue date	Revision Notes
------	------------	----------------

PLANNING

olearygoss
ARCHITECTS

Chapel House
11a Alexandra Park
Bristol BS6 6QB
T 0117 989 2661
E mail@olearygoss.co.uk
W www.olearygoss.co.uk

Project Title
Holt United Reformed Church
89 The Street, Holt
BA14 6RS

Drawing Title
**Proposed Church
Southeast Elevation**
Project No. Drawing No. Revision
3343 PA_169_C

Date 22/12/2025 Scale 1:50 @ A1 / 1:100 @ A3
Drawn by CW Checked by JG

