

ECOLOGICAL ASSESSMENT REPORT

28th September 2026

The Bell House Hotel, Sutton Benger,
Wiltshire, SN15 4RH

Applicant: Cocklebury Farmhouse Homes

Agent/planner: LP Planning

DOCUMENT CONTROL:

Version:	1
Issue:	Final (further surveys completed)
Authored by:	Zoe Barrett MSc
Report reviewed by:	Amy Parsons BSc (Hons) ACIEEM
Client:	Cocklebury Farmhouse Homes
Planning agent:	LP Planning
Local Planning Authority (LPA):	Wiltshire Council
Note to LPA:	n/a

VERSION HISTORY:

Version:	Date:	Author:	Description of change:
1	22 nd June 2022	James Gooding BSc (Hons) & Laurence Wills BSc (Hons)	Draft version changed to final version.
2	4 th March 2024	James Gooding BSc (Hons) & Laurence Wills BSc (Hons)	Inclusion of BNG.
3	12 th February 2025	Zoe Barrett MSc	Removal of BNG.

DISCLAIMER:

The copyright of this document remains with ABR Ecology Ltd ("ABR"). The contents of this document therefore must not be copied or reproduced in whole or in part for any purpose without the written consent of ABR.

ABR shall not be liable for the use of this report for purposes other than those for which the report was prepared and provided; and accept no responsibility for any documents or information supplied to ABR by others.

This document has been prepared in accordance with CIEEM's Guidelines for Ecological Report Writing (CIEEM, 2017) and Biodiversity Net Gain Report & Audit Templates (CIEEM, 2021).

This report may contain sensitive data pertaining to particularly vulnerable species. It is the responsibility of the Local Planning Authority to determine whether data and information contained within his report is made publicly available.

At the time of writing, standard methodologies have been used which are accepted by Natural England and other statutory bodies. No responsibility will be accepted where standard methodologies change and where Government, national bodies and industry subsequently modify standards.

This report has been produced using all reasonable skill and care, and a Quality Assurance (QA) review process has been conducted prior to issue of this report.

SURVEY DATA LIFESPAN AND VALIDITY OF THIS REPORT:

Unless otherwise explicitly stated, survey data contained within this report is valid for 12 months from the survey date in accordance with the Chartered Institute of Ecology and Environmental Management (CIEEM) Advice note (CIEEM, 2019) due to the presence of and/or potential for mobile species to be present within the site. However, should the condition on-site change substantially during this 12-month period, and/or if the nature/extent of the development changes, then this report may not be valid, and a reassessment of the site may be required.

This report has been prepared to identify the presence of protected species and habitats within the site, where this falls within the scope of the agreed works.

Survey data has a limited lifespan for mitigation licence applications with Natural England. Update surveys may be required e.g. in the event a bat licence is required; survey data must be sought from the then current survey season (May to August).

The results of the surveys and this assessment are representative at the time of the surveys taking place.

	ABR Ecology Ltd	T: 01202 821 325
	First Floor Offices, 35 Black Moor Rd,	E: abrecology@gmail.com
	Verwood, Dorset BH31 6AT	W: www.abrecology@gmail.com

CONTENTS

NON-TECHNICAL SUMMARY	3
1. INTRODUCTION	6
2. METHODOLOGY	8
3. RESULTS	18
4. COMPENSATION, MITIGATION AND ENHANCEMENT PLAN	28
5. REFERENCES	32
Appendix A – Site and existing plans	34
Appendix B – Proposed plans	38
Appendix C - Relevant legislation and planning policy	41
Appendix D: Photographs	45
Appendix E – Pre and post-development habitat maps & floral species lists	54
Appendix F – Bat evidence map	56
Appendix G: Bat activity (dusk) survey results	57
Appendix H: Locations of bat roosts, bat exit/entry points & surveyor locations	61
Appendix I – Biodiversity mitigation, compensation and enhancement plan	62

NON-TECHNICAL SUMMARY

- ◆ ABR Ecology Ltd were commissioned by LP Planning on behalf of their client Cocklebury Farmhouse Homes to produce an Ecological Assessment report for The Bell House Hotel, Sutton Benger, Wiltshire, SN15 4RH.
- ◆ This report was requested to inform a planning application for “*proposed internal and external alterations to hotel to include demolition of single storey toilets and associated works.*”

Survey background:

- ◆ A Preliminary Ecological Appraisal (PEA) including a Preliminary Roost Appraisal (PRA) was originally conducted on the 22nd April 2022 by class licenced ecologist Russell Hoyle ACIEEM and assistant ecologist James Gooding. The survey was then updated by class licenced ecologist Laurence Wills and assistant ecologist Georgia Linter on the 12th June 2023 and again by class licenced ecologist Becci Smith MCIEEM and assistant ecologist Zoe Barrett on the 7th January 2025.
- ◆ A suite of three bat activity (two dusk and one dawn) surveys were conducted on the 25th May and the 12th and 27th June 2023.

Habitats and Statutory Biodiversity Metric (SBM):

- ◆ Area habitats onsite include modified grassland (g4), introduced shrub (u1-847), bramble scrub (h3d), individual urban trees (u1-32), developed land; sealed surface (u1b6) and a building (u1b5). No hedgerows or watercourses are present on-site. No priority habitats (S41 NERC Act 2006) were recorded onsite.

Protected sites and Ecological Networks:

- ◆ No impacts on statutory or non-statutory sites are anticipated as part of the works. No Ecological Networks exist onsite; therefore, no recommendations are made in relation to Networks.

Badgers:

- ◆ No evidence of badgers was recorded onsite; no mitigation is recommended for this species.

Barn owls and other nesting birds:

- ◆ No evidence of barn owl and no potential foraging habitats were recorded on-site. Evidence of nesting birds was identified on-site on the northwest elevation of the hotel

building; and there is potential for nesting birds within the individual trees, scrub and introduced shrub on site. Mitigation for nesting birds is provided in Section 4.

Bats:

- ◆ The PRA undertaken on the 22nd April 2022 identified the building to hold 'high potential' for roosting bats in line with national survey guidelines. Bat droppings were recorded within the loft void, identified to belong to brown long-eared bats by DNA analysis.
- ◆ Three bat activity (two dusk and one dawn) surveys were conducted on the property to determine the roost types, numbers of bats, location of access points and species of bat roosting within the property.
- ◆ The activity surveys identified a maximum count of one common pipistrelle bat emerging from the property during any one survey. The building has been assessed to support a day roost for one common pipistrelle bat and an assumed day roost for brown long-eared bats based on dropping evidence.
- ◆ **The proposed works will not impact either of the identified bat roosts as works are isolated internally, not impacting the loft voids, and to the single-storey rear flat roof extensions to be demolished was identified as holding 'negligible potential' for roosting bats. If the proposed plans change and works are to impact the loft voids or to the roof or eaves, then a bat European Protected Species (EPS) licence from Natural England will be required following planning approval and prior to any works commencing to ensure works are lawful.** It is the responsibility of the applicant to arrange for application of the licence.
- ◆ Bats are foraging and commuting across the site; measures for lighting reduction are detailed in Section 4 to minimise impacts of obtrusive lighting on foraging and commuting bats that may be using the gardens and general surrounding area.

Dormice:

- ◆ The site is not considered likely to support dormice; no mitigation is provided for this species.

Hedgehogs:

- ◆ There is potential for hedgehog onsite and there are hedgehog records nearby; mitigation is provided in Section 4.

Reptiles, common amphibians and great crested newts (GCN):

- ◆ GCN, reptiles and common amphibians are not considered to be impacted, and no mitigation is provided for these species provided the vegetation onsite is maintained short (<5cm) before and during the works.

Biodiversity enhancements:

- ◆ To ensure the proposed development is compliant with the National Planning Policy Framework (NPPF) and Core Policy 50 of the Wiltshire Core Strategy, biodiversity enhancements are required as part of the development. An enhancement strategy is provided in Section 4 of this report.

1. INTRODUCTION

- 1.1 ABR Ecology Ltd were commissioned by LP Planning on behalf of their client Cocklebury Farmhouse Homes to produce an Ecological Assessment report for The Bell House Hotel, Sutton Benger, Wiltshire, SN15 4RH (central grid reference: ST 94716 78670) (herein referred to as 'the site' / 'on-site'). This report was requested to inform a planning application for *“proposed internal and external alterations to hotel to include demolition of single storey toilets and associated works.”*
- 1.2 A Preliminary Ecological Appraisal (PEA) including a Preliminary Roost Appraisal (PRA) was originally conducted on the 22nd April 2022 by class licenced ecologist Russell Hoyle ACIEEM and assistant ecologist James Gooding. The survey was then updated by class licenced ecologist Laurence Wills and assistant ecologist Georgia Linter on the 12th June 2023 and again by class licenced ecologist Becci Smith MCIEEM and assistant ecologist Zoe Barrett on the 7th January 2025.
- 1.3 A suite of three bat activity (two dusk and one dawn) surveys were conducted on the 25th May, 12th and 27th June 2023.
- 1.4 Site plan and existing plans are provided in Appendix A and proposed plans are provided in Appendix B.

Site context

- 1.5 The application site is located in the village of Sutton Benger, Wiltshire and consists of a public house/hotel and garden with scattered trees throughout the site and in the adjacent properties. The site is immediately surrounded by residential housing in a semi-rural location. Amenity grassland is present approximately 60m from the site with arable land, grazing pasture and hedgerow networks in the wider landscape. Woodland is present approximately 390m northwest and The River Avon is located approximately 780m northeast of the site. The immediate surrounding landscape is considered to provide good opportunities for urban wildlife and the wider landscape is considered to provide excellent habitats for a variety of wildlife.

Aims and scope of the report

- 1.6 This assessment primarily aims to determine the biodiversity value of the site and looks to identify the presence/likely absence of protected and vulnerable species on-site. This report also aims to evaluate whether there will be any potential development impacts on protected species and habitats and identifies whether mitigation and/or

protected species licensing is required to ensure the development complies with legislation and national and local planning policy.

Relevant planning policy and legislation

1.7 Full details of relevant planning policy and legislation are provided in Appendix C of this report; the following policy and legislation in respect of biodiversity is applicable to this application:

- ◆ The Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019
- ◆ The Wildlife and Countryside Act 1981 (as amended) – Section 1 and Schedules 1 and 5
- ◆ The Environment Act 2021 – Part 6 Schedule 14
- ◆ Town and Country Planning Act 1990 – Schedule 7A (as inserted by Schedule 14 of the Environment Act 2021)
- ◆ The National Planning Policy Framework (NPPF) 2026 – Section 19 ‘Conserving and Enhancing the Natural Environment’: Policies N1-N6
- ◆ National Planning Practice Guidance Natural Environment - para 10-35
- ◆ The Natural Environment and Rural Communities (NERC) Act 2006 – Sections 40 and 41
- ◆ Circular 06/05: Biodiversity and Geological Conservation – Statutory Obligations and Their Impact Within the Planning System
- ◆ The Wiltshire Core Strategy – Core Policy 50: Biodiversity and Geodiversity

1.8 It is the responsibility of the applicant(s) to ensure that the proposed development proceeds in full compliance with legislation, national and local policy, and in accordance with all conditions of the obtained planning consent(s). It is also the responsibility of the applicant(s) to request a report amendment / reassessment of the site where the scale/nature of the proposed plans subsequently change.

2. METHODOLOGY

Desktop data search

- 2.1 Protected sites under the UK National Site Network including Special Protection Areas (SPAs) and Special Areas of Conservation (SACs), and Ramsars were identified within 7.5 kilometre (km) of the site; and Sites of Special Scientific Interest (SSSIs), National Nature Reserves (NNRs), and Local Nature Reserves (LNRs) were identified within 2km of the site using the Multi-Agency Geographical Information for the Countryside (MAGIC) website (MAGIC, 2026).
- 2.2 A search was also conducted on MAGIC (2026) to identify the potential presence of priority habitats, European Protected Species (EPS) licences and known great crested newt breeding ponds.
- 2.3 Wiltshire & Swindon Biological Records Centre (WSBRC) (2025) were contacted to provide records of protected, vulnerable and notable species, Sites of Importance for Nature Conservation (SINCs) and Ecological Networks within a 1km radius of the application site.
- 2.4 This information was used to evaluate the potential of the site for protected and vulnerable species, and to determine whether there is potential for development impacts on these species, surrounding habitats and protected sites.

Botanical survey (UKHab)

- 2.5 A botanical survey of the site was originally conducted on the 22nd April 2022 by experienced botanist Russell Hoyle ACIEEM and assistant ecologist James Gooding. The botanical survey was then updated on the 12th June 2023 by experience ecologist Laurence Wills and assistant ecologist Georgia Linter and again on the 7th January 2025 by experience botanist Becci Smith MCIEEM and assistant ecologist Zoe Barrett.
- 2.6 Habitats on site were classified and coded in accordance with the UKHab Classification System, using the UK Habitat Classification Definitions document Version 2.0 (UKHab Ltd, 2023a) and UKHab Field Key Version 2.1 (UKHab Ltd, 2023b). Other features of ecological interest were identified using 'target notes'. Habitats were assigned both primary and secondary (essential and additional) UKHab codes, where relevant.
- 2.7 The survey involved a detailed flora survey of habitats, and each flora species was allocated an abundance in accordance with the DAFOR scale, using local (L) as a pre-fix where a species was restricted in distribution across the habitat:

D – Dominant

A – Abundant

F – Frequent

O – Occasional

R – Rare

Protected species assessment

Badgers

- 2.8 A walkover was conducted looking for potential evidence of badgers *Meles meles*. Evidence of badgers can include the presence of setts (underground burrows), ‘snuffle marks’ (nose marks and scratches from badger foraging within the earth), latrines (territorial marking sites), scats, hair, footprints, and well-worn paths.

Barn owls and other nesting birds

- 2.9 A search was conducted for evidence of barn owl *Tyto alba* and other nesting birds within and around the buildings and vegetation. Evidence of nesting birds can include the physical presence of chicks and/or adult birds, nesting material, eggs and/or egg casings, feathers, white splashing (droppings), and pellets (for barn owls).

Bats – Daytime Bat Walkover (DBW)

- 2.10 A Daytime Bat Walkover (DBW) survey was conducted to record any habitats suitable for roosting bats. This included a Preliminary Roost Appraisal (PRA) of buildings and trees for bat suitability as detailed below.

Survey conditions, equipment and timings

- 2.11 Survey information for the Preliminary Roost Assessment (PRA) is provided in Table 1 below:

Table 1: Weather conditions, equipment and timings for survey

Survey date	Time of survey	Surveyors	Equipment used	Weather conditions		
22/05/2022	11:00am	Russell Hoyle ACIEEM and James Gooding	High-powered torch, mirrors, sealable bags, FFP3 face masks, gloves, extendable ladder, endoscope, binoculars	Temp:	Okta cloud cover:	Beaufort wind force:
				12°C	8/8	1/12
12/06/2023	20:00pm	Laurence Wills and Georgia Linter	High-powered torch, mirrors, sealable bags, FFP3 face masks, gloves, extendable ladder,	Temp:	Okta cloud cover:	Beaufort wind force:
				20°C	2/8	0/12

			endoscope, binoculars			
07/01/2025	11:30am	Becci Smith MCIEEM and Zoe Barrett	High-powered torch, mirrors, sealable bags, FFP3 face masks, gloves, extendable ladder, endoscope, binoculars	Temp:	Okta cloud cover:	Beaufort wind force:
				4°C	6/8	2/12

- 2.12 The surveying ecologists have received training in Working at Heights (and in-house training in the use of ladders for PRA surveys), Manual Handling, and Emergency First Aid At Work to ensure compliance with Health and Safety legislation (The Work at Height Regulations 2005, Manual Handling Operations Regulations 1992, The Health and Safety (First-Aid) Regulations 1981).

Buildings

- 2.13 The PRA was undertaken in accordance with The Bat Conservation Trust (BCT) Good Practice Survey Guidelines (Collins, 2016; Collins, 2023). A systematic search was made of any internal building areas / loft spaces and exterior building areas. Where present, information was compiled on the potential and actual bat entry/exit points (where possible); potential and actual bat roosting locations; and any evidence of bats found.
- 2.14 The external building assessment included an inspection of the ground/flooring, and where present, any windowsills, windowpanes, behind peeling paintwork/lifted render, brick/block work, chimneys, eaves, lead flashing, tiles and soffits etc.
- 2.15 Evidence of roosting bats in buildings can include:
- ◆ The presence of physical live/deceased bats
 - ◆ Bat droppings (distinguished from rodent droppings by their crumbly texture)
 - ◆ Fur-oil staining around entry/exit points
 - ◆ Urine splashing
 - ◆ Feeding remains, such as insect wings and casings
- 2.16 The building was identified as a 'confirmed' bat roost where bat evidence was recorded. If droppings were present, a sample of the bat droppings were collected and couriered to Swift Ecology Ltd for DNA analysis to confirm the species of bat present.
- 2.17 Most native bats in England are crevice-dwelling species, with bats roosting in remote areas, such as under roof tiles; behind cladding; in cavities; soffits; and behind lead flashing etc, and evidence of these species is often concealed and/or inaccessible.

Therefore, where no evidence of roosting bats was recorded, an assessment on the availability of potential roosting areas and bat exit/entry points around the building(s) was conducted. The building(s) were then assigned a category based on a sliding scale of potential for bats, ranging from ‘none’ to ‘high’ (Collins, 2023) (Table 2 below):

Table 2: Guidelines for assessing the potential suitability of buildings for bats (Collins, 2023)

Bat roosting potential	Description
‘High’	A structure with one of more potential roost sites that are obviously suitable for use by larger numbers of bats on a more regular basis & potentially for longer periods of time due to their size, shelter, protection, conditions (temperature, humidity, height above ground level, adverse light levels, or high levels of disturbance), and surrounding habitat. The structure has the potential to support high conservation status roosts for example maternity or classic cool/stable hibernation sites.
‘Moderate’	A structure with one or more potential roost sites that could be used by bats due to their size, shelter, protection, conditions (temperature, humidity, height above ground level, adverse light levels, or high levels of disturbance), and surrounding habitat but unlikely to support a roost of high conservation status (with respect to roost type only, such as maternity & hibernation and this is made irrespective of species conservation status, which is established after presence if confirmed via the PRA).
‘Low’	The building features one or more potential roosting features that could be used by bats opportunistically at any time of year. However, these potential roost sites do not provide enough space, shelter, protection, appropriate conditions (temperature, humidity, height above ground level, adverse light levels, or high levels of disturbance) and/or suitable surrounding habitat to be used on a regular basis or by a larger number of bats.
‘Negligible’	There are no obvious habitat features likely to be used by bats, however there is a small element of uncertainty as bats can use small and apparently unsuitable features on occasion. (*negligible is defined as ‘so small or unimportant as to be not worth considering, insignificant’. This category may be used where there are places that a bat could roost or forage (due to one attribute), but it is unlikely that they would (due to another attribute).
‘None’	No habitat features on site likely to be used by any roosting bats at any time of the year (i.e. a complete absence of crevices/suitable shelter at all ground/underground levels).

Trees

- 2.18 A Ground-Level Tree Assessment (GTLA) was undertaken in accordance with The BCT Guidelines (Collins, 2023). A systematic search was made of any trees onsite for bats and where present, information was compiled on the potential and actual bat entry/exit points (where possible); potential and actual bat roosting locations; and any evidence of bats found.

2.19 The inspection was carried out systematically and consistently around all parts of each tree (from all angles and close to the trunk and further away). Potential Roosting Features (PRFs) that can be exploited by bats include the following (Table 3 below):

Table 3: Potential Roosting Features (PRFs) for bats in trees

PRFs formed by disease and decay	PRFs formed by damage	PRFs formed by association
Woodpecker holes	Lightning strikes	Fluting Ivy
Squirrel holes	Hazard beams	
Knot holes	Subsidence cracks	
Pruning cuts	Shearing cracks	
Tear outs	Transverse snaps	
Wounds	Welds	
Cankers	Lifting bark	
Compression	Desiccation	
Forks	Fissures	
Butt rots	Frost cracks	

2.20 Trees were categorized in accordance the scale shown in Table 4 below:

Table 4: Categories for assigning tree potential for roosting bats

Suitability	Description
NONE	Either no PRFs in the tree or highly unlikely to be any.
FAR	Further assessment required to establish if PRFs are present in the tree.
PRF	A tree with at least one PRF present.

2.21 The above assessment was further refined for any trees with identified Potential Roosting Features (PRFs) which were categorized in accordance with the following scale (Table 5 below) (Collins, 2023):

Table 5: Categories for assigning tree potential for roosting bats

Suitability	Description
PRF-I	PRF is only suitable for individual bats either due to size or lack of suitable surrounding habitats.
PRF-M	PRF is suitable for multiple bats and may therefore be used by a maternity colony.

- 2.22 The tree was identified as a ‘confirmed’ bat roost where bat evidence was recorded. If droppings were present, a sample of the bat droppings were collected and couriered to Swift Ecology Ltd for DNA analysis to confirm the species of bat present.

Bats – Bat activity (dusk and dawn) surveys

- 2.23 A total of four surveyors undertook each survey on the existing hotel building. Timings and weather conditions for each survey are provided in Table 6 below:

Table 6: Timings and weather conditions for dusk and dawn activity surveys

Survey date	Timings	Surveyors	Equipment used	Weather conditions		
25/05/2023 – Dusk emergence survey	Start: 20:53 Sunset: 21:07 End: 22:45	Russell Hoyle, Aaron Templar, Chris Payne & Lewis Collins	Echo Meter Touch 2 with tablet x 4	Temp:	Okta cloud cover:	Beaufort wind force:
				Start: 15°C End: 14°C	0/8	0/12
12/06/2023 – Dusk emergence survey	Start: 21:05 Sunset: 21:25 End: 23:00	Laurence Wills, Chris Payne, Caitlin McQuillan & Georgia Linter	Echo Meter Touch 2 with tablet x 4 & Sony AX33 with two 15 LED IR floodlights	Temp:	Okta cloud cover:	Beaufort wind force:
				Start: 19°C End: 19°C	2/8	0/12
27/06/2023 – Dawn re-entry survey	Start: 03:23 Sunrise: 04:53 End: 05:08	Zoe Barrett, Aaron Templar, Kieran Mullany & Emily Parsons	Echo Meter Touch 2 with tablet x 4	Temp:	Okta cloud cover:	Beaufort wind force:
				Start: 12°C End: 12°C	8/8	0/12

- 2.24 The surveys were conducted in accordance with the BCT Good Practice Survey Guidelines (Collins, 2016; Collins, 2023) and the Interim Guidance Note: Use of Night Vision Aids for bat emergence surveys and further comment on dawn surveys (BCT, 2022).
- 2.25 The surveys involved a direct observation of the external building to identify any bats emerging from their roosts. The ecologists used automated bat detectors and a Night Vision Aid (NVA) (one Sony AX33 with two 15 LED IR floodlights) to identify any later emerging species and to identify bats where vision was limited (for example, roofs

under the cover of tree canopies). A screenshot of the 'darkest point' of the surveys captured using the NVA is provided in Appendix G.

- 2.26 Where present, information was compiled on the species, numbers, access points, roosting locations and flight paths. Information was also obtained on general activity on site such as foraging and commuting bats crossing the property.
- 2.27 The dusk surveys commenced 15 minutes before sunset and finished between 1.5-2hrs after sunset. The dawn survey commenced 1.5hrs before sunrise and finished 15 minutes after sunrise. The surveys were conducted when the temperature was 10°C with no strong winds or precipitation.
- 2.28 Following the dusk surveys, the footage from the NVA was reviewed by an analyst using a motion detection software. Bat calls were analysed using Kaleidoscope Pro Analysis Software.

Bat impact assessment

- 2.29 Following the CIEEM Bat Mitigation Guidelines (Reason, P.F. and Wray, S, 2023), the roost(s) onsite were classified in accordance with the following roost types:
- Day roost
 - Night roost
 - Maternity roost
 - Satellite roost
 - Hibernation roost
 - Feeding perch and
 - Transitional roost
- 2.30 Information on the roost type(s) and rarity of the bat species within a geographical context was used to assess the importance of the roost(s). Maternity and hibernation roosts are of higher importance than day/night or transitional roosts, which are lower in conservation value due to supporting low numbers of bats; maternity roosts support high numbers of bats and contribute more significantly to the population of the species and are therefore of higher importance.

- 2.31 Roosts are assigned a value based upon 'Guidelines for Ecological Impact Assessment (EcIA)' (CIEEM, 2018), this ranges from 'site' importance (day roosts of common species) to 'national' importance (hibernation roosts of Annex II species).
- 2.32 Once the roost(s) on site were identified and classified, the 'Minimum Expectations for Bat Mitigation Compensation, Monitoring and Management' (Natural England, 2023) document was used to design an appropriate bat mitigation, compensation and enhancement plan.

Dormice

- 2.33 An assessment was conducted to evaluate the suitability of the habitats on site for the dormouse *Muscardinus avellanarius*, a small, nocturnal mammal which occupies habitats including hedgerows, scrub, woodland and treelines. The dormouse requires good habitat connectivity and suitable food resources providing fruit, nuts, nectar and/or insects throughout the year. Where hazel *Corylus avellana* was present, a search was also made for any hazelnuts on the ground with characteristic gnaw marks.

Great crested newts

- 2.34 The habitats on site were assessed for their potential to support the great crested newt *Triturus cristatus* (GCN). GCN occupy both aquatic and terrestrial habitats, spending most of their life cycle on land and a short period of the year for breeding and egg-laying. Suitable terrestrial habitats can include grassland, woodland, hedgerows, scrub, and tall herb communities; and suitable overwintering (hibernation) sites can include piles of materials such as rubble/logs and at the base of buildings/stone walls.
- 2.35 GCN are known to travel up to 500 metres (m) from their breeding sites; for this reason, an aerial assessment was made prior to the site visit to determine if any waterbodies were present onsite and around the site (offsite). Any accessible waterbodies were assessed under the Habitat Suitability Index (HSI) (Oldham *et al*, 2000, 2008) to determine the suitability of the waterbody to support great crested newts.

Hedgehogs

- 2.36 The habitats on site were assessed for their potential to support hedgehogs *Erinaceus europaeus* and a search was undertaken for any evidence such as hedgehog scats. Suitable habitats for hedgehog can include hedgerows, grassland, shrubbery, woodland edges and gardens.

Reptiles and common amphibians

- 2.37 An appraisal of the habitats on site was conducted to evaluate their suitability for common British reptiles, such as slow worm *Anguis fragilis*, common lizard *Zootoca vivipara*, grass snake *Natrix natrix* and adder *Vipera berus*, and common amphibians such as common frog *Rana temporaria* and common toad *Bufo bufo*.
- 2.38 Suitable habitats for reptiles and amphibians include those with a varied structure, offering a range of niches for basking and foraging. Typical habitats include rough and unmanaged grassland with shorter margins, heathland, ponds/pond margins, woodland, scrub and ruderal vegetation. Potential overwintering (hibernation) sites can include piles of materials such as rubble/logs, rockeries and at the base of buildings/stone walls.

Survey limitations and assumptions

PEA and UKHabs survey

- 2.39 The site visit provides a 'snapshot' of the site and does not take into account seasonal variation. Species may have been overlooked due to the constraints of the season and time in which the survey was undertaken. A lack of evidence of a species does not confirm its absence from site, rather there was no indication of its presence at the time of survey.
- 2.40 An aerial search for waterbodies can be constrained by the accuracy of online maps. Several websites were accessed to minimise the chances of missing waterbodies, however, garden ponds within residential properties are very rarely mapped and it is possible that waterbodies have been overlooked as part of this assessment.
- 2.41 Certain species, such as bats and nesting birds, are highly mobile and it is therefore possible for these species to occupy the site at any time in the future, particularly if any alterations/changes occur to the site. The survey only provides a 'snapshot' in time and does not account for seasonal variation. As such, it is not possible to have complete certainty that species are not present, rather, there was no indication of their presence at the time of survey.
- 2.42 Often bats leave no visible sign of their presence on the outside of buildings/trees, and even when they do, wet weather can wash evidence away.

Reporting and survey lifespan

- 2.43 The data within this report should not be seen as comprehensive. Data obtained from the WSBRC (2025) data search is highly unlikely to be representative of the species

existing within the area. It is therefore possible that species may occur that have not been recorded in the area by the local records centre.

- 2.44 This report is considered valid for 12 months from the survey date in accordance with the CIEEM Advice note (CIEEM, 2019) for planning purposes only; and is only intended for the proposed plans outlined within this report. If any material changes to the site occurs or if the nature and/or extent of the proposed development changes, an update visit to reassess the site will be required, as any conclusions provided herein may not be valid.

3. RESULTS

Desktop data search

Statutory designated sites

- 3.1 MAGIC (2025) was used to identify SPAs and SACs as included under the UK National Site Network and Ramsars within 7.5km of the site; and nationally/locally protected sites (NNRs, LNRs, SSSIs) within 2km of the site. Results are presented in Table 7 below:

Table 7: Statutory designated sites around application site

Site name	Designation	Distance from application site (m/km)	Site description
Sutton Lane Meadows	SSSI	900m south	Sutton Lane Meadows is a botanically diverse area of unimproved neutral grassland in the Oxford Clay Vale of North Wiltshire. The site comprises two extremely herb-rich meadows which are cut for hay in late summer and then grazed in autumn. An exceptional variety of herbs occurs commonly in the sward, including lady's bedstraw, yarrow, common sorrel, common bird's-foot-trefoil and yellow-rattle. In addition, there are small numbers of meadow saffron, a plant which is known from only one other Wiltshire grassland site. The meadows are surrounded by species-rich hedges which attract birds such as yellowhammer and lesser whitethroat.

Impacts on statutory sites

- 3.2 No impacts on the above statutory sites are anticipated due to distance from the application site; no mitigation for statutory designated sites is recommended within this assessment.

Non-statutory designated sites

- 3.3 WSBRC (2025) provided records of non-statutory designated sites (SINCs) within 1km of the application site. The results are presented in Table 8 below:

Table 8: Non-statutory designated sites around application site

Site name	Designation	Distance from application site (m/km)	Site description
The Shrubbery	625m west	LWS	A small ancient, replanted woodland set in parkland with a stream running along the southern boundary.
Bristol Avon River	800m northeast	LWS	One of the main river systems draining north-west Wiltshire.
Sutton Lane Meadows	815m south	LWS	A small neutral meadow adjacent to a larger SSSI meadow.

Impacts on non-statutory designated sites

- 3.4 No impacts on the above non-statutory sites are anticipated due to distance from the application site; no mitigation for LWSs is recommended within this assessment.

Ecological Networks

- 3.5 No Ecological Networks were identified onsite; therefore, no further action is recommended in relation to Networks.

Priority habitats (S.41 NERC Act 2006)

- 3.6 From an aerial search, no priority habitats were identified onsite; the nearest area of priority habitat, deciduous woodland, is located 375m northwest of the site boundary (MAGIC, 2025). The proposed development is buffered by existing urban development and therefore no impacts on this habitat are anticipated.
- 3.7 No further mitigation is provided regarding priority habitats.

Protected and vulnerable species

- 3.8 WSBR (2025) provided records of protected, rare and vulnerable species within 1km of the application site. The results are presented in Table 9 below:

Table 9: Protected, rare and vulnerable species within 1km of the site

Common name	Scientific name	Number of records	Most recent record	Nearest record to site
Bats				
Brown long-eared bat	<i>Plecotus auritus</i>	5	2011	Within 1km
Common pipistrelle	<i>Pipistrellus pipistrellus</i>	4	2014	450m west
Lesser horseshoe	<i>Rhinolophus hipposideros</i>	3	2014	450m west
Myotis sp.	<i>Myotis sp.</i>	1	2014	450m west
Noctule	<i>Nyctalus noctula</i>	3	2011	620m west
Pipistrelle sp.	<i>Pipistrellus sp.</i>	1	1996	Within 1km
Serotine	<i>Eptesicus serotinus</i>	2	2014	450m west
Soprano pipistrelle	<i>Pipistrellus pygmaeus</i>	4	2014	450m west
Mammals				
Brown hare	<i>Lepus europaeus</i>	1	2016	1km south
Eurasian badger	<i>Meles meles</i>	16	2016	580m southeast
Eurasian otter	<i>Lutra lutra</i>	5	2018	50m north
Harvest mouse	<i>Micromys minutus</i>	3	1982	540m southeast
Rabbit	<i>Oryctolagus cuniculus</i>	7	2016	850m northwest
Water vole	<i>Arvicola amphibius</i>	1	1989	780m northeast
West European hedgehog	<i>Erinaceus europaeus</i>	13	2021	50m west
Birds				
Brambling	<i>Fringilla montifringilla</i>	15	2022	Within 1km
Cetti's warbler	<i>Cettia cetti</i>	7	2023	Within 1km
Fieldfare	<i>Turdus pilaris</i>	12	2021	Within 1km
Greylag goose	<i>Anser anser</i>	1	2020	Within 1km
Hobby	<i>Falco subbuteo</i>	1	2019	Within 1km
House sparrow	<i>Passer domesticus</i>	33	2022	80m southwest
Kingfisher	<i>Alcedo atthis</i>	31	2023	850m northeast
Quail	<i>Coturnix coturnix</i>	1	2019	Within 1km

Lapwing	<i>Vanellus vanellus</i>	3	2023	780m south
Lesser redpoll	<i>Acanthis cabaret</i>	2	2023	Within 1km
Little egret	<i>Egretta garzetta</i>	1	2020	Within 1km
Red kite	<i>Milvus milvus</i>	5	2021	Within 1km
Red wing	<i>Turdus iliacus</i>	26	2023	Within 1km
Reed bunting	<i>Emberiza schoeniclus</i>	21	2023	Within 1km
Skylark	<i>Alauda arvensis</i>	9	2005	465m southeast
Spotted flycatcher	<i>Muscicapa striata</i>	1	2019	Within 1km
Yellowhammer	<i>Emberiza citrinella</i>	33	2023	Within 1km
Plants				
Bluebell	<i>Hyacinthoides non-scripta</i>	7	2019	850m northwest
Butcher's-broom	<i>Ruscus aculeatus</i>	3	2018	850m northwest
Invertebrates				
Blood-vein	<i>Timandra comae</i>	1	2014	1km southwest
Cinnabar	<i>Tyria jacobaeae</i>	1	2023	1km southwest
Shaded broad-bar	<i>Scotopteryx chenopodiata</i>	1	2015	1km southwest
Small heath	<i>Coenonympha pamphilus</i>	9	2020	830m south
Reptiles and amphibians				
Common toad	<i>Bufo bufo</i>	1	2005	815m northwest
Grass snake	<i>Natrix natrix</i>	2	2014	470m southwest
Great crested newt	<i>Triturus cristatus</i>	2	2018	1km south
Slow worm	<i>Anguis fragilis</i>	2	2014	470m southwest

3.9 There are records for long-eared, *Myotis* and lesser horseshoe bats within the area. There is potential for changes in artificial lighting to impede foraging and commuting bats that may be using the general site; therefore, lighting specifications are detailed in Section 5 of this report to reduce obtrusive lighting impacts on bats.

3.10 There are nearby records for badgers, hedgehogs, reptiles and amphibians; further discussion for these species is provided under 'Protected species' further on in Section 3.

Habitat survey – UKHabs

3.11 A baseline (pre-development) habitat map with floral species lists is provided in Appendix E and photos in Appendix D of this report. A summary of the habitats recorded onsite is presented in Table 10 below:

Table 10: Habitats recorded onsite as listed under the UK Habitat Classification system

Habitat	Primary UKHab code	Secondary UKHab code(s) ¹	Description	Area of the site
Buildings	u1b5	818	An existing hotel building is present to the west of the site.	West of the site.
Developed land; sealed surface	u1b6	-	Hard standing is present in the form of a car park in the centre of the site.	Centre of the site.
Modified grassland	g4	108	Modified grassland that is regularly mown (108) is present to the north, east and south of the site, comprising lawn gardens for the hotel.	North, east and south of the site.

Introduced shrub	u1	847	Introduced shrub is present throughout the site.	Throughout the site.
Bramble scrub	h3d	-	A small area of bramble scrub is present within the green area to the east of the site, surrounded by introduced shrub and individual trees.	East of the site.
Urban trees	u1	32	A number of individual urban trees are present throughout the site to the east of the hotel building.	Throughout the site.

1: See Appendix E for list of UKHabs secondary codes

Impacts of development on existing habitats

- 3.12 The proposals will result in the demolition of the single-storey extension housing toilets, single-storey extension and stairs at the rear of the property and internal works only. No habitats on-site are to be lost or degraded because of the proposed development.
- 3.13 Mandatory Biodiversity Net Gain has not been considered as part of this report as the development is subject to the de minimis exemption. The de minimis exemption includes development that does not impact a priority habitat and impacts >25m² of on-site habitat and >5m of linear habitat, such as hedgerows.

Protected species

Badgers

- 3.14 16 badger records exist within 1km of the site (WSBRC, 2025). Despite the presence of suitable foraging habitat, no evidence to suggest badgers are present onsite was identified during the survey.
- 3.15 Based on a lack of evidence onsite, badgers are not considered to be impacted by the proposals and are not discussed further in this assessment.

Barn owls and other nesting birds

- 3.16 No evidence of barn owl was recorded on site and there are no known barn owl records within 1km of the site (WSBRC, 2025). There are currently little to no barn owl foraging habitats present on site due to the shorter nature of vegetation and urban nature of the site. Therefore, this species is not considered to be impacted and is not discussed further in this assessment.
- 3.17 Nesting birds were recorded on the northwest elevation of the existing hotel building during a dusk survey; however, this section of the building will not be impacted as part of the planned works. Additionally, the eaves around the building, the individual trees, introduced shrub and scrub on site provides suitable nesting habitat for birds. A mitigation and compensation strategy for nesting birds is provided in Section 4 of this report.

Bats

Daytime Bat Walkover (DBW)

Buildings

3.18 Descriptions of the buildings surveyed for roosting bats with any identified potential bat access points and roosting areas are provided in Table 11 below (see Appendix E for building locations and Appendix D for photographs):

Table 11: Building description

Building	Description
Hotel ('B1')	- The two-storey hotel is constructed of brick elevations. - The roof consists of a series of pitched, hipped and flat bituminous roofs. - Stone tiled roofs are present on the south, west and north elevations and the adjoining single-storey reception. - Concrete hip and roof tiles are present on the southern pitch of the northern building section. - A skylight is present on the northern aspect of the southern pitched roof. - A series of internal brick chimneys are present including one on the northern section pitch, one on the southern north pitch and two on the western pitch. - A mixture of wooden and stone doorframes and window frames are present. - Wooden soffits and fascia are present. - Wooden cladding is present on the upper half of the elevations in the central courtyard. - A single-storey extension with a pitched stone tiled roof and concrete ridge is present with a porch in the east. - Two flat roof single-storey extensions are present on the rear southern elevation. - A flat roof single-storey extension is present to the south of the northern building section within the central courtyard. - Internally, a series of loft voids are present, three of which were accessed in the west and one which was viewed but not entered in the north. An additional void was also present in the south and within the east extension porch which were surveyed on the 12th June 2023. Description of the voids accessed are provided below: Void 1 - The loft is in the south of the west roof pitches and runs south to north and measures approximately; 7.5m in length, 5m in width and 2.5m in height to the apex. - A timber ridge beam is present along the length of the loft along with purlins and collar beams. - The roof is lined with breathable membrane and bituminous 1F felt. - Fibreglass insulation present. - A water tank is present. - A chimney is present in the northern of the void and separates void 1 from void 2. Void 2 - The loft is in the centre west roof pitches and runs south to north and measures approximately; 7m in length, 4m in width and 2.8m in height to the apex. - A timber ridge beam is present along the length of the loft along with purlins and collar beams. - The roof is lined with a mixture of breathable membrane and bituminous 1F felt. - No insulation is present.

	Void 3 - The loft is in the north of the west roof pitches and runs south to north and measures approximately; 7m in length, 4m in width and 2.3m in height to the apex. - A timber ridge beam is present along the length of the loft along with purlins and collar beams. - The roof is lined with bituminous 1F felt and has areas without any lining. - No insulation is present. - A chimney is present on the east side and separates void 3 from void 4.	
	Void 4 - The loft is in the north and runs west to east and measures approximately; 15m in length, 5m in width and 2m in height to the apex. - The void could be viewed from Void 3 but was inaccessible. - A timber ridge beam is present along the length of the loft along with purlins and collar beams. - A chimney is present. - The roof has no lining. - No insulation is present.	
	Void 5 - The loft void is in the southeast and runs southwest to northeast, measuring approximately; 23m in length, 7m in width and 2m in height. - The roof is constructed from ridge beam, purlin, collar and support struts. - Bituminous 1F felt is present. - Fibreglass insulation is present with no boarding. - A water tank and water system are present. - Partially removed internal walls are present.	
	<i>Potential access points:</i>	<i>Potential roosting areas:</i>
	- Multiple gaps under the stone roof tiles throughout the roofs. - Gaps at the tiles and mortar around the chimneys. - Gaps at the verges of the stone tiled roofs. - Gaps at the tiles around the skylight. - Gaps at the hatch to the void within the porch. - Gap above a timber beam above a window on the eastern elevation.	- Roosting between the roof tiles and roof lining. - At the internal beams, stone chimney and gable tops within the loft spaces. - Between the roof tiles around the chimneys and skylight. - Between the timber beam and brickwork on the eastern elevation.
	<i>Evidence of bats recorded (refer to map in Appendix F):</i>	
	- One bat dropping recorded adjacent to the loft hatch (void 1). - Approximately 20 bat droppings under the ridge beam with possible staining on the ridge beam from bats (void 2). - Four butterfly wings (potential bat feeding remains) at the bottom of the southern chimney (void 2). - Five butterfly wings at the bottom of the chimney on the eastern side of the loft (void 3).	
	<i>DNA analysis of dropping sample (as tested by Swift Ecology Ltd):</i>	
	- Droppings confirmed to belong to brown long-eared bats.	
	<i>Roost status / potential of the building for bats:</i>	
	'Confirmed roost' for roosting bats	

3.19 Bat droppings and feeding remains were identified within loft voids 1, 2 and 3, therefore the building supports a 'confirmed' roost for brown long-eared bats (confirmed by DNA analysis of droppings).

3.20 Three bat activity (dusk and dawn) surveys were conducted upon the building in accordance with the BCT Guidelines (Collins, 2016); the results of the surveys are provided below.

Bat activity (dusk) surveys

3.21 The dusk surveys were undertaken upon the building and a summary of the survey results are provided in Table 12 below (full results are provided in Appendix G and a map showing the locations of bat roosts / bat exit/entry points with surveyor locations is provided in Appendix H of this report):

Table 12: Summary of results from the dusk surveys

Date of survey	Bats recorded emerging from/re-entering the building	General bat activity recorded on site
25/05/2023	One common pipistrelle bat emerged from beneath the wooden fascia of the eaves at the western end of the southern extension and commuted eastwards at 21:39.	- The following species were recorded generally commuting and foraging across the site during the survey: - Soprano pipistrelle - Serotine - Noctule - Common pipistrelle - Myotis sp.
12/06/2023	No bats were recorded emerging from the building.	- The following species were recorded generally commuting and foraging across the site during the survey: - Common pipistrelle - Soprano pipistrelle - Serotine - Myotis sp.
27/06/2023	No bats were recorded re-entering the building.	- The following species were recorded generally commuting and foraging across the site during the survey: - Soprano pipistrelle - Common pipistrelle - Long-eared bat sp. - Noctule - Serotine

Discussion and bat impact assessment

3.22 Bat roosts were identified within the property, the roosts have been classified in accordance with the CIEEM Bat Mitigation Guidelines (Reason, P.F. and Wray, S, 2023), as shown in Table 13 below:

Table 13: Impact assessment of the works on the onsite bat roosts

Roost reference	Species	Roost type	Maximum count of bats during any one survey	Location of access point/roost	Importance of roost	Impact
-----------------	---------	------------	---	--------------------------------	---------------------	--------

Roost 1	Brown long-eared bat	Day roost	n/a	Within loft space (roost)	Site	No impact
Roost 2	Common pipistrelle	Day roost	1	Behind fascia board of the eaves on the southern extension (roost and access point)	Site	Loss

- 3.23 The roosts were classified as day roosts as the survey data does not indicate the presence of a maternity roost. No brown long-eared bats were recorded emerging and so it is assumed that the building supports a day roost in the absence of bats emerging.
- 3.24 The building does hold limited bat hibernation potential in external crevices between the tiles and the felt; however, it is not possible to determine if a hibernation roost is present without lifting every tile and potentially destroying roosts. In accordance with the BCT Guidelines (Collins, 2023) assessment for hibernation roosting potential, the building does not support traditional hibernation features such as underground sites/tunnels/basements and so the site is deemed to hold low potential to support hibernating bats. No further survey works are deemed to be required in relation to hibernation roosts.
- 3.25 The proposals will not impact upon the identified roosts for brown long-eared bat and common pipistrelle as the proposed works are isolated to internal works, not impacting the loft voids, and demolition of the existing single-storey flat roof extension housing the toilets and the rear single-storey extension and stairs.
- 3.26 **If the proposed plans change and works are to impact the loft voids or to the roof or eaves, then a bat European Protected Species (EPS) licence from Natural England will be required following planning approval and prior to any works commencing to ensure works are lawful.**
- 3.27 No further surveys or licensing requirements are recommended, however, further information regarding the validity of this report and what to do in the unlikely event a bat is unexpectedly found is provided in Section 4 of this report.

Trees

- 3.28 The trees on-site were assessed for their potential to support roosting bats; all trees onsite were not considered to hold potential for roosting bats due to a lack of Potential Roost Features (PRFs) and/or smaller size. No further action is recommended in

relation to roosting bats and trees; however, further information is provided in Section 5 regarding the validity of the survey.

Artificial Lighting at Night (ALAN)

- 3.29 The development is anticipated to result in a change to Artificial Lighting At Night (ALAN) through internal light spill and external light fixtures.
- 3.30 Illuminating a bat roost can cause disturbance and this may result in the bats abandoning the roost or even becoming entombed within it (BCT & ILP, 2023). Lighting is therefore considered an obstruction under the legislation protecting bats and their roosts. ALAN is consequently a key consideration and must be controlled to minimise impacts on bats that are roosting within the buildings on site.
- 3.31 A number of commuting and foraging bats were also recorded across the general property and within the gardens. Bats are very sensitive to artificial lighting, which can impede their ability to successfully forage and can alter flightpaths (BCT & ILP, 2023). As bats are using the property during nocturnal hours, it is also essential that new lighting is designed to minimise impacts on foraging bats, particularly around areas with mature vegetation such as trees and hedges. Light spill can extend beyond the site boundary and may therefore also impact bats using neighbouring land.
- 3.32 Specifications for new lighting designed to reduce impacts on bats are detailed in Section 4.

Dormice

- 3.33 No known dormouse records exist within the local area (WSBRC, 2025); the nearest European Protected Species (EPS) licence is located 12km southwest of the site (MAGIC, 2025) and the habitat on site is not considered suitable for dormice due to the site's urban location. Therefore, dormice are not considered to be affected by the proposed works and no mitigation is advised for this species.

Great crested newts

- 3.34 The site holds some potential for terrestrial great crested newts (GCN) around the fringes of the site, in the introduced shrub, scrub and roost bases of larger trees, however, the lawns are regularly maintained through a mowing regime and are at a short sward height, providing sub-optimal habitat. The site is surrounded by residential gardens and roads, and it is considered unlikely that GCN would be utilising the surrounding gardens due to fragmented habitat connectivity around the site.

- 3.35 There are no waterbodies within the site and an aerial assessment did not reveal any waterbodies within 250m of the site. The nearest record for GCN is approximately 1km south of the site (WSBRC, 2025). For these reasons, it is considered unlikely great crested newts would be impacted by the proposed development and no mitigation is advised for this species.

Hedgehogs

- 3.36 There are suitable habitats on-site for hedgehog including the modified grassland and introduced shrub which provide suitable foraging and sheltering grounds. There are 13 known records for hedgehog with the closest record approximately 50m west of the site (WSBRC, 2025).
- 3.37 Hedgehogs are a species of 'principal importance' under the NERC Act 2006 and have been in historic decline (Wembridge *et al.*, 2022); gardens and green spaces are an important refuge for urban populations of this species.
- 3.38 There is therefore potential for hedgehogs to be present onsite during the nocturnal hours and potential for an overall loss in foraging habitat and severance of commuting through installation of garden fencing. Mitigation for this species is provided in Section 4 of this report.

Reptiles and common amphibians

- 3.39 There is some suitable habitat on site for reptiles limited to the bramble scrub and introduced shrub. However, the site is surrounded by urban development on all sides, with no green corridors or connectivity to suitable habitat for these species. The lawns are maintained through a mowing regime and are at a short sward height, providing sub-optimal habitat.
- 3.40 For these reasons, reptiles and common amphibians are considered unlikely to be impacted by the proposed development provided the site is maintained as existing and these species are not considered further in this assessment.

4. COMPENSATION, MITIGATION AND ENHANCEMENT PLAN

Bats

Conclusions of roosting bats

- 4.1 The PRA and dusk surveys of The Bell House Hotel were undertaken, and the building was identified to support day roosts for an individual common pipistrelle bat and a low number of brown long-eared bats which are of 'site' importance. The proposals for internal works and demolition of the single-storey flat-roof extension housing the toilets and rear single-storey extension and stairs will not impact on the identified roosts. Therefore, bats are not considered to be impacted as part of the proposed works and no further action is recommended.
- 4.2 **If the proposed plans change and works are to impact the loft voids or to the roof or eaves then a bat European Protected Species (EPS) licence from Natural England will be required following planning approval and prior to any works commencing to ensure works are lawful.**
- 4.3 The survey can only be considered valid for 12-18 months from the survey date in accordance with the CIEEM Advice Note (CIEEM, 2019). The 12-18 month period is considered acceptable where the condition of the building on site remain unchanged since the survey and the proposals for the site are unchanged. If any changes to the plans occur, or if 12-18 months pass and no works have been undertaken, this report and any conclusions provided will not be valid. In this event, it is the responsibility of the applicant to contact ABR Ecology to determine whether an amended report or resurvey of the site is required.
- 4.4 Due to the localised nature of the work, that will not be impacting the identified bat roosts, an update site visit has been deemed to not be required to update this report.
- 4.5 **In the unlikely event bat(s) are encountered at any stage, work must cease immediately and Natural England or a suitably qualified bat ecologist must be sought for advice by the applicant/landowner.** The applicant must be aware of the severe penalties associated with bat crimes and their legal obligation to report this information.
- 4.6 In the event a bat is unexpectedly discovered, the nature of the advice will concern allowing the bat(s) to leave of their own accord or waiting for a licensed person to remove the bat(s). A bat licence may then be deemed necessary following the

necessary survey work. **All persons including contractors are explicitly forbidden from handling bats or interfering with bats in any way.**

Foraging and commuting bats

4.7 Bat records exist within the local area, however, the site is not located adjacent to dark unlit habitats and/or rural habitats, and so the full lighting specifications as outlined in the 'Bats and Artificial Lighting At Night' Guidance Note BN08/23 (BCT & ILP, 2023) is not considered appropriate for the site. However, artificial lighting will be kept to a minimum as detailed below:

- ◆ Preferably, no net increase in external light fixtures will be installed. If external lighting is required, this will be limited and only installed where required for safety purposes. Light fixtures will only be installed at doorways/at the site entrance etc to allow for visibility.
- ◆ All luminaires installed will lack UV elements when manufactured. Metal halide, compact fluorescent sources will not be used.
- ◆ LED luminaires only will be used due to their sharp cut-off, lower intensity, good colour rendition and dimming capability.
- ◆ A warm white light source (2700Kelvin or lower) will be adopted to reduce blue light component.
- ◆ Light sources will feature peak wavelengths higher than 550nm to avoid the component of light most disturbing to bats (Stone, 2012).
- ◆ No lighting will be permitted within 5m of the bat/bird boxes / identified bat roosts within the building.

Hedgehogs

4.8 The site likely supports hedgehog due to surrounding urban garden networks and the presence of nearby records. The following measures will be followed to ensure they are protected during works and to ensure habitat connectivity is maintained:

- ◆ Any new fencing and boundaries proposed around the gardens will feature a minimum of one hedgehog highway (130mm x 130mm hole) along every boundary to ensure habitat connectivity for hedgehogs (Appendix I); this can comprise either a specialised hedgehog highway gravel board (<https://www.garden-fence-panels.co.uk/concrete-posts-bases/concrete->

[gravel-boards/hedgehog-friendly-concrete-base-panel-plain/](#)) or if timber gravel boards are used a custom-made hole.

- ◆ A hedgehog highway sign will also be installed above each highway to encourage new occupiers to keep these open for hedgehogs (can be purchased from <https://shop.britishhedgehogs.org.uk/product/hedgehog-highway-sign/>).
- ◆ During works, any trenches/pits will be boarded over at the end of each working day or alternatively a 130mm wide ramp/board will be installed in each trench/pit to allow hedgehogs to escape.
- ◆ Materials must be stored on pallets raised off the ground and away from surrounding vegetation to discourage hedgehogs from taking refuge within them.

Nesting birds

4.9 Nesting birds were recorded on the northwest elevation of the building during one of the dusk activity surveys, however, this area will be fully retained and unaffected by the proposed works. The individual trees introduced shrub and bramble scrub provide suitable nesting habitat for birds. Therefore, the following mitigation strategy will be strictly adhered to, this will minimise impacts on potential nesting birds on site and within the vicinity:

- ◆ Any scaffolding that may be required on-site for any of the proposed works will be in the form of a temporary scaffolding tower that will be lowered following the conclusion of its use each day of the construction. The scaffolding will not obstruct any of the eaves and must remain a minimum of 1m below the eaves around the building.
- ◆ Any demolition works or vegetation clearance should take place between the start of September and the end of January when birds are least likely to be nesting. However, it must be noted that some species, such as wood pigeons *Columba palumbus*, nest all year round and so works should proceed with caution during this time.
- ◆ Where this is not possible and works take place between the start of February and end of August, a pre-works check for nesting birds must be undertaken by a suitably experienced ecologist. If an active nest is encountered, all works must cease immediately, and the nest must be left undisturbed. The ecologist will establish a works exclusion zone around the nest and this will be marked

out with hazard tape and signage put up; a second site visit by the ecologist to check nest occupation will be required before works can continue in this area. Works may only continue when the nest is deemed to be unoccupied/no longer active by the ecologist. A camera to monitor nesting activity may be necessary.

- ◆ **If a bird's nest is encountered at any other unsupervised time, all works in the area must cease immediately the ecologist must be contacted immediately to provide further advice.**

Biodiversity enhancements

4.10 Features will be included within the proposed development to enhance the site for biodiversity (Appendix I for plan and specifications). The new dwellings will feature the following:

- ◆ One 'Vivara Pro Build-in WoodStone Bat Boxes' (<https://www.nhbs.com/vivara-pro-build-in-woodstone-bat-box>) or similar approved will be installed in the northwestern elevation of the existing building during construction.
- ◆ Two 'PRO UK Rendered Build-In Swift Box' or similar approved (<https://www.nhbs.com/vivara-pro-rendered-build-in-swift-box-uk-brick-size>) will be installed in the northwestern elevation of the existing building during construction.
- ◆ Two 'BeePot Bee Hotels' or similar approved (<https://www.wildcare.co.uk/greenblue-beepot-large-planter-bee-house.html>) will be installed in the gardens of the hotel in a south facing position.

5. REFERENCES

Bat Conservation Trust (BCT) (2022). *Interim Guidance Note: Use of Night Vision Aids for bat emergence surveys and further comment on dawn surveys.*

Bat Conservation Trust (BCT) and Institute for Lighting Professionals (ILP) (2023). *Bats and Artificial Lighting At Night' Guidance Note BN08/23.* BCT, London. Accessed from: <https://theilp.org.uk/publication/guidance-note-8-bats-and-artificial-lighting/>

CIEEM (Chartered Institute of Ecology and Environmental Management) (2017a). *Guidelines for Ecological Report Writing (2nd ed).* CIEEM, Winchester. Accessed from: <https://cieem.net/resource/guidelines-for-ecological-report-writing/>

CIEEM (Chartered Institute of Ecology and Environmental Management) (2017b). *Guidelines for Preliminary Ecological Appraisal (2nd ed).* CIEEM, Winchester. Available from: <https://cieem.net/resource/guidance-on-preliminary-ecological-appraisal-gpeal/>.

CIEEM (Chartered Institute of Ecology and Environmental Management) (2018). *Guidelines for Ecological Impact Assessment in the UK and Ireland.* Accessed from: <https://cieem.net/resource/guidelines-for-ecological-impact-assessment-ecia/>

CIEEM (Chartered Institute of Ecology and Environmental Management) (2019). *Advice Note On The Lifespan Of Ecological Reports & Surveys.* CIEEM, Winchester. Accessed from: <https://cieem.net/resource/advice-note-on-the-lifespan-of-ecological-reports-and-surveys/>

Collins, J (ed) (2016). *Bat Surveys for Professionals Ecologists: Good Practice Guidelines (3rd Edition).* The Bat Conservation Trust, London.

Collins, J (ed) (2023). *Bat Surveys for Professionals Ecologists: Good Practice Guidelines (4th Ed).* BCT, London. Accessed from: <https://www.bats.org.uk/resources/guidance-for-professionals/bat-surveys-for-professional-ecologists-good-practice-guidelines-4th-edition>

Coreo (2024). *Coreo application.*

DEFRA (2021). *European protected sites requiring nutrient neutrality strategic solutions.* Accessed from: <https://publications.naturalengland.org.uk/file/6565585214504960>

Department for Communities and Local Government (2005). *Circular 06/2005: Biodiversity and Geological Conservation – Statutory Obligations and their Impact within the Planning System.*

Department for Levelling Up, Housing and Communities (2026). *The National Planning Policy Framework (NPPF).*

JNCC (The Joint Nature Conservation Committee) (2016). *UK BAP priority habitats.*

JNCC (The Joint Nature Conservation Committee) (2016). *UK BAP priority terrestrial mammal species.*

- MAGIC (2026). *Search for Priority Habitat Inventory habitats, EPS licences, GCN ponds and statutory sites around The Bell House Hotel, Sutton Benger*. Accessed from: <https://magic.defra.gov.uk/MagicMap.aspx>
- Oldham, R.S., Brady, L.D., Sewell, D.L. & Baker J.M.R. (2008). *ARG UK Advice Note 5: Great Crested Newt Habitat Suitability Index*. Amphibian and Reptile Groups of the United Kingdom.
- Oldham, R.S., Keeble, J., Swan, M.J.S. & Jeffcote, M. (2000). *Evaluating the suitability of habitat for the Great Crested Newt (Triturus cristatus)*. Herpetological Journal 10 (4), 143-155.
- Stone, E.L., Jones, G., Harris, S. (2012). *Conserving energy at a cost to biodiversity? Impacts of LED lighting on bats*. Glob. Change Biol. 18, 2458–2465.
- UKHab Ltd (2023a). *UK Habitat Classification Version 2.0*. Accessed from: <http://www.ukhab.org/>
- UKHab Ltd (2023b). *UK Habitat Classification Field Key*. Accessed from: <http://www.ukhab.org/>
- Wembridge, D., Johnson, G., Al-Fulaij, N., & Langton, S. (2022). *The State of Britain's Hedgehogs 2022*. British Hedgehog Preservation Society (BHPS) and People's Trust for Endangered Species (PTES). Accessed from: <https://www.hedgehogstreet.org/about-our-hedgehog-street-campaign/stateof/>
- Wiltshire Council (2015). *The Wiltshire Core Strategy (2015)*.
- Wiltshire & Swindon Biological Records Centre (WSBRC) (2025). *The Bell House Hotel, Sutton Benger – non-statutory sites and species data search 1km radius*.

Appendix A – Site and existing plans





786 The Bell House

Planning





CLIENT
OneTwoEight Co.
ADDRESS
The Bell House
47 High St
Sutton Benger
Chippenham
SN15 4RH

NOTE: BY DATE NOTES
1:500 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150 160 170 180 190 200 210 220 230 240 250 260 270 280 290 300 310 320 330 340 350 360 370 380 390 400 410 420 430 440 450 460 470 480 490 500 510 520 530 540 550 560 570 580 590 600 610 620 630 640 650 660 670 680 690 700 710 720 730 740 750 760 770 780 790 800 810 820 830 840 850 860 870 880 890 900 910 920 930 940 950 960 970 980 990 1000 1010 1020 1030 1040 1050 1060 1070 1080 1090 1100 1110 1120 1130 1140 1150 1160 1170 1180 1190 1200 1210 1220 1230 1240 1250 1260 1270 1280 1290 1300 1310 1320 1330 1340 1350 1360 1370 1380 1390 1400 1410 1420 1430 1440 1450 1460 1470 1480 1490 1500 1510 1520 1530 1540 1550 1560 1570 1580 1590 1600 1610 1620 1630 1640 1650 1660 1670 1680 1690 1700 1710 1720 1730 1740 1750 1760 1770 1780 1790 1800 1810 1820 1830 1840 1850 1860 1870 1880 1890 1900 1910 1920 1930 1940 1950 1960 1970 1980 1990 2000 2010 2020 2030 2040 2050 2060 2070 2080 2090 2100 2110 2120 2130 2140 2150 2160 2170 2180 2190 2200 2210 2220 2230 2240 2250 2260 2270 2280 2290 2300 2310 2320 2330 2340 2350 2360 2370 2380 2390 2400 2410 2420 2430 2440 2450 2460 2470 2480 2490 2500 2510 2520 2530 2540 2550 2560 2570 2580 2590 2600 2610 2620 2630 2640 2650 2660 2670 2680 2690 2700 2710 2720 2730 2740 2750 2760 2770 2780 2790 2800 2810 2820 2830 2840 2850 2860 2870 2880 2890 2900 2910 2920 2930 2940 2950 2960 2970 2980 2990 3000 3010 3020 3030 3040 3050 3060 3070 3080 3090 3100 3110 3120 3130 3140 3150 3160 3170 3180 3190 3200 3210 3220 3230 3240 3250 3260 3270 3280 3290 3300 3310 3320 3330 3340 3350 3360 3370 3380 3390 3400 3410 3420 3430 3440 3450 3460 3470 3480 3490 3500 3510 3520 3530 3540 3550 3560 3570 3580 3590 3600 3610 3620 3630 3640 3650 3660 3670 3680 3690 3700 3710 3720 3730 3740 3750 3760 3770 3780 3790 3800 3810 3820 3830 3840 3850 3860 3870 3880 3890 3900 3910 3920 3930 3940 3950 3960 3970 3980 3990 4000 4010 4020 4030 4040 4050 4060 4070 4080 4090 4100 4110 4120 4130 4140 4150 4160 4170 4180 4190 4200 4210 4220 4230 4240 4250 4260 4270 4280 4290 4300 4310 4320 4330 4340 4350 4360 4370 4380 4390 4400 4410 4420 4430 4440 4450 4460 4470 4480 4490 4500 4510 4520 4530 4540 4550 4560 4570 4580 4590 4600 4610 4620 4630 4640 4650 4660 4670 4680 4690 4700 4710 4720 4730 4740 4750 4760 4770 4780 4790 4800 4810 4820 4830 4840 4850 4860 4870 4880 4890 4900 4910 4920 4930 4940 4950 4960 4970 4980 4990 5000 5010 5020 5030 5040 5050 5060 5070 5080 5090 5100 5110 5120 5130 5140 5150 5160 5170 5180 5190 5200 5210 5220 5230 5240 5250 5260 5270 5280 5290 5300 5310 5320 5330 5340 5350 5360 5370 5380 5390 5400 5410 5420 5430 5440 5450 5460 5470 5480 5490 5500 5510 5520 5530 5540 5550 5560 5570 5580 5590 5600 5610 5620 5630 5640 5650 5660 5670 5680 5690 5700 5710 5720 5730 5740 5750 5760 5770 5780 5790 5800 5810 5820 5830 5840 5850 5860 5870 5880 5890 5900 5910 5920 5930 5940 5950 5960 5970 5980 5990 6000 6010 6020 6030 6040 6050 6060 6070 6080 6090 6100 6110 6120 6130 6140 6150 6160 6170 6180 6190 6200 6210 6220 6230 6240 6250 6260 6270 6280 6290 6300 6310 6320 6330 6340 6350 6360 6370 6380 6390 6400 6410 6420 6430 6440 6450 6460 6470 6480 6490 6500 6510 6520 6530 6540 6550 6560 6570 6580 6590 6600 6610 6620 6630 6640 6650 6660 6670 6680 6690 6700 6710 6720 6730 6740 6750 6760 6770 6780 6790 6800 6810 6820 6830 6840 6850 6860 6870 6880 6890 6900 6910 6920 6930 6940 6950 6960 6970 6980 6990 7000 7010 7020 7030 7040 7050 7060 7070 7080 7090 7100 7110 7120 7130 7140 7150 7160 7170 7180 7190 7200 7210 7220 7230 7240 7250 7260 7270 7280 7290 7300 7310 7320 7330 7340 7350 7360 7370 7380 7390 7400 7410 7420 7430 7440 7450 7460 7470 7480 7490 7500 7510 7520 7530 7540 7550 7560 7570 7580 7590 7600 7610 7620 7630 7640 7650 7660 7670 7680 7690 7700 7710 7720 7730 7740 7750 7760 7770 7780 7790 7800 7810 7820 7830 7840 7850 7860 7870 7880 7890 7900 7910 7920 7930 7940 7950 7960 7970 7980 7990 8000 8010 8020 8030 8040 8050 8060 8070 8080 8090 8100 8110 8120 8130 8140 8150 8160 8170 8180 8190 8200 8210 8220 8230 8240 8250 8260 8270 8280 8290 8300 8310 8320 8330 8340 8350 8360 8370 8380 8390 8400 8410 8420 8430 8440 8450 8460 8470 8480 8490 8500 8510 8520 8530 8540 8550 8560 8570 8580 8590 8600 8610 8620 8630 8640 8650 8660 8670 8680 8690 8700 8710 8720 8730 8740 8750 8760 8770 8780 8790 8800 8810 8820 8830 8840 8850 8860 8870 8880 8890 8900 8910 8920 8930 8940 8950 8960 8970 8980 8990 9000 9010 9020 9030 9040 9050 9060 9070 9080 9090 9100 9110 9120 9130 9140 9150 9160 9170 9180 9190 9200 9210 9220 9230 9240 9250 9260 9270 9280 9290 9300 9310 9320 9330 9340 9350 9360 9370 9380 9390 9400 9410 9420 9430 9440 9450 9460 9470 9480 9490 9500 9510 9520 9530 9540 9550 9560 9570 9580 9590 9600 9610 9620 9630 9640 9650 9660 9670 9680 9690 9700 9710 9720 9730 9740 9750 9760 9770 9780 9790 9800 9810 9820 9830 9840 9850 9860 9870 9880 9890 9900 9910 9920 9930 9940 9950 9960 9970 9980 9990 10000 10010 10020 10030 10040 10050 10060 10070 10080 10090 10100 10110 10120 10130 10140 10150 10160 10170 10180 10190 10200 10210 10220 10230 10240 10250 10260 10270 10280 10290 10300 10310 10320 10330 10340 10350 10360 10370 10380 10390 10400 10410 10420 10430 10440 10450 10460 10470 10480 10490 10500 10510 10520 10530 10540 10550 10560 10570 10580 10590 10600 10610 10620 10630 10640 10650 10660 10670 10680 10690 10700 10710 10720 10730 10740 10750 10760 10770 10780 10790 10800 10810 10820 10830 10840 10850 10860 10870 10880 10890 10900 10910 10920 10930 10940 10950 10960 10970 10980 10990 11000 11010 11020 11030 11040 11050 11060 11070 11080 11090 11100 11110 11120 11130 11140 11150 11160 11170 11180 11190 11200 11210 11220 11230 11240 11250 11260 11270 11280 11290 11300 11310 11320 11330 11340 11350 11360 11370 11380 11390 11400 11410 11420 11430 11440 11450 11460 11470 11480 11490 11500 11510 11520 11530 11540 11550 11560 11570 11580 11590 11600 11610 11620 11630 11640 11650 11660 11670 11680 11690 11700 11710 11720 11730 11740 11750 11760 11770 11780 11790 11800 11810 11820 11830 11840 11850 11860 11870 11880 11890 11900 11910 11920 11930 11940 11950 11960 11970 11980 11990 12000 12010 12020 12030 12040 12050 12060 12070 12080 12090 12100 12110 12120 12130 12140 12150 12160 12170 12180 12190 12200 12210 12220 12230 12240 12250 12260 12270 12280 12290 12300 12310 12320 12330 12340 12350 12360 12370 12380 12390 12400 12410 12420 12430 12440 12450 12460 12470 12480 12490 12500 12510 12520 12530 12540 12550 12560 12570 12580 12590 12600 12610 12620 12630 12640 12650 12660 12670 12680 12690 12700 12710 12720 12730 12740 12750 12760 12770 12780 12790 12800 12810 12820 12830 12840 12850 12860 12870 12880 12890 12900 12910 12920 12930 12940 12950 12960 12970 12980 12990 13000 13010 13020 13030 13040 13050 13060 13070 13080 13090 13100 13110 13120 13130 13140 13150 13160 13170 13180 13190 13200 13210 13220 13230 13240 13250 13260 13270 13280 13290 13300 13310 13320 13330 13340 13350 13360 13370 13380 13390 13400 13410 13420 13430 13440 13450 13460 13470 13480 13490 13500 13510 13520 13530 13540 13550 13560 13570 13580 13590 13600 13610 13620 13630 13640 13650 13660 13670 13680 13690 13700 13710 13720 13730 13740 13750 13760 13770 13780 13790 13800 13810 13820 13830 13840 13850 13860 13870 13880 13890 13900 13910 13920 13930 13940 13950 13960 13970 13980 13990 14000 14010 14020 14030 14040 14050 14060 14070 14080 14090 14100 14110 14120 14130 14140 14150 14160 14170 14180 14190 14200 14210 14220 14230 14240 14250 14260 14270 14280 14290 14300 14310 14320 14330 14340 14350 14360 14370 14380 14390 14400 14410 14420 14430 14440 14450 14460 14470 14480 14490 14500 14510 14520 14530 14540 14550 14560 14570 14580 14590 14600 14610 14620 14630 14640 14650 14660 14670 14680 14690 14700 14710 14720 14730 14740 14750 14760 14770 14780 14790 14800 14810 14820 14830 14840 14850 14860 14870 14880 14890 14900 14910 14920 14930 14940 14950 14960 14970 14980 14990 15000 15010 15020 15030 15040 15050 15060 15070 15080 15090 15100 15110 15120 15130 15140 15150 15160 15170 15180 15190 15200 15210 15220 15230 15240 15250 15260 15270 15280 15290 15300 15310 15320 15330 15340 15350 15360 15370 15380 15390 15400 15410 15420 15430 15440 15450 15460 15470 15480 15490 15500 15510 15520 15530 15540 15550 15560 15570 15580 15590 15600 15610 15620 15630 15640 15650 15660 15670 15680 15690 15700 15710 15720 15730 15740 15750 15760 15770 15780 15790 15800 15810 15820 15830 15840 15850 15860 15870 15880 15890 15900 15910 15920 15930 15940 15950 15960 15970 15980 15990 16000 16010 16020 16030 16040 16050 16060 16070 16080 16090 16100 16110 16120 16130 16140 16150 16160 16170 16180 16190 16200 16210 16220 16230 16240 16250 16260 16270 16280 16290 16300 16310 16320 16330 16340 16350 16360 16370 16380 16390 16400 16410 16420 16430 16440 16450 16460 16470 16480 16490 16500 16510 16520 16530 16540 16550 16560 16570 16580 16590 16600 16610 16620 16630 16640 16650 16660 16670 16680 16690 16700 16710 16720 16730 16740 16750 16760 16770 16780 16790 16800 16810 16820 16830 16840 16850 16860 16870 16880 16890 16900 16910 16920 16930 16940 16950 16960 16970 16980 16990 17000 17010 17020 17030 17040 17050 17060 17070 17080 17090 17100 17110 17120 17130 17140 17150 17160 17170 17180 17190 17200 17210 17220 17230 17240 17250 17260 17270 17280 17290 17300 17310 17320 17330 17340 17350 17360 17370 17380 17390 17400 17410 17420 17430 17440 17450 17460 17470 17480 17490 17500 17510 17520 17530 17540 17550 17560 17570 17580 17590 17600 17610 17620 17630 17640 17650 17660 17670 17680 17690 17700 17710 17720 17730 17740 17750 17760 17770 17780 17790 17800 17810 17820 17830 17840 17850 17860 17870 17880 17890 17900 17910 17920 17930 17940 17950 17960 17970 17980 17990 18000 18010 18020 18030 18040 18050 18060 18070 18080 18090 18100 18110 18120 18130 18140 18150 18160 18170 18180 18190 18200 18210 18220 18230 18240 18250 18260 18270 18280 18290 18300 18310 18320 18330 18340 18350 18360 18370 18380 18390 18400 18410 18420 18430 18440 18450 18460 18470 18480 18490 18500 18510 18520 18530 18540 18550 18560 18570 18580 18590 18600 18610 18620 18630 18640 18650 18660 18670 18680 18690 18700 18710 18720 18730 18740 18750 18760 18770 18780 18790 18800 18810 18820 18830 18840 18850 18860 18870 18880 18890 18900 18910 18920 18930 18940 18950 18960 18970 18980 18990 19000 19010 19020 19030 19040 19050 19060 19070 19080 19090 19100 19110 19120 19130 19140 19150 19160 19170 19180 19190 19200 19210 19220 19230 19240 19250 19260 19270 19280 19290 19300 19310 19320 19330 19340 19350 19360 19370 19380 19390 19400 19410 19420 19430 19440 19450 19460 19470 19480 19490 19500 19510 19520 19530 19540 19550 19560 19570 19580 19590 19600 19610 19620 19630 19640 19650 19660 19670 19680 19690 19700 19710 19720 19730 19740 19750 19760 19770 19780 19790 19800 19810 19820 19830 19840 19850 19860 19870 19880 19890 19900 19910 19920 19930 19940 19950 19960 19970 19980 19990 20000 20010 20020 20030 20040 20050 20060 20070 20080 20090 20100 20110 20120 20130 20140 20150 20160 20170 20180 20190 20200 20210 20220 20230 20240 20250 20260 20270 20280 20290 20300 20310 20320 20330 20340 20350 20360 20370 20380 20390 20400 20410 20420 20430 20440 20450 20460 20470 20480 20490 20500 20510 20520 20530 20540 20550 20560 20570 20580 20590 20600 20610 20620 20630 20640 20650 20660 20670 20680 20690 20700 20710 20720 20730 20740 20750 20760 20770 20780 20790 20800 20810 20820 20830 20840 20850 20860 20870 20880 20890 20900 20910 20920 20930 20940 20950 20960 20970 20980 20990 21000 21010 21020 21030 21040 21050 21060 21070 21080 21090 21100 21110 21120 21130 21140 21150 21160 21170 21180 21190 21200 21210 21220 21230 21240 21250 21260 21270 21280 21290 21300 21310 21320 21330 21340 21350 21360 21370 21380 21390 21400 21410 21420 21430 21440 21450 21460 21470 21480 21490 21500 21510 21520 21530 21540 21550 21560 21570 21580 21590 21600 21610 21620 21630 21640 21650 21660 21670 21680 21690 21700 21710 21720 21730 21740 21750 21760 21770 21780 21790 21800 21810 21820 21830 21840 21850 21860 21870 21880 21890 21900 21910 2192

786 The Bell House

Planning

ref.
 Oct 2018/18/19 Co.
 The Bell House
 47 High St
 Sutton Sanger
 Chippingham
 SN11 4BN



1:1000
 1:1000
 1:1000

EX elevations

786 - 3 - 04 A 11
 1:100 A1 L Oct 2025

ARTEL
 architects that build
 47 High St, Sutton Sanger, Chippingham, SN11 4BN
 01245 451111

Appendix B – Proposed plans



786 The Bell House

Planning

CLIENT
OneTwoEight Co.
ADDRESS
The Bell House
47 High St
Sutton Benger
Chippenham
SN15 4RH

REV	BY	DATE	NOTES
A	RCJ	20/05/2024	proposed permeability through the roof was extension relocated to western facade through boundary wall

PR site plan

PROJECT	STATUS	DRAWING	REV	DRAWN
786	3	11	A	
SCALE	1:500	SIZE	A3 L	DATE
				Oct. 2025

ARTEL ³¹
architects that build
artel31.co.uk · 01249 445656 · 5 Union Road SN15 1HW

THIS DRAWING IS COPYRIGHT © OF ARTEL LIMITED
REPRODUCTION IS ONLY TO TAKE PLACE WITH PRIOR WRITTEN AUTHORITY
ALL DIMENSIONS TO BE CONFIRMED ON SITE BEFORE ANY WORK COMMENCES
ANY DISCREPANCIES FOUND IN DRAWINGS OR OTHER DOCUMENTS MUST
BE BROUGHT TO THE ATTENTION OF THE ARCHITECT BEFORE PROCEEDING

blue edged hatched area
indicates area of existing timber
floor to be removed and
replaced with flagstones as
outlined in accompanying
construction method statement

786 The Bell House

Planning
OneTwoEight Co.
The Bell House
47 High St
Sutton Denier
Clipperton
SN15 4BH

■ 1st floor
 ■ 2nd floor
 ■ 3rd floor
 ■ 4th floor
 ■ 5th floor
 ■ 6th floor
 ■ 7th floor
 ■ 8th floor
 ■ 9th floor
 ■ 10th floor
 ■ 11th floor
 ■ 12th floor
 ■ 13th floor
 ■ 14th floor
 ■ 15th floor
 ■ 16th floor
 ■ 17th floor
 ■ 18th floor
 ■ 19th floor
 ■ 20th floor
 ■ 21st floor
 ■ 22nd floor
 ■ 23rd floor
 ■ 24th floor
 ■ 25th floor
 ■ 26th floor
 ■ 27th floor
 ■ 28th floor
 ■ 29th floor
 ■ 30th floor
 ■ 31st floor
 ■ 32nd floor
 ■ 33rd floor
 ■ 34th floor
 ■ 35th floor
 ■ 36th floor
 ■ 37th floor
 ■ 38th floor
 ■ 39th floor
 ■ 40th floor
 ■ 41st floor
 ■ 42nd floor
 ■ 43rd floor
 ■ 44th floor
 ■ 45th floor
 ■ 46th floor
 ■ 47th floor
 ■ 48th floor
 ■ 49th floor
 ■ 50th floor
 ■ 51st floor
 ■ 52nd floor
 ■ 53rd floor
 ■ 54th floor
 ■ 55th floor
 ■ 56th floor
 ■ 57th floor
 ■ 58th floor
 ■ 59th floor
 ■ 60th floor
 ■ 61st floor
 ■ 62nd floor
 ■ 63rd floor
 ■ 64th floor
 ■ 65th floor
 ■ 66th floor
 ■ 67th floor
 ■ 68th floor
 ■ 69th floor
 ■ 70th floor
 ■ 71st floor
 ■ 72nd floor
 ■ 73rd floor
 ■ 74th floor
 ■ 75th floor
 ■ 76th floor
 ■ 77th floor
 ■ 78th floor
 ■ 79th floor
 ■ 80th floor
 ■ 81st floor
 ■ 82nd floor
 ■ 83rd floor
 ■ 84th floor
 ■ 85th floor
 ■ 86th floor
 ■ 87th floor
 ■ 88th floor
 ■ 89th floor
 ■ 90th floor
 ■ 91st floor
 ■ 92nd floor
 ■ 93rd floor
 ■ 94th floor
 ■ 95th floor
 ■ 96th floor
 ■ 97th floor
 ■ 98th floor
 ■ 99th floor
 ■ 100th floor

PR ground floor plan


786 5' 12" 6'

1:100 A1 L Oct 2025

ARTEL
architects that build
100% carbon neutral 100% local materials

786 The Bell House

Planning
 OneTwoEight Co.
 The Bell House
 47 High St
 Sutton Swaner
 Chiggeston
 DN15 4BH



PR elevations
 786 - 3 - 14 8 11
 1:100 • A1 L Oct 2025
ARTEL
 architects that build
 100% local materials • 100% local labour

Appendix C - Relevant legislation and planning policy

Legislation

Protected species

In England, all bats, dormice *Muscardinus avellanarius*, otters *Lutra lutra*, white-clawed crayfish *Austropotamobius pallipes* and great crested newts *Triturus cristatus* are legally protected under the Conservation of Habitats and Species (Amendment) (EU Exit) Regulations 2019.

A number of species are also listed under Annex II of the EC Habitats and Species Directive 1992 due to their rarity, including barbastelle *Barbastella barbastellus*, Bechstein's bat *Myotis bechsteinii*, greater horseshoe *Rhinolophus ferrumequinum*, lesser horseshoe *Rhinolophus hipposideros*, great crested newt, white-clawed crayfish and otter.

The above named species and adders *Vipera berus*, slow worms *Anguis fragilis*, grass snakes *Natrix natrix*, common lizards *Zootoca vivipara*, common frog *Rana temporaria*, palmate newt *Lissotriton helveticus*, smooth newt *Lissotriton vulgaris*, water voles *Arvicola amphibius* and several invertebrate species are also protected under Schedule 5 of the Wildlife and Countryside Act (WCA) 1981 (as amended).

Schedule 9 of the WCA 1981 includes non-native, invasive species including (but not limited to) Himalayan balsam *Impatiens glandulifera* and signal crayfish *Pacifastacus leniusculus*. Badgers *Meles meles* are legally protected under The Protection of Badgers Act (1992).

All birds, their nests and eggs are protected under Section 1 of The WCA 1981 (as amended) and it is thus an offence, to intentionally kill, injure or take any wild bird; intentionally take, and damage or destroy the nest of any wild bird while it is in use or being built.

Some wild bird species, such as barn owls *Tyto alba*, are afforded additional protection under Schedule 1 of the WCA 1981 (as amended). This legislation makes the disturbance of any wild bird included in Schedule 1 illegal while it is building a nest or is in, on or near a nest containing eggs or young; or disturbance of dependent young of such a bird.

Certain species are listed under Section 41 of the Natural Environment and Rural Communities (NERC) Act 2006 as species of 'principal importance' (JNCC, 2007) such as hedgehog *Erinaceus europaeus*, due to their national decline; under Section 40, Local Planning Authorities have a duty to conserve these species.

Protected habitats and sites

A number of sites designated for nature conservation are afforded legal protection due to being of international importance. The UK National Sites Network includes Special Protection Areas (SPAs) for birds and Special Areas of Conservation (SACs) for habitats; Ramsars, designated for important wetland habitats, do not form part of the National Sites Network but are protected in the same way.

Habitats listed under Annex I of the EC Habitats and Species Directive 1992 are included due to their rarity and importance to the maintenance of protected species populations. Examples include estuaries, northern Atlantic wet heaths with *Erica tetralix*, and blanket bogs.

Other nationally protected sites include Sites of Special Scientific Interest (SSSIs), National Nature Reserves (NNRs) Local Nature Reserves (LNRs) and Protected Road Verges which are designated under the WCA 1981 and strengthened by the NERC Act 2006.

Several habitats are listed under Section 41 of the NERC Act 2006 including certain hedgerows, arable field margins, grassland, fen, swamp, marine habitats, woodlands and rivers.

Biodiversity Net Gain (BNG) – The Environment Act 2021

Part 6 Schedule 14 of the Environment Act 2021 ‘Biodiversity Gain as Condition of Planning Permission’ mandates a minimum 10% measurable habitat net gain for all major and minor planning applications (with certain applications being exempt). Under Sch. 14, there is a legal requirement to deliver a minimum 10% measurable habitat net gain value post-development compared to the measured pre-development value of a site, as measured using the national Metric calculation tool issued by the Secretary of State.

This legislation was enacted into law on 12th February 2024 for major applications and 2nd April 2024 for minor applications. For all applications subject to mandatory BNG, a biodiversity gain condition must be discharged through submission of a Biodiversity Gain Plan to the relevant Local Planning Authority detailing how the development has met the minimum 10% net gain objective. Offsite habitats and significant onsite habitat enhancements are subject to a minimum of 30 years maintenance under the Act.

National and local planning policy

The National Planning Policy Framework (NPPF)

The National Planning Policy Framework (NPPF) (Department for Levelling Up, Housing & Communities, 2026) sets out the Government’s planning policies for England and how these should be applied. In the context of this report, Section 19 of NPPF is relevant and applicable, Section 19 states:

‘Planning policies and decisions should contribute to and enhance the natural environment by minimising impacts on and providing net gains for biodiversity, including by establishing coherent ecological networks that are more resilient to current and future pressures.’

New developments and projects are supported where plans promote the conservation, restoration and enhancement of priority habitats, ecological networks and the protection and recovery of priority species; and identify and pursue measurable net gains for biodiversity.

To ensure this application is compliant with Section 19 of NPPF, enhancements for biodiversity, such as the inclusion of bat roosting and/or bird nesting boxes, are required as part of the development.

Wiltshire Core Strategy

The Wiltshire Core Strategy (Wiltshire Council, 2015) was adopted in January 2015 and includes the following relevant policy:

Core Policy 50: Biodiversity and Geodiversity

Protection

Development proposals must demonstrate how they protect features of nature conservation and geological value as part of the design rationale. There is an expectation that such features shall be retained, buffered, and managed favourably in order to maintain their ecological value, connectivity and functionality in the long-term. Where it has been demonstrated that such features cannot be retained, removal or damage shall only be acceptable in circumstances where the anticipated ecological impacts have been mitigated as far as possible and appropriate compensatory measures can be secured to ensure no net loss of the local biodiversity resource, and secure the integrity of local ecological networks and provision of ecosystem services.

All development proposals shall incorporate appropriate measures to avoid and reduce disturbance of sensitive wildlife species and habitats throughout the lifetime of the development.

Any development potentially affecting a Natura 2000 site must provide avoidance measures in accordance with the strategic plans or guidance set out in paragraphs 6.75-6.77 [refer to full strategy for details] above where possible, otherwise bespoke measures must be provided to demonstrate that the proposals would have no adverse effect upon the Natura 2000 network. Any development that would have an adverse effect on the integrity of a European nature conservation site will not be in accordance with the Core Strategy.

Biodiversity enhancement

All development should seek opportunities to enhance biodiversity. Major development in particular must include measures to deliver biodiversity gains through opportunities to restore, enhance and create valuable habitats, ecological networks and ecosystem services. Such enhancement measures will contribute to the objectives and targets of the Biodiversity Action Plan (BAP) or River Basin/Catchment Management Plan, particularly through landscape scale projects, and be relevant to the local landscape character.

Local sites

Sustainable development will avoid direct and indirect impacts upon local sites through sensitive site location and layout, and by maintaining sufficient buffers and ecological connectivity with the wider environment. Damage or disturbance to local sites will generally be unacceptable, other than in exceptional circumstances where it has been demonstrated that such impacts:

- i. cannot reasonably be avoided*
- ii. are reduced as far as possible*

- iii. *are outweighed by other planning considerations in the public interest*
- iv. *where appropriate compensation measures can be secured through planning obligations or agreements.*

Development proposals affecting local sites must make a reasonable contribution to their favourable management in the long-term.

It is the applicant's/landowner's responsibility to ensure that the proposed development proceeds in full compliance with this report and/or any update version report thereafter, that works are undertaken lawfully, in compliance with national and local policy, and in accordance with all conditions of the obtained planning consent(s).

Appendix D: Photographs

Photos taken in 2022:



Photo 1: Western elevation of the hotel.



Photo 2: Front northern elevation of the hotel.



Photo 3: Rear southern elevation of the hotel.



Photo 4: Side eastern gable end at the southern end of the hotel.



Photo 5: Porch area on the eastern elevation of the hotel.



Photo 6: Porch area on the north of the eastern of the hotel.



Photo 7: West elevation of the rear extension



Photo 8: Chimney on the northern pitch ridgeline.



Photo 9: Wooden clad upper half of the hotel within the central courtyard and boarded up window.



Photo 10: Flat roof extension south of the northern roofs.



Photo 11: The upper half of the of the southernmost pitched and hipped roof in the north with concrete roof tiles.



Photo 12: Rear of the hotel on the west side.



Photo 13: Gaps at the verges at the gable ends of the hotel.



Photo 14: Gaps in the tiles at the verges of the gable ends on the western pitch.



Photo 15: The southern garden.



Photo 16: Hard standing and wall in the west of the southern garden.



Photo 17: Fruit trees in the east of the southern garden.



Photo 18: Large stand of ground elder dominant in the introduced shrub in the east of the southern garden.



Photo 19: Hard standing carpark in the north of the site.



Photo 20: Introduced shrub in the northwest of the eastern garden.



Photo 21: Modified grassland in the center of the eastern garden with ornamental planting borders.



Photo 22: Modified grassland and hard standing path north of the hotel.



Photo 23: Compost heap in the southwest of the eastern garden.



Photo 24: Water tank in 'Void 1' of the hotel.



Photo 25: Internal of 'Void 1'.



Photo 26: Butterfly wing feeding remains.




Photo 27: Internal of 'Void 2'.



Photo 28: Staining at the ridge beam in 'Void 2'.



Photo 29: Brown long-eared bat droppings in 'Void 2'.



Photo 30: Internal of 'Void 2'.



Photo 31: Area of the roof of 'Void 3' where the bitumen lining turns to no lining.



Photo 32: Area of no lining in 'Void 3'.



Photo 33: Butterfly wing feeding remains at the base of the chimney in 'Void 3'.



Photo 34: View of Void 4 which was inaccessible.

Photos taken in 2025:



Photo 35: Internal of void 1.



Photo 36: Internal of void 1.



Photo 37: Internal of void 2.



Photo 38: Internal of void 5.



Photo 39: Modified grassland to the south of the hotel.



Photo 40: Modified grassland and introduced shrub to the south of the hotel.



Photo 41: Modified grassland and introduced shrub to the south of the hotel.



Photo 42: South elevation of the hotel to be demolished.



Photo 43: Introduced shrub.



Photo 45: Compost heap to the southeast.



Photo 46: Modified grassland to the east of the hotel in the green area to be retained.



Photo 47: Introduced shrub in the green area to the east to be retained.



Photo 35: Cherry trees and modified grassland to the south of the hotel.



Photo 36: Front eastern elevation of the existing hotel.



Photo 37: Existing hotel building.



Photo 38: Car park at the north of the site.



Photo 39: Modified grassland and introduced shrub at the north of the hotel building.



Photo 40: Front elevation of the existing hotel building from the road.

Appendix E – Pre and post-development habitat maps & floral species lists


Baseline habitats plan



Species lists for habitats:

Common name	Latin name	DAFOR scale abundance
Modified grassland (g4-108):		
Bluebell sp.	<i>Hyacinthoides sp.</i>	Locally abundant to rare
Cleavers	<i>Galium aparine</i>	Occasional
Clover sp.	<i>Trifolium sp.</i>	Abundant
Cock's-foot	<i>Dactylis glomerata</i>	Frequent
Common bird's-foot-trefoil	<i>Lotus corniculatus</i>	Locally occasional
Common cat's-ear	<i>Hypochaeris radicata</i>	Occasional
Common ragwort	<i>Jacobaea vulgaris</i>	Rare
Creeping buttercup	<i>Ranunculus repens</i>	Occasional
Daisy	<i>Bellis perennis</i>	Occasional
Dandelion sp.	<i>Taraxacum sp.</i>	Occasional
Dove's-foot crane's-bill	<i>Geranium molle</i>	Locally frequent
Field speedwell	<i>Veronica persica</i>	Locally frequent
Field wood-rush	<i>Luzula campestris</i>	Occasional
Greater plantain	<i>Plantago major</i>	Occasional
Green alkanet	<i>Pentaglottis sempervirens</i>	Locally occasional
Ground elder	<i>Aegopodium podagraria</i>	Locally abundant
Lesser celandine	<i>Ficaria verna</i>	Locally occasional
Lords-and-ladies	<i>Arum maculatum</i>	Locally occasional to rare
Perennial rye-grass	<i>Lolium perenne</i>	Dominant
Red dead-nettle	<i>Lamium purpureum</i>	Locally abundant
Red fescue	<i>Festuca rubra</i>	Occasional
Ribwort plantain	<i>Plantago lanceolata</i>	Occasional
Self-heal	<i>Prunella vulgaris</i>	Locally frequent to rare
Springy turf-moss	<i>Rhytidiadelphus squarrosus</i>	Locally abundant to occasional
White dead-nettle	<i>Lamium album</i>	Rare
Yarrow	<i>Achillea millefolium</i>	Occasional
Bramble scrub (h3d):		
Bramble	<i>Rubus fruticosus</i>	Dominant
Introduced shrub (u1-847):		
Bluebell ornamental sp.	<i>Hyacinthoides sp.</i>	Locally abundant
Buddleia	<i>Buddleja spp.</i>	Rare
Chives	<i>Allium schoenoprasum</i>	Rare
Cow parsley	<i>Anthriscus sylvestris</i>	Locally abundant
Daffodil sp.	<i>Narcissus sp.</i>	Locally abundant
Ground elder	<i>Aegopodium podagraria</i>	Locally dominant
Ground-ivy	<i>Glechoma hederacea</i>	Locally occasional
Ivy	<i>Hedera helix</i>	Locally occasional
Lords-and-ladies	<i>Arum maculatum</i>	Rare
Stinking iris	<i>Iris foetidissima</i>	Rare
Individual trees (u1-32):		
Apple	<i>Malus sp.</i>	Locally occasional
Cherry laurel	<i>Prunus laurocerasus</i>	Locally frequent
Corsican pine	<i>Pinus nigra laricio</i>	Rare
European lime	<i>Tilia x europaea</i>	Occasional
Goat willow	<i>Salix caprea</i>	Rare
Golden king holly	<i>Ilex x altaclarensis</i>	Rare
Laurel sp.	<i>Laurus sp.</i>	Rare
Lawson cypress	<i>Chamaecyparis lawsoniana</i>	Frequent
Scot's pine	<i>Pinus sylvestris</i>	Occasional

Appendix F – Bat evidence map



Key



Internal chimney



Loft hatch



Water tank



Inaccessible loft voids



Staining at ridge beam



Single brown long-eared bat dropping



Scattering of approximately 20 brown long-eared bat droppings below the ridge beam.



Four butterfly wing feeding remains.



Five butterfly wing feeding remains

Appendix G: Bat activity (dusk) survey results

Table 18: Bat activity (dusk) survey results

Bat activity (dusk) survey						
Date: 25/05/2023	Sunset: 21:07	Weather conditions: Mild and dry	Precipitation: None	Site location: Bell House Hotel, Sutton Benger		
Temp: Start: 15°C End: 14°C	Beaufort wind force (Bft): 0/12	Detectors used: EchoMeter Touch 2 + tablets x 4		Oktas cloud cover: 0/8	Start Time: 20:53	End Time: 22:45
Surveyor:		Surveyor position:		NVA used? (Y/N):	NVA equipment used:	
Russell Hoyle ACIEEM		Southeast		N	n/a	
Aaron Templar		Northeast		N	n/a	
Chris Payne		North		N	n/a	
Lewis Collins		Southwest		N	n/a	
Time	Sp. if ID'd	Number of bats		Comments on behaviour/activity		
21:22	Soprano pipistrelle	1		Heard not seen in the southeast and southwest.		
21:23 to 22:26	Serotine	1		Heard not seen in the northeast.		
21:20	Noctule	1		Faint call heard not seen in the southwest.		
21:24	Noctule	1		Heard not seen in the southeast.		
21:33	Soprano pipistrelle	1		Brief call heard not seen in the southwest.		
21:37 to 22:09	Common pipistrelle	1		Frequently foraged up and down the alleyway to the west of the property, travelling from north to south and north again.		
21:39	Common pipistrelle	1		Emerged from beneath the wooden fascia of the eaves at the western end of the southern extension and commuted eastwards (red circle).		
21:40	Noctule	1		Heard not seen in the southwest.		
21:43 to 22:45	Serotine	1		Commuted from the west to the east and foraged in the southeast infrequently until the end of the survey.		
21:44	Soprano pipistrelle	1		Heard not seen in the north.		
21:45	Serotine	1		Commuted from the west to the east over the alleyway to the west of the property.		
21:46	Serotine	1		Commuted from the southeast to the northeast.		
21:50	Serotine	1		Commuted from the southwest to the north.		
21:53	Soprano pipistrelle	1		Heard not seen in the southeast.		
21:55	Noctule	1		Heard not seen in the southwest.		
22:00 to 22:45	Soprano pipistrelle	1		Foraged in the north until the end of the survey.		
22:05	Serotine	1		Heard not seen in the southwest.		
22:08	Serotine	1		Commuted from the northeast to the west.		
22:08	Serotine	2		Commuted from the east to the west over the alleyway in the east of the property.		
22:08	Soprano pipistrelle	1		Heard not seen in the southwest.		
22:10	Myotis sp.	1		Heard not seen in the southeast.		

22:12	Soprano pipistrelle	1	Heard not seen in the northeast.
22:22	Soprano pipistrelle	1	Heard not seen in the southeast.
22:23	Common pipistrelle	1	Heard not seen in the southwest.
22:27	Noctule	1	Heard not seen in the northeast.

Figure 1: Location of common pipistrelle emergence.



Table 19: Bat activity (dusk) survey results

Bat activity (dusk) survey						
Date: 12/06/2023	Sunset: 21:25	Weather conditions: Mild and dry	Precipitation: None	Site location: Bell House Hotel, Sutton Benger		
Temp: Start: 19°C End: 19°C	Beaufort wind force (Bft): 0/12	Detectors used: EchoMeter Touch 2 + tablets x 4		Oktas cloud cover: 2/8	Start Time: 21:05	End Time: 23:00
Surveyor:		Surveyor position:		NVA used? (Y/N):	NVA equipment used:	
Laurence Wills		East		Y	Sony AX33 with two 15 LED IR floodlights	
Chris Payne		North		N	n/a	
Caitlin McQuillan		West		N	n/a	
Georgia Linter		South		N	n/a	
Time	Sp. if ID'd	Number of bats		Comments on behaviour/activity		
21:53	Common pipistrelle	1		Heard not seen in the east.		
21:55	Soprano pipistrelle	1		Heard not seen in the north.		
21:56	Serotine	1		Commutated from the west to the east over the southern garden.		
21:59	Soprano pipistrelle	1		Commutated from the north to the east in the north.		
21:59	Serotine	1		Commutated around the trees to the east.		
21:59	Serotine	1		Commutated from the west to the east over the southern garden.		

22:07	Common pipistrelle	1	Foraged in the southern garden.
22:11	Serotine	1	Heard not seen in the north.
22:17	Serotine	1	Heard not seen in the east.
22:19	Soprano pipistrelle	1	Heard not seen in the north.
22:21	Serotine	1	Heard not seen in the east, south and in the north.
22:22	Soprano pipistrelle	1	Heard not seen in the east.
22:30	Serotine	1	Heard not seen in the east.
22:31	Common pipistrelle	1	Heard not seen in the west.
22:39	Soprano pipistrelle	1	Heard not seen in the north.
22:44	Common pipistrelle	1	Heard not seen in the north.
22:45	Myotis sp.	1	Heard not seen in the south.
22:51	Soprano pipistrelle	1	Heard not seen in the south.

Figure 4: Screenshot of the darkest point recorded during survey for NVA Sony AX33



Table 20: Bat activity (dusk) survey results

Bat activity (dusk) survey						
Date: 27/06/2023	Sunset: 04:53	Weather conditions: Mild and dry	Precipitation: None	Site location: Bell House Hotel, Sutton Benger		
Temp: Start: 12°C End: 12°C	Beaufort wind force (Bft): 0/12	Detectors used: EchoMeter Touch 2 + tablets x 4		Oktas cloud cover: 8/8	Start Time: 03:23	End Time: 05:08
Surveyor:		Surveyor position:		NVA used? (Y/N):	NVA equipment used:	
Zoe Barrett		North		N	n/a	
Aaron Templar		East		N	n/a	
Kieran Mullany		Southwest		N	n/a	
Emily Parsons		South		N	n/a	
Time	Sp. if ID'd	Number of bats		Comments on behaviour/activity		
03:21	Soprano pipistrelle	1		Heard but not seen in the north.		

03:23	Soprano pipistrelle	1	Foraging around the graveyard across the road, to the south of the site.
03:24-03:41	Soprano pipistrelle	1	Heard but not seen in the east.
03:24-04:06	Common pipistrelle	1	Heard but not seen in the southwest and the south.
03:31	Soprano pipistrelle	1	Commuted from northeast to southwest across the site.
03:39	Soprano pipistrelle	1	Heard but not seen in the north.
03:41	Long-eared bat sp.	1	Heard but not seen in the east.
03:41-03:44	Noctule	1	Heard but not seen in the north and the east.
03:45-04:05	Noctule	1	Heard but not seen in the south and the north.
03:43	Serotine	1	Commuted from southwest to east across the site.
03:59-04:08	Common pipistrelle	1	Foraging in the south of the site.
04:03	Soprano pipistrelle	1	Commuted from west to southeast across the site.
04:04	Noctule	1	Commuted from northeast to east over the trees to the east of the site.
04:07	Serotine	1	Commuted from east to west across the graveyard to the south of the site.
04:11-04:35	Noctule	1	Heard but not seen in the north and the south.
04:19	Soprano pipistrelle	1	Heard but not seen in the north.
04:28	Common pipistrelle	1	Heard but not seen in the east.
04:29	Noctule	1	Commuted from south to north across the site.
04:34	Noctule	1	Commuted from south to north across the site.

Appendix H: Locations of bat roosts, bat exit/entry points & surveyor locations



*Maximum count of one bat exiting from/entering access point during any one survey

Figure 1


LEGEND:	
Key:	Description:
	Surveyor position
	Building subject to dusk surveys
Bat roosts and bat access point location:	
	Brown long-eared day roost within internal building area to remain unaffected by proposed works
	Common pipistrelle access point & day roost to remain unaffected by proposed works



Appendix I – Biodiversity mitigation, compensation and enhancement plan

Key:

-  Two 'PRO UK Rendered Build-In Swift Box' units will be installed within the existing building during construction. The boxes must be positioned as close to the eaves as possible.
 -  One 'Vivara Pro Build-in WoodStone Bat Box' unit will be installed within the existing building during construction as close to the eaves as possible.
- (Examples of designs overleaf).



Vivara Pro Build-in WoodStone Bat Box:



PRO UK Rendered Build-In Swift Box:



Bee pot hotel:



Hedgehog fence access:

